


NEVADA ENVIRONMENTAL RESPONSE TRUST WEIR DEWATERING TREATMENT PLANT

1489 WEST WARM SPRINGS ROAD, STE. 110
HENDERSON, NEVADA, 89014
PHONE: 702.946.6700 FAX: 702.997.7140



TETRA TECH

www.tetrattech.com



SITE PLAN

ENGINEER OF RECORD
MICHAEL SCHMIDT, PE
TETRA TECH
2110 POWERS FERRY ROAD SE, SUITE 202
ATLANTA, GA 30339
TEL: 770.738.6059
FAX: 770-850-0950
MICHAEL.SCHMIDT@TETRATECH.COM

Bar Measures 1 inch

PROJECT LOCATION:

510 SOUTH FOURTH STREET
HENDERSON, NEVADA 89015

CLIENT INFORMATION:

NEVADA ENVIRONMENTAL
RESPONSE TRUST

Tt PROJECT No.:

200-01299-16015

CLIENT PROJECT No.:

PROJECT DESCRIPTION / NOTES:

WEIR DEWATERING TREATMENT: GENERAL CONTRACTOR PACKAGE

ISSUED:

02-15-2017 - 75% SUBMITTAL TO BOR

VICINITY MAP:



NOT TO SCALE

2/15/2017 1:47:47 PM - P:\NER\01299\200-01299-1601\CAD\SHHEFILES\G-002 INDEX OF DRAWINGS.DWG - GULMIRE, CALEB

Discipline	Sheet Number	Sheet Title
General	G-001	Cover Sheet
General	G-002	Drawing Index
General	G-003	General Notes
General	G-004	Site Access
Civil	C-001	Symbols and Abbreviations
Civil	C-100	Existing Conditions Plan
Civil	C-101	Key Plan
Civil	C-102	Overall Site Plan
Civil	C-200	Not used
Civil	C-201	Not used
Civil	C-202	Not used
Civil	C-20X	Not used
Civil	C-301-1	Effluent Line Plan and Profile
Civil	C-301-2	Historic Lateral Weir Influent Pipeline Plan and Profile
Civil	C-301-3	Historic Lateral Weir Influent Pipeline Plan and Profile
Civil	C-301-4	Historic Lateral Weir Influent Pipeline Plan and Profile
Civil	C-303	Historic Lateral Pump Station Site Plan
Civil	C-304	Historic Lateral Pump Station Site Grading Plan
Civil	C-306	Historic Lateral Pump Station Section
Civil	C-401	Sunrise Mountain PS and Central WTP Site Plan
Civil	C-402	Sunrise Mountain PS and Central WTP Site Grading Plan
Civil	C-405	Sunrise Mountain PS and Central WTP Section
Civil	C-901	Details
Civil	C-902	Details
Civil	C-903	Civil Details
Civil	C-904	Civil Details
Structural	S-001	Structural Concrete Notes
Structural	S-002	Structural Concrete Details
Structural	S-201	Sunrise Mountain Pump Station Foundation Plan
Structural	S-301	Historic Lateral Pump Station Foundation Plan
Structural	S-302	Historic Lateral Pump Station Foundation Sections
Structural	S-401	Central Water Treatment Plant Foundation Plan
Structural	S-402	Foundation Sections
Structural	S-403	Central Water Treatment Plant Foundation Details
Process	D-001	Process Legend, Abbreviations and General Notes
Process	D-101	Process Flow Diagram
Process	D-102	Equipment, Piping and Valve Schedule
Process	D-103	Equipment, Piping and Valve Schedule
Process	D-201	Sunrise Mountain Pump Station Equipment and Piping Plan
Process	D-202	Sunrise Mountain Pump Station Equipment and Piping Sections
Process	D-301	Historic Lateral Pump Station Equipment and Piping Plan
Process	D-302	Historic Lateral Pump Station Equipment and Piping Sections
Process	D-401	Central Water Treatment Plant Equipment Plan
Process	D-402	Central Water Treatment Plant Piping Layout
Process	D-501	Cyclone System Equipment and Piping Plan
Process	D-502	Cyclone System Equipment and Piping Sections
Process	D-601	Multi-Media Filter System Equipment and Piping Plan
Process	D-602	Multi-Media Filter System Equipment and Piping Sections
Process	D-701	Ion Exchange System Equipment and Piping Plan
Process	D-702	Ion Exchange System Equipment and Piping Sections
Process	D-801	Waste, Backwash and Treated Water System Equipment and Piping Plan
Process	D-802	Treated Water Pumping systems Plan
Process	D-803	Waste, Backwash and Treated Water System Equipment and Piping Plan
Process	D-804	Waste, Backwash and Treated Water System Sections
Process	D-805	Waste, Backwash and Treated Water System Sections
Electrical	E-001	Electrical Legend
Electrical	E-200	Sunrise Mountain PS and Central WTP Site Plan
Electrical	E-201	Sunrise Mountain Pump Station Tanks Electrical Plan
Electrical	E-202	Sunrise Mountain Pump Station Pumps Electrical Plan
Electrical	E-210	Sunrise Mountain Pump Station Grounding Plan
Electrical	E-220	Central Water Treatment Plant Site Lighting Plan
Electrical	E-301	Historic Lateral Pump Station Electrical Site Plan
Electrical	E-310	Historic Lateral Pump Station Grounding Plan
Electrical	E-410	Central Water Treatment Plant Site Grounding Plan
Electrical	E-411	Central Water Treatment Plant Site Grounding Plan
Electrical	E-501	Hydrocyclones Electrical Plan
Electrical	E-601	Multi-Media Filters Electrical Plan
Electrical	E-701	Ion Exchange Electrical Plan
Electrical	E-801	Waste Water Tanks Electrical Plan
Electrical	E-802	Backwash and Waste Pumps Electrical Plan
Electrical	E-803	Central Water Treatment Plant Pumps Electrical Plan
Electrical	E-804	Treated Water Tanks Electrical Plan
Electrical	E-1401	Historic Lateral Single Line Diagram
Electrical	E-1402	Central Water Treatment Plant Single Line Diagram
Electrical	E-1403	Panel Board Schedules
Electrical	E-1501	Electrical Details
Electrical	E-1502	Electrical Details
Electrical	E-503	Electrical Details
Instrumentation	I-001	Instrumentation Notes/Legend
Instrumentation	I-002	Process Interlock Matrix
Instrumentation	I-003	System Architecture
Instrumentation	I-201	Sunrise Mountain Pump Station Feed P&ID
Instrumentation	I-202	Sunrise Mountain Pump Station Influent Tanks and Pumps P&ID
Instrumentation	I-301	Historic Lateral Pump Station Feed P&ID
Instrumentation	I-302	Historic Lateral Pump Station Influent Tanks and Pumps P&ID
Instrumentation	I-401	Central Water Treatment Plant Feed P&ID
Instrumentation	I-501	Cyclone HC-1 P&ID
Instrumentation	I-502	Cyclone HC-2 P&ID
Instrumentation	I-601	Multi-Media Filters MMF-1A/1B P&ID
Instrumentation	I-602	Multi-Media Filters MMF-1C/1D P&ID
Instrumentation	I-603	Multi-Media Filters MMF-1E/1F P&ID
Instrumentation	I-604	Multi-Media Filters Air Scour Blower P&ID
Instrumentation	I-701	Ion Exchange IX-1A/2A P&ID
Instrumentation	I-702	Ion Exchange IX-1B/2B P&ID
Instrumentation	I-703	Ion Exchange IX-1C/2C P&ID
Instrumentation	I-801	Treated Water Tanks and Pumps P&ID
Instrumentation	I-802	Cyclone Waste Tank P&ID
Instrumentation	I-803	Backwash Waste Tank P&ID
Instrumentation	I-804	Cyclone and Backwash Waste Pumps P&ID
Instrumentation	I-805	Filter Rinse/Backwash Pumps P&ID
Instrumentation	I-806	Filter Rinse Water Transfer Pumps P&ID
Instrumentation	I-900	MCP-100 Panel Layout
Instrumentation	I-901	MCP-100 Bill of Materials
Instrumentation	I-902	MCP-100 Panel Wire Diagram
Instrumentation	I-920	RCP-300 Panel Layout
Instrumentation	I-921	RCP-300 Bill of Materials
Instrumentation	I-922	RCP-300 Panel Wire Diagram



www.tetratech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.987.7140

MARK	DATE	DESCRIPTION	BY
A	11/29/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	CG

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
WEIR DEWATERING TREATMENT
INDEX OF DRAWINGS

Project No.: 200-01299-16015
Designed By: J. GUO
Drawn By: S. ULREY
Checked By: C. FLORES

G-002

Copyright: Tetra Tech

GENERAL NOTES

GENERAL:

- ALL LABOR, MATERIALS, AND METHODS OF CONSTRUCTION SHALL BE IN STRICT ACCORDANCE WITH THE MINIMUM ENGINEERING AND CONSTRUCTION STANDARDS ADOPTED BY CLARK COUNTY, LATEST EDITION. WHERE CONFLICTS OR OMISSIONS EXIST, THE CLARK COUNTY STANDARDS SHALL DICTATE. SUBSTITUTIONS AND DEVIATION FROM PLANS AND SPECIFICATIONS SHALL BE PERMITTED ONLY WHEN WRITTEN APPROVAL HAS BEEN ISSUED BY THE ENGINEER.
- SHOP DRAWINGS OF ALL MATERIALS BEING USED SHALL BE SUBMITTED FOR APPROVAL PRIOR TO INSTALLATION.
- ALL MATERIALS AND CONSTRUCTION TO BE IN ACCORDANCE WITH THE CLARK COUNTY CONSTRUCTION SPECIFICATIONS, LATEST EDITION, UNLESS OTHERWISE WAIVED.
- GENERAL CONTRACTOR SHALL OBTAIN ALL REQUIRED PERMITS IN HAND BEFORE BEGINNING ANY CONSTRUCTION.
- THE LOCATION OF UTILITIES SHOWN ON THE DRAWINGS HAVE BEEN DETERMINED FROM UTILITY LOCATES AND RECORD DRAWINGS. THERE MAY BE OTHER UTILITIES NOT SHOWN ON THE DRAWINGS WHICH PRESENTLY EXIST IN THE AREA OF CONSTRUCTION.
- LOCATE, VERIFY AND MAINTAIN CONTROL POINTS SHOWN ON THE DRAWINGS AND ESTABLISH TEMPORARY CONTROL POINTS AS NEEDED. THE CONSTRUCTION MANAGER (CM) SHALL RESTORE SURVEY MONUMENTS THAT ARE DAMAGED OR DESTROYED DURING CONSTRUCTION.
- MAINTAIN A CURRENT SET OF CONSTRUCTION PLANS AND ALL PERMITS ON THE JOB SITE DURING ALL PHASES OF CONSTRUCTION. PROVIDE TOTAL (2) SETS OF RECORD DRAWINGS WITHIN TWO (2) WEEKS AFTER COMPLETION OF THIS PROJECT.
- BASE MAPPING COORDINATE SYSTEM AND CONTROL POINTS PROVIDED BY ATKINS ENGINEERING.
- ALL EXCESS FILL FROM SITE SHALL BE STOCKPILED WHERE SHOWN ON THE DRAWINGS.
- CLEAR AREAS INDICATED SHALL BE COMPLETELY CLEAR OF ALL TIMBER, RUBBISH, AND ALL OTHER DEBRIS AND OBSTRUCTIONS RESTING ON OR PROTRUDING THROUGH THE SURFACE OF THE GROUND.
- PROVIDE THROUGH ACCESS TO EXISTING BUILDINGS AND FACILITIES THROUGHOUT CONSTRUCTION.
- CONDUCT SITE GRADING PROCEDURES IN A MANNER TO MINIMIZE DAMAGE TO EXISTING BUILDINGS AND FACILITIES, AS APPLICABLE.
- VERIFY LOCATION AND GRADE OF ALL CONNECTIONS TO NEW AND EXISTING PIPING AND UTILITIES PRIOR TO BEGINNING WORK.
- IF FIELD CONDITIONS ARE FOUND TO BE DIFFERENT THAN SHOWN ON THE DRAWINGS, PROVIDE IMMEDIATE NOTIFICATION SO THAT APPROPRIATE ACTION CAN BE TAKEN.
- NOTIFY UTILITY COMPANIES WHICH MAY HAVE THEIR UTILITIES WITHIN THE CONSTRUCTION AREAS TO LOCATE THEIR FACILITIES IN THE FIELD FORTY-EIGHT (48) HOURS PRIOR TO BEGINNING CONSTRUCTION.

DEMOLITION:

- OBTAIN NECESSARY PERMITS AND LICENSES FOR PERFORMING THE DEMOLITION WORK, AS APPLICABLE.
- NOTIFY ALL UTILITY COMPANIES OR LOCAL AUTHORITIES FURNISHING GAS, WATER, ELECTRICAL, TELEPHONE, OR SEWER SERVICE SO THEY CAN REMOVE, RELOCATE, DISCONNECT, CAP OR PLUG THEIR EQUIPMENT IN ORDER TO FACILITATE DEMOLITION.
- WHERE REQUIRED, PROTECT ALL UTILITIES AND OTHER IMPROVEMENTS SHOWN ON THESE PLANS AND UTILITIES AND OTHER IMPROVEMENTS NOT SHOWN.
- WHERE REQUIRED, PROTECT ALL WALLS, STRUCTURES, AND UTILITIES NOT MARKED FOR REMOVAL OR DEMOLITION AND PROMPTLY REPAIR ANY DAMAGE.
- REMOVE UNSALVAGEABLE MATERIALS AND YARD WASTE FROM THE SITE IMMEDIATELY AND DISPOSE OF IN ACCORDANCE WITH APPLICABLE FEDERAL, STATE, AND LOCAL REGULATIONS.

EARTHWORK, GRADING, STABILIZATION, PAVING AND DRAINAGE:

- REFER TO THE FINAL COUNTY APPROVED GEOTECHNICAL DOCUMENTATION FOR ALL RECOMMENDATIONS ON EARTHWORK, BACKFILL, COMPACTION, GRADING AND SUBGRADE PREPARATION.
- STABILIZED SUBGRADE SHALL BE PER GEOTECHNICAL REPORT, REPORT OF GEOTECHNICAL INVESTIGATION, WEIR DEWATERING TREATMENT, CENTRAL WATER TREATMENT PLANT, NEVADA ENVIRONMENTAL RESPONSE TRUST, HENDERSON, NEVADA, TETRA TECH, DATED FEBRUARY 14, 2017, AND REPORT OF GEOTECHNICAL INVESTIGATION, WEIR DEWATERING TREATMENT, PUMP STATIONS, NEVADA ENVIRONMENTAL RESPONSE TRUST, HENDERSON, NEVADA, TETRA TECH, DATED FEBRUARY 14, 2017.
- ALL ORGANIC SOILS BELOW UTILITY TRENCHES SHALL BE REMOVED AND REPLACED WITH SUITABLE MATERIAL AND COMPACTED.
- ALL EARTHFILL SHALL HAVE MAXIMUM LIFT THICKNESS OF 6 INCHES, MOISTURE CONDITIONED TO WITHIN \pm 2% OF OPTIMUM MOISTURE CONTENT AND SHALL BE COMPACTED TO THE MINIMUM DRY DENSITIES AS MEASURED BY ASTM D1557 AS INDICATED IN THE FINAL COUNTY APPROVED GEOTECHNICAL DOCUMENTATION.
- MOISTURE REQUIREMENTS SHALL BE MET USING THE FOLLOWING:
 - DRY SUBGRADE: ADD WATER, THEN MIX TO MAKE MOISTURE CONTENT UNIFORM THROUGHOUT.
 - WET SUBGRADE: AERATE MATERIAL BY BLADING, DICING, HARROWING, OR OTHER METHODS, TO HASTEN DRYING PROCESS.
- ALL PIPES SHALL HAVE 2 FEET MINIMUM COVER UNLESS OTHERWISE SPECIFIED IN PLANS, TAKING CARE TO PROVIDE PROPER GRADE ELEVATIONS AND ALIGNMENTS.
- CONDUCT IN-PLACE FIELD DENSITY TESTS FOR QUALITY ASSURANCE AREA USING ASTM D1557 NUCLEAR DENSOMETER METHOD. QUALITY ASSURANCE FIELD DENSITY TESTING FREQUENCY FOR EMBANKMENT IS ONE TEST PER 500 LINEAL FEET MINIMUM. FREQUENCY FOR LIFT FOR TANK FLOOR AND FOUNDATION BACKFILL IS AT LEAST ONE TEST PER 2,500 SQUARE FEET OF PLACEMENT.
- CONDUCT SITE GRADING PROCEDURES IN A MANNER TO MINIMIZE DAMAGE TO EXISTING BUILDINGS AND FACILITIES.
- GENERAL CONTRACTOR SHALL COMPLY WITH THE ADDITIONAL REQUIREMENTS FOR THE CLARK COUNTY GRADING PERMIT, INCLUDING:
 - PREPARATION OF A FINAL REPORT, INCLUDING ALL TESTING RESULTS AND THEIR COMPLIANCE WITH THE APPROVED PROJECT DRAWINGS AND SPECIFICATIONS. THIS REPORT SHALL BE SUBMITTED TO CLARK COUNTY FOR APPROVAL.
 - THE QA TESTING FIRM SHALL REQUEST FROM THE COUNTY A FINAL INSPECTION OF THE PROJECT SITE TO CHECK FOR COMPLIANCE WITH THE APPROVED PROJECT DRAWINGS AND SPECIFICATIONS.
 - AFTER THE FINAL REPORT HAS BEEN APPROVED, THE QA TESTING FIRM SHALL ACCOMPANY THE COUNTY DURING FINAL INSPECTION.
- AFTER OTHER EARTHWORK HAS BEEN FINISHED, AND FILLING AND BACKFILLING OPERATIONS ARE COMPLETED, ALL AREAS ON THE SITE SHALL BE BROUGHT TO GRADE WITHIN A TOLERANCE OF \pm 0.1 FEET AT THE INDICATED ELEVATIONS, SLOPES AND CONTOURS.

EROSION CONTROL NOTES:

- TEMPORARY STABILIZATION IS REQUIRED OF ALL SOIL LEFT BARE FOR GREATER THAN 14 DAYS.
- MAINTAIN TRACKING CONTROL DEVICES. REMOVE ALL SEDIMENT, MUD, CONSTRUCTION DEBRIS, OR OTHER POTENTIAL POLLUTANTS THAT MAY HAVE BEEN DISCHARGED TO, OR ACCUMULATED IN, THE PUBLIC RIGHTS OF WAY AS A RESULT OF CONSTRUCTION ACTIVITIES ASSOCIATED WITH THIS SITE DEVELOPMENT OR CONSTRUCTION PROJECT EACH DAY. SUCH MATERIALS SHALL BE PREVENTED FROM ENTERING THE STORM SEWER SYSTEM.
- ADDITIONAL CONSTRUCTION SITE DISCHARGE BEST MANAGEMENT PRACTICES MAY BE REQUIRED DUE TO UNFORESEEN EROSION PROBLEMS OR IF THE SUBMITTED PLAN DOES NOT MEET THE CLARK COUNTY PERFORMANCE STANDARDS AND THE LAS VEGAS VALLEY CONSTRUCTION SITE BMP GUIDANCE MANUAL.
- TEMPORARY OR PERMANENT STABILIZATION PRACTICES WILL BE INSTALLED ON DISTURBED AREAS AS SOON AS PRACTICABLE AND NO LATER THAN 14 DAYS AFTER THE CONSTRUCTION ACTIVITY IN THAT PORTION OF THE SITE HAS TEMPORARILY OR PERMANENTLY CEASED. SOME EXCEPTIONS MAY APPLY: REFER TO THE NEVADA STORMWATER GENERAL PERMIT FOR CONSTRUCTION ACTIVITY NVR100000, SECTION III.A.5.
- INSPECT ALL DISTURBED AREAS, AREAS USED FOR STORAGE OF MATERIALS AND EQUIPMENT THAT ARE EXPOSED TO PRECIPITATION, VEHICLE ENTRANCE AND EXIT LOCATIONS AND ALL BMP'S IN ACCORDANCE WITH THE NERT AP-5 SOLIDS REMOVAL STORMWATER POLLUTION PREVENTION PLAN (SWPPP) AS REVIEWED AND ACCEPTED BY THE CLARK COUNTY DEPARTMENT OF BUILDING AND FIRE PREVENTION, OCTOBER 5, 2015. SOME EXCEPTIONS TO WEEKLY INSPECTIONS MAY APPLY, SUCH AS SUSPENSION OF LAND DISTURBANCE ACTIVITIES. REFER TO THE NEVADA STORM WATER GENERAL PERMIT FOR CONSTRUCTION ACTIVITY NVR100000, SECTION III.A.12.
- ACCUMULATED SEDIMENT IN BMP'S SHALL BE REMOVED WITHIN SEVEN DAYS AFTER A STORM WATER RUNOFF EVENT OR PRIOR TO THE NEXT ANTICIPATED STORM EVENT, WHICHEVER IS EARLIER. SEDIMENT MUST BE REMOVED WHEN BMP DESIGN CAPACITY HAS BEEN REDUCED BY 50 PERCENT OR MORE.
- GOOD HOUSEKEEPING: THE SITE SHOULD BE KEPT IN AN ORDERLY FASHION, THE CONSTRUCTION MANAGER (CM) SHALL INSURE THE FOLLOWING ITEMS ARE ADDRESSED.
 - AN EFFORT TO STORE ONLY WHAT IS NEEDED ON THE SITE.
 - KEEP ALL STORED MATERIALS IN A NEAT AND ORDERLY FASHION IN THE ORIGINAL CONTAINERS WHEN POSSIBLE.
 - FOLLOW ALL MANUFACTURERS RECOMMENDED PROCEDURES FOR DISPOSAL OF WASTE MATERIAL.
 - INSPECT DAILY TO INSURE WASTE MATERIAL IS DISPOSED OF PROPERLY.

SPILL CONTROL NOTES:

- IN ADDITION TO THE GOOD HOUSEKEEPING AND MATERIAL MANAGEMENT PRACTICES DISCUSSED IN THE PREVIOUS NOTES OF THIS PLAN, THE FOLLOWING PRACTICES WILL BE FOLLOWED FOR SPILL PREVENTION AND CLEANUP:
 - MANUFACTURERS' RECOMMENDED METHODS FOR SPILL CLEANUP WILL BE CLEARLY POSTED AND SITE PERSONNEL WILL BE MADE AWARE OF THE PROCEDURES AND THE LOCATION OF THE INFORMATION AND CLEANUP SUPPLIES.
 - ALL SPILLS WILL BE CLEANED UP IMMEDIATELY AFTER DISCOVERY.
 - SPILLS OF TOXIC OR HAZARDOUS MATERIAL WILL BE REPORTED TO THE APPROPRIATE STATE OR LOCAL GOVERNMENT AGENCY, REGARDLESS OF SIZE.
 - THE SPILL PREVENTION PLAN WILL BE ADJUSTED TO INCLUDE MEASURES TO PREVENT THIS TYPE OF SPILL FROM REOCCURRING AND HOW TO CLEAN UP THE SPILL IF THERE IS ANOTHER ONE. A DESCRIPTION OF THE SPILL, WHAT CAUSED IT, AND THE CLEANUP MEASURES WILL ALSO BE INCLUDED.
 - THE SITE SUPERINTENDENT RESPONSIBLE FOR THE DAY-TO-DAY SITE OPERATIONS WILL BE THE SPILL PREVENTION AND CLEANUP COORDINATOR.

STORMWATER COMPLIANCE NOTES:

- THE OWNER, SITE DEVELOPER, CONTRACTOR, AND/OR THEIR AUTHORIZED AGENTS SHALL EACH DAY REMOVE ALL SEDIMENT, MUD, CONSTRUCTION DEBRIS, OR OTHER POTENTIAL POLLUTANTS THAT MAY HAVE BEEN DISCHARGED TO, OR ACCUMULATED IN, THE PUBLIC RIGHTS OF WAY AS A RESULT OF CONSTRUCTION ACTIVITIES ASSOCIATED WITH THIS SITE DEVELOPMENT OR CONSTRUCTION PROJECT. SUCH MATERIALS SHALL BE PREVENTED FROM ENTERING THE STORM SEWER SYSTEM.
- ADDITIONAL CONSTRUCTION SITE DISCHARGE BEST MANAGEMENT PRACTICES MAY BE REQUIRED OF THE OWNER AND HIS OR HER AGENTS DUE TO UNFORESEEN EROSION PROBLEMS OR IF THE SUBMITTED PLAN DOES NOT MEET THE CLARK COUNTY PERFORMANCE STANDARDS AND THE LAS VEGAS VALLEY CONSTRUCTION SITE BMP GUIDANCE MANUAL.
- TEMPORARY OR PERMANENT STABILIZATION PRACTICES WILL BE INSTALLED ON DISTURBED AREAS AS SOON AS PRACTICABLE AND NO LATER THAN 14 DAYS AFTER THE CONSTRUCTION ACTIVITY IN THAT PORTION OF THE SITE HAS TEMPORARILY OR PERMANENTLY CEASED. SOME EXCEPTIONS MAY APPLY: REFER TO THE NEVADA STORMWATER GENERAL PERMIT FOR CONSTRUCTION ACTIVITY NVR100000, SECTION III.A.5. ALSO COMPLY WITH THE BOR AND CLARK COUNTY PARKS AND RECREATION.
- AT A MINIMUM, THE CONTRACTOR OR HIS AGENT SHALL INSPECT ALL DISTURBED AREAS, AREAS USED FOR STORAGE OF MATERIALS AND EQUIPMENT THAT ARE EXPOSED TO PRECIPITATION, VEHICLE ENTRANCE AND EXIT LOCATIONS, AND ALL BMP'S WEEKLY, AND WITHIN 24 HOURS AFTER ANY RAIN EVENT OF 0.5 INCHES OR MORE. THE CONTRACTOR OR HIS AGENT SHALL UPDATE OR MODIFY THE STORMWATER POLLUTION PREVENTION PLAN AS NECESSARY. SOME EXCEPTIONS TO WEEKLY INSPECTIONS MAY APPLY, SUCH AS SUSPENSION OF LAND DISTURBANCE ACTIVITIES. REFER TO THE NEVADA STORMWATER GENERAL PERMIT FOR CONSTRUCTION ACTIVITY NVR100000, SECTION III.A.12.
- ACCUMULATED SEDIMENT IN BMP'S SHALL BE REMOVED WITHIN SEVEN DAYS AFTER A STORMWATER RUNOFF EVENT OR PRIOR TO THE NEXT ANTICIPATED STORM EVENT, WHICHEVER IS EARLIER. SEDIMENT MUST BE REMOVED WHEN BMP DESIGN CAPACITY HAS BEEN REDUCED BY 50 PERCENT OR MORE.



www.tetratech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.997.7140

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	CG

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
WEIR DEWATERING TREATMENT
GENERAL NOTES

Project No.: 200-01299-16015
Designed By: J. GUO
Drawn By: S. ULREY
Checked By: C. FLORES


G-003


2/24/2017 1:32:33 PM - P:\NERR\01299\200-01299-160\15\CAD\SHSHEETFILES\G-004 - SITE ACCESS & EGRESS.DWG - GULMIRE, CALEB





EGRESS AND STAGING PLAN
SCALE: 1" = 200'

LEGEND:

CONSTRUCTION STAGING AND PARKING 

CONSTRUCTION ACCESS 





SCALE: 1" = 200'

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HR
C	02/15/17	75% SUBMITTAL TO BOR	CG

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA

WEIR DEWATERING TREATMENT

SITE ACCESS

Project No.: 200-01299-16015
Designed By: J. GUO
Drawn By: S. ULREY
Checked By: C. FLORES

G-004

 **TETRA TECH**

www.tetra.tech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.997.7140

Copyright Tetra Tech


2/15/2017 11:36:59 AM - P:\MER01299\200-01299-16015\CADD\SHEETFILES\C-100.DWG - GULMIRE, CALEB

F
E
D
C
B
A

1 2 3 4 5 6 7



EXISTING CONDITIONS PLAN
SCALE: 1" = 200'



MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	CG

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
**WEIR DEWATERING TREATMENT
EXISTING
CONDITIONS PLAN**

Project No.: 200-01299-16015
Designed By: J. GUO
Drawn By: S. ULREY
Checked By: C. FLORES

C-100



TETRA TECH
www.tetra.tech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.997.7140

Copyright Tetra Tech



2/21/2017 1:18:32 PM - O:\PROJECTS\ATLANTA\TAIER\01299\200-01299-16015\CAD\SHEETFILES\C-101.DWG - REYES, HECTOR



SITE AREA KEY		
AREA NO.	STRUCTURES	SHEET NUMBERS
NA	GENERAL	001-099
1	OVERALL SITEWORK	100-199
2	SUNRISE MOUNTAIN PUMP STATION	200-299
3	HISTORIC LATERAL PUMP STATION	300-399
4	CENTRAL WATER TREATMENT PLANT	400-499 (SEE INSET)

SITE AREA KEY		
AREA NO.	STRUCTURES	SHEET NUMBERS
5	CYCLONES	500-599
6	MULTI-MEDIA FILTERS	600-699
7	ION EXCHANGE	700-799
8	CENTRAL WATER TREATMENT PLANT WASTE, BACKWASH & EFFLUENT	800-899
NA	DETAILS	900-999

KEY PLAN
SCALE: 1" = 200'



CENTRAL WATER TREATMENT PLANT (INSET)
SCALE: N.T.S.



TETRA TECH
www.tetra.tech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.997.7140

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	CG


NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
WEIR DEWATERING TREATMENT
KEY PLAN

Project No.: 200-01299-16015
Designed By: J. GUO
Drawn By: S. ULREY
Checked By: C. FLORES

C-101

Copyright: Tetra Tech

2/23/2017 3:16:55 PM - \\TTS139FS1\GROUPS\CADD\NERT DEWATERING\WORKING - UPDATED 02/07/17\CIVIL DRAWINGS-PREF ROUTE-PLAN-PROFILES.DWG - LINTZ, ANDREW



LEGEND:
 ● B-7 PROPOSED BORING LOCATION

TETRA TECH
 www.tetra-tech.com
 1489 West Warm Springs Road, Suite 110
 Henderson, NV 89014
 Phone: 702.946.6700 Fax: 702.997.7140

MARK	DATE	DESCRIPTION
A	11/28/16	ISSUED FOR 60% SUBMITTAL
B	02/14/17	75% SUBMITTAL TO BOR


NEVADA ENVIRONMENTAL RESPONSE TRUST
 HENDERSON, NEVADA
 LAS VEGAS WASH WEIR DEWATERING
 WEIR DEWATERING PIPELINE

Project No.: 200-01299-16002
 Designed By: P. PATTON
 Drawn By: F. MENICHELLI
 Checked By: D. SHEA

C-102
 Sheet #


Copyright: Tetra Tech

2/23/2017 4:07:12 PM - \\TTS139FS1\GROUPS\CADD\NERT DEWATERING\WORKING - UPDATED 020717\CIVIL DRAWINGS-PREF ROUTE-PLAN-PROFILES.DWG - LINTZ, ANDREW



PLAN VIEW
SCALE: 1"=50'

- NOTES:**
1. AVOID AND PROTECT THE EXISTING UNDERGROUND GWETS 12" DIAMETER LINE. LOCATION, DEPTH, AND SIZE ARE APPROXIMATE, AND CONTRACTOR SHALL VERIFY THIS INFORMATION DURING CONSTRUCTION. IF CONFLICT EXISTS NOTIFY THE DESIGN ENGINEER.
 2. ESTIMATED TOPOGRAPHY BASED ON PUBLICLY AVAILABLE LIDAR DATA.



PROFILE:
SCALE: 1"= 50' HORIZ.
1"= 5' VERT


MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	DS
B	02/15/17	75% SUBMITTAL TO BOR	DS

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
LAS VEGAS WASH WEIR DEWATERING
WEIR DEWATERING PIPELINE
EFFLUENT LINE
PLAN AND PROFILE
SHEET 1 OF 5

Project No.: 200-01299-16002
Designed By: P. PATTON
Drawn By: F. MENICHELLI
Checked By: D. SHEA


Copyright: Tetra Tech

2/23/2017 4:33:09 PM - \\TTS139F51\GROUPS\CADD\NERT DEWATERING\WORKING - UPDATED 020717\CIVIL DRAWINGS-PREF ROUTE-PLAN-PROFILES.DWG - LINTZ, ANDREW



PLAN VIEW
SCALE: 1"=50'

- NOTES:**
1. AVOID AND PROTECT THE EXISTING UNDERGROUND GWETS 12" DIAMETER LINE. LOCATION, DEPTH, AND SIZE ARE APPROXIMATE, AND CONTRACTOR SHALL VERIFY THIS INFORMATION DURING CONSTRUCTION. IF CONFLICT EXISTS NOTIFY THE DESIGN ENGINEER.
 2. ESTIMATED TOPOGRAPHY BASED ON PUBLICLY AVAILABLE LIDAR DATA.



PROFILE:
SCALE: 1"= 50' HORIZ.
1"= 5' VERT

TETRA TECH
www.tetra-tech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.997.7140

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	DS
B	02/15/17	75% SUBMITTAL TO BOR	DS


NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
LAS VEGAS WASH WEIR DEWATERING
WEIR DEWATERING PIPELINE
**HISTORIC LATERAL WEIR
INFLUENT PIPELINE
PLAN AND PROFILE**

Project No.: 200-01299-16002
Designed By: P. PATTON
Drawn By: F. MENICHELLI
Checked By: D. SHEA

C-301-2
Sheet ##


Copyright: Tetra Tech

2/23/2017 4:37:55 PM - \\TTS139FS1\GROUPS\CADD\NERT DEWATERING\WORKING - UPDATED 020717\CIVIL DRAWINGS-PREF ROUTE-PLAN-PROFILES.DWG - LINTZ, ANDREW




PLAN VIEW
SCALE: 1"=50'

- NOTES:**
1. REMOVE AND REPLACE EXISTING ENTRANCE GATE AS NECESSARY FOR PIPE LINE INSTALLATION.
 2. ESTIMATED TOPOGRAPHY BASED ON PUBLICLY AVAILABLE LIDAR DATA.



PROFILE:
SCALE: 1"= 50' HORZ.
1"= 5' VERT



TETRA TECH
www.tetra.tech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.997.7140

MARK	DATE	DESCRIPTION	BY	DS
A	11/28/16	ISSUED FOR 60% SUBMITTAL	DS	DS
B	02/15/17	75% SUBMITTAL TO BOR	DS	DS

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
LAS VEGAS WASH WEIR DEWATERING
WEIR DEWATERING PIPELINE
**HISTORIC LATERAL WEIR
INFLUENT PIPELINE
PLAN AND PROFILE**

Project No.: 200-01299-16002
Designed By: P. PATTON
Drawn By: F. MENICHELLI
Checked By: D. SHEA

C-301-3
Sheet #

Copyright: Tetra Tech


2/23/2017 4:47:59 PM - \\TTS139FS1\GROUPS\CADD\NERT DEWATERING\WORKING - UPDATED 020717\CIVIL DRAWINGS-PREF ROUTE-PLAN-PROFILES.DWG - LINTZ, ANDREW



PLAN VIEW
SCALE: 1"=50'

NOTES:

1. THE DETAILED ALIGNMENT AND DESIGN FOR THE RAW WATER PIPELINE FROM THE HISTORIC LATERAL WEIR DEWATERING SITE IS CURRENTLY BEING PREPARED BY OTHERS (I.E. SOUTHERN NEVADA WATER AUTHORITY CONTRACTOR).
2. ESTIMATED TOPOGRAPHY BASED ON PUBLICLY AVAILABLE LIDAR DATA.
3. SITE RESTORATION DUE TO PIPELINE INSTALLATION WILL BE PERFORMED IN ACCORDANCE WITH BOR AND CLARK COUNTY PARKS AND RECREATION REQUIREMENTS.
4. TEMPORARILY REMOVE AND REPLACE EXISTING SURFACE IRRIGATION PIPING IF DISTURBED DURING PIPELINE INSTALLATION.



PROFILE:
SCALE: 1"= 50' HORZ.
1"= 5' VERT

TETRA TECH
www.tetra-tech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.997.7140

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	DS
B	02/15/17	75% SUBMITTAL TO BOR	DS


NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
LAS VEGAS WASH WEIR DEWATERING
WEIR DEWATERING PIPELINE
**HISTORIC LATERAL WEIR
INFLUENT PIPELINE
PLAN AND PROFILE**

Project No.: 200-01299-16002
Designed By: P. PATTON
Drawn By: F. MENICHELLI
Checked By: D. SHEA

C-301-4
Sheet #

Copyright: Tetra Tech

2/21/2017 1:45:28 PM - O:\PROJECTS\ATLANTA\TAIR01299\200-01299-16015\CAD\SHEETFILES\C-201.DWG - REYES, HECTOR



TETRA TECH
 www.tetra.tech.com
 1489 West Warm Springs Road, Suite 110
 Henderson, NV 89014
 Phone: 702.946.6700 Fax: 702.997.7140

MARK	DATE	DESCRIPTION	BY
A	11/29/16	ISSUED FOR 60% SUBMITTAL	HCR
B	02/15/17	75% SUBMITTAL TO BOR	

NEVADA ENVIRONMENTAL RESPONSE TRUST
 HENDERSON, NEVADA
 WEIR DEWATERING TREATMENT
 HISTORICAL LATERAL
 PUMP STATION
 SITE PLAN

Project No.: 200-01299-16015
 Designed By: C. FLORES
 Drawn By: H. REYES
 Checked By: C. FLORES

C-303

Copyright: Tetra Tech

2/15/2017 11:51:39 AM - P:\N\01299\200-01299-16015\CADD\SHEETFILES\C-402.DWG - GULMIRE, CALEB



MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	CG

NEVADA ENVIRONMENTAL RESPONSE TRUST
 HENDERSON, NEVADA

**WEIR DEWATERING TREATMENT
 HISTORICAL LATERAL
 PUMP STATION
 SITE GRADING PLAN**

Project No.: 200-01299-16015
 Designed By: C. FLORES
 Drawn By: H. REYES
 Checked By: C. FLORES


C-304

TETRA TECH


www.tetra-tech.com
 1489 West Warm Springs Road, Suite 110
 Henderson, NV 89014
 Phone: 702.946.6700 Fax: 702.987.7140

Copyright Tetra Tech

2/15/2017 1:05:02 PM - P:\NER\01299\200-01299-16015\CAD\SHEETFILES\C-206.DWG - GUILMIRE, CALEB



SECTION A
SCALE: 1" = 20'H 1" = 2'V



www.tetratech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.997.7140

MARK	DATE	DESCRIPTION	BY
A	11/29/16	ISSUED FOR 60% SUBMITTAL	HCR
B	2/15/17	75% SUBMITTAL TO BOR	CG


NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
**HISTORICAL LATERAL
PUMP STATION
SECTION**


Project No.: 200-01299-16015
Designed By: C. FLORES
Drawn By: H. REYES
Checked By: C. FLORES

C-306

Copyright Tetra Tech

2/20/2017 5:51:16 PM - P:\N\01299\200-01299-16015\CAD\SH\FILES\C-201.DWG - GULMIRE, CALEB



TETRA TECH

 www.tetra-tech.com
 1489 West Warm Springs Road, Suite 110
 Henderson, NV 89014
 Phone: 702.946.6700 Fax: 702.967.7140


MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	02/15/17	75% SUBMITTAL TO BOR	CG

NEVADA ENVIRONMENTAL RESPONSE TRUST
 HENDERSON, NEVADA
**SUNRISE MOUNTAIN PS
 AND CENTRAL WTP
 SITE PLAN**


Project No.: 200-01299-16015
 Designed By: C. FLORES
 Drawn By: H. REYES
 Checked By: C. FLORES

C-401
 Copyright: Tetra Tech

2/20/2017 5:47:27 PM - P:\NERR\01299\200-01299-16015\CAD\DWG\C-402.DWG - GULMIRE, CALEB



NOTES:
1. ALL SPOT ELEVATIONS ARE AT BOTTOM OF GRAVEL. REFER TO SHEET C-405 FOR SECTIONS.



EARTHWORK
CUT 2,087 CY
FILL 1,846 CY
NET 241 CY (CUT)
CUT FACTOR 1.1
FILL FACTOR 1.0

TETRA TECH
www.tetra-tech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.967.7140



MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	CG

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
**SUNRISE MOUNTAIN PS
AND CENTRAL WTP
SITE GRADING PLAN**

Project No.: 200-01299-16015
Designed By: C. FLORES
Drawn By: H. REYES
Checked By: C. FLORES

C-402
Copyright: Tetra Tech

2/20/2017 11:32:10 AM - P:\N\01299\200-01299-16015\CAD\SHEETFILES\C-206.DWG - GULMIRE, CALEB



www.tetra.tech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.987.7140

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	02/15/17	75% SUBMITTAL TO BOR	CG


NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
**WEIR DEWATERING TREATMENT
SUNRISE MOUNTAIN PS
AND CENTRAL WTP
SECTION**

Project No.: 200-01299-16015
Designed By: C. FLORES
Drawn By: H. REYES
Checked By: C. FLORES


C-405

Copyright Tetra Tech

2/15/2017 1:36:08 PM - P:\NER\01299\200-01299-16015\CAD\SHEETFILES\C-900.DWG - GULMIRE, CALEB



1 TYPICAL GEOMEMBRANE INSTALLATION
903 NOT TO SCALE



- ① EXCAVATE CONTINUOUS ANCHOR TRENCH ALONG TOP OF BERM FILL.
- ② INSTALL GEOMEMBRANE LINER PER MANUFACTURER'S RECOMMENDATIONS.
- ③ COMPACTED SOIL BACKFILL PER RECOMMENDATIONS IN GEOTECHNICAL REPORT.

2 ANCHORING OF GEOMEMBRANE AT TOP OF SLOPE
903 SCALE: 3/4"=1'-0"

TETRA TECH
www.tetratech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.997.7140

MARK	DATE	DESCRIPTION	BY
A	02/15/17	75% SUBMITTAL TO BOR	CG

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA


WEIR DEWATERING TREATMENT

CIVIL DETAILS


Project No.: 200-01299-16015
Designed By: J. GUO
Drawn By: C. GULMIRE
Checked By: C. FLORES

C-903

Copyright Tetra Tech




1 TYPICAL TRENCH SECTION
SCALE: NTS




2 HISTORIC LATERAL WEIR PIPELINE AND WTP EFFLUENT DISCHARGE PIPELINE CROSS SECTION (TYP.)
SCALE: NTS

GENERAL NOTES:


1. COMPACT UPPER 6 INCHES OF SUBGRADE TO A MINIMUM OF 90 PERCENT OF MODIFIED PROCTOR MAXIMUM DRY DENSITY ASTM D1557.
2. EARTH BACKFILL TO BE COMPACTED TO A MINIMUM OF 90 PERCENT OF MAXIMUM DRY DENSITY (+/- 3 PERCENT OF OPTIMUM MOISTURE CONTENT) PER ASTM D1557 (MODIFIED PROCTOR).
3. THE EXISTING DIRT/GRAVEL ACCESS ROAD TO THE WEST OF THE PROPOSED PIPELINE TRENCH SHALL BE USED FOR TEMPORARY CONSTRUCTION ACCESS.
4. INFLUENT AND EFFLUENT PIPELINES SHALL BE 18-INCH (OUTSIDE DIAMETER) SCHEDULE 40 CARBON STEEL PIPE WITH VICTAULIC/GROOVED ENDS. STEEL PIPING WILL BE JOINED USING VICTAULIC AGS FLEXIBLE COUPLINGS (STYLE W77) OR OTHER ENGINEER APPROVED EQUIVALENT.
5. ALL SUBSURFACE PIPING AND CONDUIT SHALL HAVE DETECTABLE METALLIC TAPE INSTALLED WITHIN 8 INCHES OF THE TRENCH FINISHED TO FACILITATE LOCATING THE NEWLY INSTALLED UNDERGROUND UTILITIES DURING FUTURE PIPELINE MAINTENANCE AND/OR POTENTIAL REPAIR.
6. PIPELINE INTERFACE/CONNECTIONS TO THE CENTRAL WATER TREATMENT PLANT AND HISTORIC LATERAL PUMP STATION ARE APPROXIMATE. CONTRACTOR SHALL MAKE THE CONNECTIONS AT THESE LOCATIONS BASED ON ACTUAL FIELD CONDITIONS AT THE TIME OF CONSTRUCTION.
7. GRADING AT THE SURFACE OF THE PIPELINE TRENCHES WILL MATCH TO THE EXISTING/SURROUNDING GRADES AND SHALL ALSO PROMOTE DRAINAGE OF SURFACE/STORM WATER AWAY FROM THE TRENCH TO THE LAS VEGAS WASH TO THE NORTH UNLESS OTHERWISE DIRECTED BY THE ENGINEER.
8. ALL AREAS DISTURBED DURING THE INSTALLATION OF THE WEIR DEWATERING PIPELINES SHALL BE RESTORED TO THE PRE-CONSTRUCTION CONDITIONS THAT INCLUDES CONTOUR GRADES, EXISTING VEGETATION TYPES, GRAVEL OR PAVED SURFACES, ETC. UNLESS OTHERWISE DIRECTED BY THE NEVADA ENVIRONMENTAL RESPONSE TRUST, CLARKE COUNTY, AND/OR OTHER APPLICABLE REGULATORY AUTHORITY.
9. ALL SOIL STOCKPILES WILL BE PLACED A MINIMUM OF 2 FEET BEYOND THE EDGE OF THE OPEN TRENCH EXCAVATION.
10. USE A NONWOVEN, 16 OZ/SY GEOTEXTILE BENEATH THE RIPRAP BEDDING LAYER, MIRAFI 1160N OR EQUIVALENT. PLACE RIPRAP AND BEDDING MATERIAL SO AS NOT TO DAMAGE GEOTEXTILE.




3 HLPS INFLUENT PIPELINE CROSS SECTION (TYP.)
SCALE: NTS




4 WTP EFFLUENT DISCHARGE PIPELINE (TYP.)
SCALE: NTS



5 PIPE SECTION TRANSITION TO ABOVEGRADE/UNDERGROUND (TYP.)
SCALE: NTS



6 RIPRAP APRON FOR END SECTIONS (TYP.)
SCALE: NTS



NOTE:
TRANSITION END OF RIPRAP APRON DOWN TO UPPER EDGE OF EXISTING STREAM CHANNEL. APRON MAY BE SKEWED AND DIMENSIONS ADJUSTED TO MATCH AND LINE UP WITH DOWNSTREAM CHANNEL TO SUIT EXISTING CONDITIONS. EXACT LAYOUT AND DIMENSIONS TO BE DETERMINED IN THE FIELD DURING CONSTRUCTION BY THE FIELD ENGINEER.


MARK	DATE	DESCRIPTION	BY	DS
A	11/28/16	ISSUED FOR 60% SUBMITTAL	DS	DS
B	2/15/17	75% SUBMITTAL TO BOR		

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
LAS VEGAS WASH WEIR DEWATERING WEIR DEWATERING PIPELINE


Project No.: 200-01299-16002
Designed By: P. PATTON
Drawn By: F. MENICHELLI
Checked By: D. SHEA

2/14/2017 5:05:33 PM - NTS\1389\51\GROUPO\CADD\NERT DEWATERING\WORKING - UPDATED 020717\C-901-DETAILS-REV B2.DWG - LINTZ, ANDREW


2/14/2017 5:06:15 PM - NTTS\39F51\GROUP\CADD\NERT DEWATERING\WORKING - UPDATED 020717\C-902-DETAILS-REV B.DWG - LINTZ, ANDREW




7 INFLUENT AND EFFLUENT PIPELINES SUPPORT
C-301-2 SCALE: NTS





B INFLUENT AND EFFLUENT PIPELINE SUPPORT SECTION
C-301-2 SCALE: NTS



8 PEDESTAL DETAIL
SCALE: NTS



9 PIPE RESTRAINT CLAMP (TYP.)
SCALE: NTS



10 ASPHALT ROAD CUT AT PARK ENTRANCE
C-301-3 SCALE: NTS


- NOTES:**
1. SAW CUT ASPHALT ROAD A MINIMUM OF 1 FT FROM TOP EDGE OF TRENCH. REPAIR ROADWAY CUT WITH EQUIVALENT DEPTH OF ASPHALT AND COMPACTED ROAD BASE.
 2. COMPACT SUBGRADE AND FILL MATERIAL BELOW COMPACTED ROAD BASE TO 95% OF MODIFIED PROCTOR (ASTM D1557).
 3. ASPHALT ROAD MIX TO COMPLY WITH SECTION 401.02.02 OF THE NDOT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, 2014.

MARK	DATE	DESCRIPTION
A	11/28/16	ISSUED FOR 60% SUBMITTAL
B	02/15/17	75% SUBMITTAL TO BOR


NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
LAS VEGAS WASH WEIR DEWATERING
WEIR DEWATERING PIPELINE

Project No.: 200-01299-16002
Designed By: P. PATTON
Drawn By: F. MENCHELLI
Checked By: D. SHEA


Copyright Tetra Tech




1 TYPICAL EXTRUSION WELD
C-904 NOT TO SCALE



2 TYPICAL GEOMEMBRANE LINER FLOOR INSTALLATION
C-904 NOT TO SCALE



3 TYPICAL HOT WEDGE DOUBLE TRACK FUSION WELD
C-904 NOT TO SCALE



4 CONCRETE EMBEDMENT STRIP
C-904 NOT TO SCALE

2/15/2017 1:37:15 PM - P:\N\01299\200-01299-1601\CAD\SH\FILES\C-900.DWG - GULMIRE, CALEB



www.tetratech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.997.7140

MARK	DATE	DESCRIPTION	BY
A	02/15/17	75% SUBMITTAL TO BOR	CG


NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
**WEIR DEWATERING TREATMENT
SYMBOLS
CIVIL DETAILS**

Project No.: 200-01299-16015
Designed By: J. GUO
Drawn By: C. GULMIRE
Checked By: C. FLORES

C-904

Copyright: Tetra Tech


F
E
D
C
B
A




MARK	THREAD	PROJ.	MIN WASHER THICKNESS	MIN WASHER DIMENSION
3/4 AB 18	4"	4 1/2"	5/16"	2"
1 AB 24	5"	5 1/2"	3/8"	3"

TYPE AB EMBEDDED ANCHOR BOLT

- NOTES:
- USE HEAVY HEX NUTS, ASTM A-193 (GRADE 303 OR 305) FOR ALL BOLTS. PROVIDE DOUBLE NUTS FOR MARK No. s WITH DN.
 - BOLTS SHALL BE ASTM A193 THREADED ROD OR A193 GRADE 303 OR 305 STAINLESS STEEL UNLESS NOTED OTHERWISE.
 - THREADS SHALL BE UNC-2.
 - ANCHOR BOLTS FOR ALL EQUIPMENT AND COLUMNS SHALL BE SET BY TEMPLATE.
 - EXPANSION ANCHORS WHERE REQUIRED SHALL BE HILTI KWIK BOLT TZ. INSTALL PER MANUFACTURER'S RECOMMENDATIONS.
 - BUNDLE ANCHOR BOLTS FOR SHIPMENT BY MARK No. AND TAG WITH MARK No. AND EQUIPMENT DESCRIPTION.
 - SEE DETAIL DRAWINGS FOR ACTUAL BOLT DIMENSIONS.
 - EPOXY FOR POST INSTALLING ANCHOR RODS AND REBAR DOWELS SHALL BE HILTI HIT-RE-500 V3 ADHESIVE ANCHORS WITH RODS AS SHOWN ON SCHEDULE. INSTALL PER MANUFACTURER'S RECOMMENDATIONS.




TYP ANCHOR BOLT CALL-OUT



MARK	DIA	h'ef
3/8"	2"	
1/2"	3 1/2"	
5/8"	4"	
3/4"	4 3/4"	

*ANCHOR DIMENSIONS UNO HKB ANCHORS SHALL BE HILTI KWIK BOLT TZ EXPANSION ANCHORS, OR APPROVED ALTERNATE. INSTALL ANCHORS PER MANUFACTURER'S RECOMMENDATIONS.

TYPE HKB EXPANSION ANCHOR




MARK	DIA	TYPE	LENGTH	HOLE DIA	HOLE DEPTH (MIN)	PROJ. "P"	ROD TYPE
1 EAB 18	1 1/4"		12 1/2"	6"	HILTI HAS		

TYPE EAB EPOXY ANCHOR

STRUCTURAL NOTES:

- A. GENERAL SITE INFORMATION**
- DESIGN CODE ASCE 7-10/IBC-2015 RISK CATEGORY III. CLARK COUNTY, NEVADA.
 - WIND SPEED 120 MPH; EXPOSURE C; OCCUPANCY CATEGORY III.
 - SEISMIC DESIGN PARAMETERS: S_s=0.490; S₁=0.161. SITE CLASS: D; SEISMIC DESIGN CATEGORY C.
- B. FOUNDATION CONSTRUCTION**
- FOUNDATION CONSTRUCTION AND SITE PREPARATION METHODS SHALL FOLLOW RECOMMENDATIONS OUTLINED IN GEOTECHNICAL REPORT; PROVIDED BY TETRA TECH. SPECIFIC REQUIREMENTS ARE:
FOUNDATION SYSTEM: SLAB ON GRADE
FROST DEPTH: 0 FT
SOIL COMPOSITION: SILTY SAND WITH GRAVEL.
ALLOWABLE BEARING PRESSURE: 2500 PSF
MODULUS OF SUBGRADE REACTION: 100 PCI
 - EXCAVATION AND BACKFILL:
A. FOLLOW SPECIFIC RECOMMENDATIONS OUTLINED OF THE REFERENCED ABOVE GEOTECHNICAL REPORT.
B. ENTIRE AREA AROUND EACH FOUNDATION MUST BE THOROUGHLY PROBED FOR UNDERGROUND PIPE, CONDUIT, HIGH PRESSURE LINES, ETC., BEFORE ANY EXCAVATION IS BEGUN.
C. STRUCTURAL BACKFILL SHALL CONSIST OF GRANULAR NON-EXPANSIVE SAND, GRAVEL AND SAND-GRAVEL MIXTURES, WITH PLASTICITY INDEX BELOW 15, WITH 100% LESS THAN 4" SIZE ROCKS AND MAX. 20% PASSING NO. 200 SIEVE. IT SHALL BE PLACED IN 6" MAX. LIFTS. STRUCTURAL FILL IN FOUNDATION AREAS SHOULD BE COMPACTED TO 100% OF THE ASTM D1557, MODIFIED PROCTOR DENSITY.
 - SUBGRADE CONDITIONS SHOULD BE INSPECTED BY A GEOTECHNICAL ENGINEER PRIOR TO PLACEMENT OF ANY CONCRETE. STRUCTURAL FILL SHALL BE INSPECTED AND TESTED.
- C. CONCRETE**
- ALL CONCRETE WORK SHALL CONFORM TO THE REQUIREMENTS OF ACI 301 SPECIFICATIONS FOR STRUCTURAL CONCRETE FOR BUILDINGS, LATEST EDITION, ACI-318 BUILDING CODE REQUIREMENTS FOR REINFORCED CONCRETE, ACI 350 CONCRETE STRUCTURES FOR CONTAINMENT OF HAZARDOUS MATERIALS. CONCRETE STRENGTH TEST SHALL BE PERFORMED IN ACCORDANCE WITH THE REQUIREMENTS OF ACI-318, CHAPTER 5.
 - CONCRETE AND REINFORCEMENT SHALL BE DESIGNED AND PLACED IN ACCORDANCE WITH ACI BUILDING CODE REQUIREMENTS FOR REINFORCED CONCRETE ACI-318, LATEST EDITION, ACI-305 "HOT WEATHER CONCRETING" AND ACI-306 "COLD WEATHER CONCRETING" SHALL BE FOLLOWED.
 - CONCRETE PARAMETERS SHALL BE AS FOLLOWS:
- | EXPOSURE CATEGORY & CLASS | | | | | f'c AT 28 DAYS | CEMENT TYPE | MAX W/C RATIO | AIR CONTENT | MAX SLUMP | OTHER PROVISIONS |
|---------------------------|----------------------|--------------------------|----------------------|------------------|----------------|-------------|---------------|--------------|-----------|------------------|
| TYPE | "F" FREEZING THAWING | "C" CORROSION PROTECTION | "S" SULFATE EXPOSURE | "P" PERMEABILITY | | | | | | |
| A | F0 | C2 | S0 | P0 | 4500 | II | 0.45 | 3.5% TO 6.5% | 4" TO 6" | N/A |
- CEMENT SHALL CONFORM TO ASTM C150
 - AGGREGATES SHALL BE CRUSHED STONE CONFORMING TO "SPECIFICATION FOR CONCRETE AGGREGATES" ASTM C33.
 - WATER USED IN MIXING CONCRETE SHALL CONFORM TO ASTM C1602.
 - REINFORCING BARS SHALL BE DEFORMED, INTERMEDIATE GRADE NEW BILLET STEEL CONFORMING TO ASTM A615 INCLUDING SUPPLEMENTARY REQUIREMENTS S1, GRADE 60. FIELD SPLICES AND DEVELOPMENT LENGTH SHALL COMPLY WITH THE FOLLOWING SCHEDULE. UNO. REINFORCEMENT SHALL BE INSPECTED BEFORE CONCRETE IS PLACED.



BAR SIZE	LAP CLASS	TLS (in.)				HOOK, TIE AND BEND DIMENSIONS (in.)						
		CONC. COVER = 1-1/2"		CONC. COVER = 2"		Ldh	A	B	C	D	E	F
		TOP	OTHER	TOP	OTHER							
#3	B	16	16	16	16	8	4.5	2.5	2.25	2.25	2.25	1.5
#4	B	20	16	20	16	10	6	2.5	3	3	3	2
#5	B	25	19	25	19	12	7.5	2.5	3.75	3.75	3.75	2.5
#6	B	29	23	29	23	19	9	3	9	4.75	4.5	4.5
#7	B	48	37	43	33	17	10.5	3.5	10.5	5.5	5.25	5.25
#8	B	61	47	49	37	19	12	4	12	6.25	6	6
#9	B	75	58	60	46	22	14	5	NA	NA	9.25	NA
#10	B	91	70	74	57	25	15.5	5.5	NA	NA	10.25	NA
#11	B	109	84	89	68	27	17	6	NA	NA	11.5	NA

- WHERE:
- TOP BARS ARE ALL HORIZONTAL BARS SO PLACED THAT MORE THAN 12" OF FRESH CONCRETE IS CAST IN THE MEMBER BELOW THE DEVELOPMENT LENGTH OR SPLICE.
 - ALL BARS THAT ARE NOT 'TOP' BARS ARE 'OTHER' BARS.

- CONCRETE PROTECTION FOR REINFORCEMENT - CLEAR DISTANCE FROM FACE OF CONCRETE TO BAR SHALL BE AS FOLLOWS UNLESS NOTED:
A. CONCRETE DEPOSITED AGAINST GROUND OR VOID FORM: 3"
B. CONCRETE SURFACES EXPOSED TO WEATHER OR IN CONTACT WITH GROUND AFTER REMOVAL OF FORMS: 2"
C. SURFACES NOT EXPOSED TO GROUND OR WEATHER: 3/4" FOR SLABS AND WALLS WITH #11 AND SMALLER BARS, 1-1/2" FOR BEAMS AND COLUMNS.
- EXPANSION JOINT MATERIAL FOR EXPANSION OR ISOLATION JOINTS SHALL BE PREMOULDED, BITUMINOUS IMPREGNATED FIBERBOARD CONFORMING TO ASTM D994.
- JOINT SEALANT FOR ALL CONCRETE CONTROL, CONSTRUCTION AND ISOLATION JOINTS SHALL BE SIKAFLEX-1c SL BY SIKA CORP., OR ENGINEER APPROVED EQUAL.
- GROUT USED FOR VARIOUS APPLICATIONS SHALL BE AS FOLLOWS:
A. GROUT USED FOR STRUCTURAL STEEL / COLUMN BASE PLATES SHALL BE PREPACKED, HIGH-FLUIDITY NON-SHRINK NATURAL AGGREGATE GROUT SUCH AS 'FIVE STAR GROUT' BY FIVE STAR PRODUCTION INC OR APPROVED EQUAL. FOLLOW MANUFACTURER'S INSTRUCTIONS FOR INSTALLATION. SPACE BETWEEN THE ANCHOR BOLTS AND OVERSIZED HOLES IN THE BASE PLATE SHALL BE FULLY GROUTED WITH NON-SHRINK GROUT TO ASSURE PROPER SHEAR TRANSFER. GROUTING SHALL BE PERFORMED ONE BOLT AT A TIME, WHILE OTHER BASE PLATE BOLTS ARE FULLY TIGHTENED.
B. GROUT USED FOR GROUTING COMPRESSORS, TURBINES, LARGE PUMPS AND OTHER RECIPROCATING OR ROTATING EQUIPMENT THAT REQUIRES EPOXY GROUTING SHALL BE 'FIVE-STAR HP' EPOXY GROUT BY FIVE STAR PRODUCTS, INC., OR APPROVED EQUAL. FOLLOW MANUFACTURER'S INSTRUCTIONS FOR INSTALLATION.
- ALL WELDING PROCEDURES, INCLUDING STUD WELDING, AND QUALIFICATIONS SHALL BE IN ACCORDANCE WITH AWS D1.1.
- ALL SLABS SHALL BE GIVEN A FLOAT FINISH AS DESCRIBED IN ACI 301. ALL WALKS AND EXTERIOR SLABS SHALL BE BROOM FINISHED AFTER CONCRETE HAS RECEIVED A FLOAT FINISH.
- EXPOSED CORNERS SHALL BE CHAMFERED 3/4" UNLESS NOTED.
- COMPARE ALL ELECTRICAL, MECHANICAL AND PIPING DRAWINGS FOR EMBEDDED ITEMS (PIPE, CONDUIT, ETC.) AND BLOCKOUTS SHOWN CORRESPOND TO THOSE SHOWN ON THE STRUCTURAL DRAWINGS. NOTIFY THE ENGINEER OF ANY DISCREPANCIES BEFORE PLACING ANY CONCRETE.
- IF REINFORCING OR MESH IS FIELD CUT FOR SMALL OPENINGS, CONDUIT, ELECTRICAL BOXES, ETC., CUT REINFORCING SHALL BE REPLACED WITH AN EQUIVALENT AREA OF STEEL ALL SUCH BARS SHALL EXTEND 24" MINIMUM (OR MESH LAP 2') BEYOND CORNER OR EDGE OF OPENING IF NECESSARY. REINFORCING SHALL BE BENT TO PROVIDE THIS MINIMUM EMBEDMENT. MAKE ALL BARS CONTINUOUS AROUND CORNERS.
- THE CONTRACTOR SHALL VERIFY ALL EQUIPMENT ANCHOR BOLT DIMENSIONS AGAINST THE CERTIFIED EQUIPMENT DRAWINGS BEFORE PLACING CONCRETE. TOLERANCES FOR ANCHOR BOLT LOCATIONS AND ELEVATIONS SHALL BE AS DEFINED IN THE AMERICAN INSTITUTE OF STEEL CONSTRUCTION (AISC) CODE OF STANDARD PRACTICE.

CONTRACTOR'S MEANS AND METHODS


- THE STRUCTURAL DRAWINGS AND NOTES REPRESENT THE FINISHED STRUCTURE. THEY DO NOT INDICATE THE METHOD OF CONSTRUCTION. FOR THIS REASON, DURING ERECTION OF THE STRUCTURE AND/OR THE DEMOLITION OF THE STRUCTURE OR PORTIONS OF THE STRUCTURE, THE CONTRACTOR SHALL BE RESPONSIBLE FOR TEMPORARY BRACING TO WITHSTAND ALL LOADS TO WHICH THE STRUCTURE MAY BE SUBJECTED, INCLUDING LATERAL LOADS, EXCAVATIONS, SHORING, STOCKPILES OF MATERIALS AND EQUIPMENT, IN ADDITION TO ANY WORKER SAFETY REQUIREMENTS. SUCH BRACING SHALL BE LEFT IN PLACE AS LONG AS IT MAY BE REQUIRED FOR SAFETY AND UNTIL ALL STRUCTURAL FRAMING AND DIAPHRAGMS ARE IN PLACE WITH CONNECTIONS COMPLETED.
- DISCOVERY: DURING CONSTRUCTION, THE CONTRACTOR MAY ENCOUNTER EXISTING CONDITIONS OR AS BUILT DIMENSIONS WHICH ARE NOT NOW KNOWN OR ARE AT VARIANCE WITH PROJECT DOCUMENTATION (DISCOVERY). SUCH CONDITIONS MAY INTERFERE WITH CONSTRUCTION OR REQUIRE PROTECTION AND / OR SUPPORT OF EXISTING WORK DURING CONSTRUCTION, OR MAY CONSIST OF DAMAGE OR DETERIORATION TO THE STRUCTURAL MATERIALS OR COMPONENTS WHICH COULD JEOPARDIZE THE INTEGRITY OF THE STRUCTURE(S) PRIOR TO PROCEEDING WITH WORK RELATED TO SUCH DISCOVERIES.
- IT IS THE CONTRACTOR'S RESPONSIBILITY TO IMMEDIATELY NOTIFY THE STRUCTURAL ENGINEER OF ANY DISCOVERY HE OR SHE MAY INTERFERE WITH THE PROPER EXECUTION OF THE WORK OR JEOPARDIZE THE INTEGRITY OF THE STRUCTURE(S) PRIOR TO PROCEEDING WITH WORK RELATED TO SUCH DISCOVERIES.

CONTRACTOR'S COORDINATION

- THE CONTRACTOR SHALL VERIFY AND COORDINATE ALL DIMENSIONS AND DETAILS BETWEEN ALL TRADES, SUBCONTRACTORS AND VENDOR SUPPLIED EQUIPMENT PRIOR TO COMMENCING ANY CONSTRUCTION. THE STRUCTURAL ENGINEER SHALL BE IMMEDIATELY NOTIFIED ANY INCONSISTENCIES RELATING TO THE STRUCTURE. FAILURE TO DO SO SHALL RELIEVE THE ENGINEER OF ALL CONSEQUENCES RELATED TO THE INCONSISTENCY.

- SEE MECHANICAL, ELECTRICAL AND OTHER DISCIPLINE'S DRAWINGS FOR ADDITIONAL INFORMATION RELATING TO THE STRUCTURE.

STRUCTURAL TESTING & INSPECTION REQUIREMENTS				
REQUIRED INSPECTION VERIFICATION OR TEST	VERIFICATION MONITORING FREQUENCY	TYPE AND/OR FREQUENCY OF TESTING	IBC SECTION & REFERENCE CRITERIA	INSPECTOR QUALIFICATIONS
1. SOILS				
A. SITE PREPARATION			IBC 1704.7.1	
B. DURING FILL PLACEMENT	CONTINUOUS OR PERIODIC	VISUAL OBSERVATION: DURING PLACEMENT AND COMPACTION OF FILL, SPECIAL INSPECTOR SHALL DETERMINE THAT THE MATERIAL BEING USED AND THE MAXIMUM LIFT THICKNESS COMPLY WITH THE PROJECT REQUIREMENTS. PIT RUN MATERIALS SHALL BE VISUALLY MONITORED BY THE TESTING LAB WITH ADDITIONAL SAMPLES TESTED EACH DAY, OR MORE OFTEN IF MATERIAL APPEARS TO VARY.	IBC 1704.7.2 GEOTECHNICAL REPORT, STRUCTURAL NOTES	QUALIFICATIONS BASED ON ASTM D3740
C. EVALUATION OF IN-PLACE DENSITY OF FILL	CONTINUOUS OR PERIODIC	PROVIDE (1) ONE DENSITY TEST FOR EACH 2000 SQ. FT. REFER TO NOTES ON BUILDING PAD FOR TESTING SPECIFICATIONS.	IBC 1704.7.3 GEOTECHNICAL REPORT, STRUCTURAL NOTES	QUALIFICATIONS BASED ON ASTM D1557
D. CLAY CAP	CONTINUOUS OR PERIODIC	PLACEMENT OF CLAY CAP SHALL BE MONITORED BY GEOTECHNICAL ENGINEER WITH A WRITTEN REPORT SENT TO STRUCTURAL ENGINEER.	IBC 1704.7.3 GEOTECHNICAL REPORT, STRUCTURAL NOTES	QUALIFICATIONS BASED ON ASTM D3740
2. CONCRETE CONSTRUCTION				
A. REINFORCING STEEL	PERIODIC	PROVIDE PERIODIC INSPECTION OF REINFORCING SIZES, SPACING, GRADE OF REBAR, AND PLACEMENT AT THE FOLLOWING FREQUENCY:	IBC 1704.4, ACI 318 - CH. 3.5, 7.1.7.1, STRUCTURAL NOTES	QUALIFICATIONS BASED ON ASTM E309
B. REINFORCING STEEL WELDING		NO FIELD WELDING PERMITTED.	AWSD1.4 ACI 318 3.5.2	CWI
C. ANCHORS TO BE INSTALLED IN CONCRETE PRIOR TO & DURING PLACEMENT OF CONCRETE WHERE ALLOWABLE LOADS HAVE BEEN INCREASED	CONTINUOUS		IBC1704.4	TRAINED FIELD TECHNICIAN WITH ONE YEAR MIN. EXPERIENCE
D. VERIFY USE OF CONCRETE MIX DESIGN	PERIODIC	EACH CONCRETE POUR	ACI 318 - CH. 4, 5.2, 5.4	QUALIFICATIONS BASED ON ASTM C1077
E. SAMPLING OF FRESH CONCRETE	CONTINUOUS EACH CONCRETE POUR	1. ALL CONCRETE TESTING IS TO BE MADE AFTER WATER, IF ANY, IS ADDED TO SITE. 2. PROVIDE A SET OF (4) FOUR CYLINDERS TO BE TAKEN FOR EVERY 75 CUBIC YARDS OF CONCRETE, OR FRACTION THEREOF. BY TESTING LAB. MONITOR SLUMP AND AIR CONTENT OF CONCRETE AND NOTIFY DELIVERY DRIVER IF SLUMP DEVIATES MORE THAN PERMITTED BY STRUCTURAL NOTES. CONTACT SUPPLIER FOR FURTHER DIRECTIONS.	ASTM C172 ASTM C31 ACI 318 - CH. 5.6, 5.8	QUALIFICATIONS BASED ON ASTM C1077
F. PLACEMENT OF CONCRETE	CONTINUOUS		ACI 318 - CH. 5.9, 5.10	QUALIFICATIONS BASED ON ASTM C1077
G. MAINTENANCE OF SPECIFIED CURING TEMPERATURE TECHNIQUES	PERIODIC	EACH CONCRETE POUR	ACI 318 - CH. 5.11, 5.13.	QUALIFICATIONS BASED ON ASTM C1077
H. REMOVAL OF SHORES AND FORMS FROM STRUCTURAL SLABS	PERIODIC	VERIFY IN-SITU CONCRETE STRENGTH PRIOR TO REMOVAL.	ACI 318 - CH. 6.1.1, STRUCTURAL NOTES.	QUALIFICATIONS BASED ON ASTM E309
3. STEEL CONSTRUCTION				
A. MATERIAL VERIFICATION OF STRUCTURAL STEEL	PERIODIC	1. IDENTIFICATION MARKINGS TO CONFORM TO ASTM STANDARDS SPECIFIED IN THE APPROVED CONSTRUCTION DOCUMENTS.	IBC 1708.6, STRUCTURAL NOTES	FIELD TECHNICIAN WITH ONE YEAR MINIMUM EXPERIENCE
B. MATERIAL VERIFICATION OF WELD FILLER MATERIALS	PERIODIC	1. IDENTIFICATION MARKINGS TO CONFORM TO SPECIFICATION IN THE APPROVED CONSTRUCTION DOCUMENTS.	ASTM A6 OR ASTM A569	CWI
C. WELDING OF STRUCTURAL STEEL	PERIODIC	1. SINGLE PASS FILLET WELDS 5/16"	AWSD1.1	CWI
	PERIODIC	2. ROOF DECK WELDS	AWSD1.3	CWI



1 SKID CLAMP
SCALE: NONE

TETRA TECH
www.tetrattech.com
1489 West Warm Springs Road, Suite 110 Henderson, NV 89014
Tel: 702.946.6700 Fax: 702.997.7140

MARK	DATE	DESCRIPTION	BY	
			SA/B	RWB
A	11/28/16	ISSUED FOR 60% SUBMITTAL		
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL		
C	02/15/17	ISSUED FOR 75% SUBMITTAL TO BOR		


NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
WEIR DEWATERING TREATMENT
STRUCTURAL CONCRETE NOTES

Project No.: 200-01299-16015
Designed By: SAB
Drawn By: RWB
Checked By: CC


NOT FOR CONSTRUCTION

S-001


2/14/2017 11:56:08 AM C:\Users\rebecca.walsh\Documents\S-CVTFP-2015-ECI_Rebecca.Benson.rvt




1 SLAB ON GRADE
SCALE: NONE




2 CONTROL JOINT (SJ)
SCALE: NONE




3 CONSTRUCTION JOINT (CJ)
SCALE: NONE




4 ISOLATION JOINT (IJ)
SCALE: NONE




5 EXPANSION JOINT (EJ)
SCALE: NONE




6 JOINT FILL
SCALE: NONE




7 TYP. FLOOR JOINTS
SCALE: NONE




8 WALL CORNER REBAR
SCALE: NONE




9 WALL 'TEE' REBAR
SCALE: NONE




10 WALL CORNER REBAR
SCALE: NONE




11 WALL 'TEE' REBAR
SCALE: NONE




12 FRP CURB ANGLE
SCALE: NONE




13 PIPE BOLLARD DETAIL
SCALE: NONE




14 RECTANGULAR SLAB OR WALL OPENING
SCALE: NONE




15 ROUND SLAB OR WALL OPENING
SCALE: NONE




17 DURA-BLOK SUPPORT
SCALE: 3/4" = 1'-0"




16 DURA-BLOK SLEEPER
SCALE: 3/4" = 1'-0"



18 BALANCED PIPE SUPPORT
SCALE: NONE



19 UNBALANCED PIPE SUPPORT
SCALE: NONE



MIC-C90-D
SCALE: NONE



www.tetrattech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Tel: 702.946.6700 Fax: 702.997.7140

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	SAB
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	RWB
C	02/15/17	ISSUED FOR 75% SUBMITTAL TO BOR	RWB






NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
WEIR DEWATERING TREATMENT
STRUCTURAL CONCRETE
DETAILS

Project No.: 200-01299-16015
Designed By: SAB
Drawn By: RWB
Checked By: CC

S-002

NOT FOR CONSTRUCTION

Copyright: Tetra Tech



TAG #	OPERATING WEIGHT	HEIGHT OF CENTER OF GRAVITY
PU-1A	6000 LB	29 IN
PU-1B	6000 LB	29 IN
PU-1C	6000 LB	29 IN
PU-1D (SHELF SPARE)	6000 LB	29 IN

SUNRISE MOUNTAIN PUMP STATION FOUNDATION PLAN
SCALE: 1/4" = 1'-0"

SEE CIVIL LAYOUT DRAWINGS FOR COORDINATES.

SEE SHEET S-401 FOR CONTINUATION


NOT FOR CONSTRUCTION

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	SAB
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	RWB
C	02/15/17	ISSUED FOR 75% SUBMITTAL TO BOR	RWB

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
**WEIR DEWATERING TREATMENT
SUNRISE MOUNTAIN PUMP
STATION FOUNDATION
PLAN**

Project No.: 200-01299-16015
Designed By: SAB
Drawn By: RWB
Checked By: CC


S-201



HISTORIC LATERAL PUMP STATION FOUNDATION PLAN
SCALE: 1/8" = 1'-0"

TAG #	OPERATING WEIGHT	HEIGHT OF CENTER OF GRAVITY
PU-2A	6000 LB	29 IN
PU-2B	6000 LB	29 IN
PU-2C	6000 LB	29 IN
PU-2D (SHELF SPARE)	6000 LB	29 IN

NOT FOR CONSTRUCTION



www.tetrattech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Tel: 702.946.6700 Fax: 702.997.7140



MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	RWB
B	01/27/17	ISSUED FOR DRAFT 80% SUBMITTAL	RWB
C	02/15/17	ISSUED FOR 75% SUBMITTAL TO BOR	RWB

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
**WEIR DEWATERING TREATMENT
HISTORIC LATERAL PUMP
STATION FOUNDATION
PLAN**

Project No.: 200-01299-16015
Designed By: SAB
Drawn By: RWB
Checked By: CC

S-301

SEE S-201
FOR CONTINUATION



CENTRAL WATER TREATMENT PLANT FOUNDATION PLAN

SCALE: 1" = 10'-0"

NOT FOR CONSTRUCTION


MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	SAB
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	RWB
C	02/15/17	ISSUED FOR 75% SUBMITTAL TO BOR	RWB

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
**WEIR DEWATERING TREATMENT
CENTRAL WATER
TREATMENT PLANT
FOUNDATION PLAN**


Project No.:	200-01299-16015
Designed By:	SAB
Drawn By:	RWB
Checked By:	CC

S-401


2/14/2017 11:56:10 AM C:\Users\rebecca.walsh\Documents\S-CVTFP-2015-ECI_Rebecca.Benson.rvt




A CONCRETE REINFORCEMENT SECTION
S-201 SCALE: 1/2" = 1'-0"




B CYCLONE FOUNDATION SECTION
SCALE: 1/2" = 1'-0"




C FOUNDATION SECTION
S-401 SCALE: 1/2" = 1'-0"




1 MULTIMEDIA FILTER SKID PAD DETAIL
S-401 SCALE: 1/4" = 1'-0"




E MULTIMEDIA FILTER SKID REINFORCEMENT SECTION
S-402 SCALE: 1/4" = 1'-0"




3 HDPE LINER-DETAIL
S-402 SCALE: 3/4" = 1'-0"



2 MULTIMEDIA FILTER SADDLE SUPPORT PEDESTAL DETAIL
S-401 SCALE: 1/4" = 1'-0"



G MULTIMEDIA FILTER PEDESTAL SECTION
S-402 SCALE: 1/2" = 1'-0"



D EQUIPMENT PAD SECTION
S-201 SCALE: 1/2" = 1'-0"

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	SAB
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	RWB
C	02/15/17	ISSUED FOR 75% SUBMITTAL TO BOR	RWB

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
WEIR DEWATERING TREATMENT
CENTRAL WATER
TREATMENT PLANT
FOUNDATION SECTIONS

Project No.: 200-01299-16015
Designed By: SAB
Drawn By: RWB
Checked By: CC


TETRA TECH
www.tetrattech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Tel: 702.946.6700 Fax: 702.997.7140

NOT FOR CONSTRUCTION

S-402

Copyright: Tetra Tech

2/15/2017 1:28:41 PM - NTTS17\F51.TT.LOCAL\ERP\PROJ\CTS\NER01299200-01299-16015\CAD\SHEETFILES\D-101.DWG - WOLFORD, LINDY



MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	LBW

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	LBW

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA

WEIR DEWATERING TREATMENT

PROCESS FLOW DIAGRAM

Project No.: 200-01299-16015
 Designed By: J. GUO
 Drawn By: S. ULREY
 Checked By: J. GUO

D-101

Copyright Tetra Tech

2/15/2017 2:34:09 PM - P:\NER\01299\200-01299-16015\CAD\SHEETFILES\D-001.DWG - GULMIRE, CALEB

VALVE DESIGNATIONS

SYMBOLS		MARK	TYPE
PIPEWORK DRAWINGS	FLOW DIAGRAMS		
		B	BALL VALVE
		A	GATE VALVE
		BV	BUTTERFLY VALVE
		C	STANDARD CHECK VALVE
		CC	CUSHION CHECK VALVE
		DC	DOUBLE VANE CHECK VALVE
		IB	INDUSTRIAL BUTTERFLY VALVE
		PV	PLUG VALVE
SEE STRUCTURAL		PRW	PRESSURE RELIEF VALVE (WALL TYPE)
SEE STRUCTURAL		PRS	PRESSURE RELIEF VALVE (SLAB TYPE)
		RA	RESILIENT SEATED GATE VALVE
		RC	RADIAL CHECK VALVE
		RP	PINCH VALVE
		SC	SILENT CHECK VALVE
		SV	SURGE OR PRESSURE RELIEF VALVE
		TPSV	TAPPING SLEEVE AND VALVE
		TSV	TELESCOPIC VALVE

OPERATORS (SCHEMATICS ONLY)

SYMBOL	TYPE	SYMBOL	TYPE
THROTTLING SERVICE			
	PNEUMATIC		ELECTRIC
	ELECTRIC		HYDRAULIC
OPEN - SHUT SERVICE			
	PNEUMATIC		ELECTRIC
	ELECTRIC		HYDRAULIC

JOINT DESIGNATIONS

SYMBOL	MARK	TYPE
	F□	FLANGED JOINT
	M□	MECHANICAL JOINT
	S□	SCREWED JOINT
	PO□	PUSH ON JOINT
	BFC	BOLTED FLEXIBLE COUPLING
	GC	GROOVED COUPLING
	W□	SHOP WELDED JOINT (STEEL PIPE)
	FW□	FIELD WELDED JOINT (STEEL PIPE)
	ST□	SOCKET TYPE JOINT (FRP OR PVC PIPE)
	E□	EXPANSION JOINT
	BF	BLIND FLANGE
	AFC	ADAPTER FLANGE COUPLING

SLEEVE AND WALL PIPE DESIGNATIONS

SYMBOL	DESCRIPTION
	CORED HOLE IN EXISTING WALL
	WALL SLEEVE W/WATER COLLAR (STANDARD)
	FLANGE X PLAIN END WALL PIPE
	FLANGE X PLAIN END WALL PIPE
	FLANGE X FLANGE WALL PIPE
	MECHANICAL JOINT X MECHANICAL JOINT WALL PIPE
	MECHANICAL JOINT X PLAIN END WALL PIPE
	PUSH ON BELL JOINT X PLAIN END WALL PIPE

PIPING AND EQUIPMENT SYMBOLS

	VTR	VENT TO ROOF
	PI	CHEMICAL SEAL W/PRESS GAUGE
	PI	PRESSURE GAUGE
	PI	PULSATION DAMPENER W/PRESS GAUGE
	P	SUCTION ACCUMULATOR W/PRESS GAUGE
		ELBOW UP
		ELBOW DOWN
		TEE UP
		TEE DOWN
		REDUCER-CONCENTRIC
		REDUCER-ECCENTRIC
		WYE STRAINER
		UNION
	M	METER (TOTALIZING)
		PIPING (BELOW SLAB)
	F.D.	FLOOR DRAIN
	E.D.	EQUIPMENT DRAIN
	C.O.	CLEANOUT-FLOOR
	C.O.	CLEANOUT-HORIZONTAL
	D	PIPE TO DRAIN
		ELECTRIC
	BFP	BACKFLOW PREVENTER
	PRV XX PSI	PRESSURE RELIEF VALVE SET POINT
	BPV XX PSI	BACK PRESSURE VALVE SET POINT
		PUMP
		GLOBE VALVE
		PET COCK
		PLUG VALVE - GAS
		PRESSURE RELIEF VALVE
		TEMPERING VALVE
	H.B.	HOSE BIBB (3/4")
	S.C.	SILL COCK (3/4")
	F.H.B.	FLUSHING HOSE BIBB (1-1/2")
	W.H.	WALL HYDRANT (1-1/2")

PROCESS FLOW ABBREVIATIONS

CA	COMPRESSED AIR
BP	BYPASS
C	COAGULANT
D	DRAIN
DCT	DECANT
EI	EQUALIZATION TANK INFLUENT
F	FILTRATE
FS	FINAL TANK SLUDGE
NAOH	SODIUM HYDROXIDE/CAUSTIC
P	PERLITE
PEW	PLANT EFFLUENT WATER
PH	pH
POLY	POLYMER
PW	POTABLE WATER
PWW	PROCESS WASTEWATER
NPW	NONPOTABLE WATER
RWW	RECYCLED WASTEWATER
SLD	SLUDGE
SN	SUPERNATANT
SPD	SUMP PUMP DISCHARGE
TDH	TOTAL DYNAMIC HEAD
THS	THICKENED SLUDGE
TS	TRANSFER SLUDGE
TUR	TURBIDIMETER
WS	WASTE SLUDGE

PLUMBING ABBREVIATIONS

D	DRAIN
HW	HOT WATER
NG	NATURAL GAS
PW	POTABLE WATER
SAN	SANITARY DRAIN
SPD	SUMP PUMP DISCHARGE
SW	SERVICE WATER
V	VENT
VTR	VENT TO ROOF

FEED AND MONITORING SYMBOLS

	DIFFERENTIAL PRESSURE MEASUREMENT / SWITCH
	FLOW SWITCH
	PRESSURE ELEMENT / TRANSMITTER
	TURBIDIMETER
	pH ANALYZER
	FLOW METER

TETRA TECH
www.tetra-tech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.967.7140

MARK	DATE	DESCRIPTION	BY	SKU	CG
A	11/29/16	ISSUED FOR 60% SUBMITTAL			
B	02/19/17	75% SUBMITTAL TO BOR			


NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
WEIR DEWATERING TREATMENT
PROCESS LEGEND,
ABBREVIATIONS,
AND GENERAL NOTES

Project No.:	200-01299-16015
Designed By:	C. FLORES
Drawn By:	S. ULREY
Checked By:	N. FOGEL


D-001

Copyright: Tetra Tech

2/15/2017 11:11:57 AM C:\Users\lindy.walford\Desktop\Active Projects\Revit\Revit 2015\D-CVTP-2015_lindy.walford.rvt



1 SUNRISE MOUNTAIN PUMP STATION PIPING LAYOUT
D-201 SCALE: 1/8" = 1'-0"




MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	SKU
B	02/15/17	75% SUBMITTAL TO BOR	LBW


NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
SUNRISE MOUNTAIN PUMP STATION EQUIPMENT & PIPING PLAN

Project No.: 200-01299-16015
Designed By: J. GUO
Drawn By: S. ULREY
Checked By: S. DARIAN


1 2 3 4 5 6 7




1 Section
D-202 SCALE: 1/4" = 1'-0"




2 SECTION
D-202 SCALE: 1/4" = 1'-0"



3 SECTION
D-202 SCALE: 1/4" = 1'-0"



4 Section
D-202 SCALE: 1/4" = 1'-0"



TETRA TECH
www.tetratech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Tel: 702.946.6700 Fax: 702.987.7140

MARK	DATE	DESCRIPTION	BY	SKU	LBW
A	11/28/16	ISSUED FOR 60% SUBMITTAL			
B	02/15/17	75% SUBMITTAL TO BOR			

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA

**WEIR DEWATERING TREATMENT
SUNRISE MOUNTAIN PUMP
STATION EQUIPMENT &
PIPING SECTIONS**


Project No.: 200-01299-16015
Designed By: J. GUO
Drawn By: S. ULREY
Checked By: S. DARIAN

D-202


2/15/2017 11:12:06 AM C:\Users\lindy.walford\Desktop\Projects\Revit\Revit 2015\D-CVTP-2015_lindy.walford.rvt

Copyright: Tetra Tech

2/15/2017 11:12:25 AM C:\Users\lindy.wolford\Desktop\Projects\Revit\Revit 2015\D-CVTP-2015.lndy.wolford.rvt



1 HISTORIC LATERAL PUMP STATION PIPING LAYOUT
D-301 SCALE: 1/8" = 1'-0"




MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	SKU
B	02/15/17	75% SUBMITTAL TO BOR	LBW

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
**WEIR DEWATERING TREATMENT
STATION EQUIPMENT &
PIPING PLAN**

Project No.: 200-01299-16015
Designed By: J. GUO
Drawn By: S. ULREY
Checked By: S. DARIAN

2/15/2017 11:12:34 AM C:\Users\lindy.walford\Desktop\Projects\Revit\Revit 2015\D-CV\TP-2015_indy.walford.rvt



www.tetratech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Tel: 702.946.6700 Fax: 702.987.7140

MARK	DATE	DESCRIPTION	BY	SKU	LBW
A	11/28/16	ISSUED FOR 60% SUBMITTAL			
B	02/15/17	75% SUBMITTAL TO BOR			

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA


**WEIR DEWATERING TREATMENT
STATION EQUIPMENT &
PIPING SECTIONS**

Project No.: 200-01299-16015
Designed By: J. GUO
Drawn By: S. ULREY
Checked By: S. DARIAN

D-302

Copyright: Tetra Tech

2/15/2017 11:15:46 AM C:\Users\lindy.walford\Desktop\Projects\Revit\Revit 2015\D-CVTP-2015_lindy.walford.rvt




1 CENTRAL WATER TREATMENT PLANT PIPING LAYOUT
 D-402 SCALE: 1/8" = 1'-0"

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	SKU
B	02/15/17	75% SUBMITTAL TO BOR	LBW


NEVADA ENVIRONMENTAL RESPONSE TRUST
 HENDERSON, NEVADA
**WEIR DEWATERING TREATMENT
 CENTRAL WATER
 TREATMENT PLANT PIPING
 LAYOUT**

Project No.: 200-01299-16015
 Designed By: J. GUO
 Drawn By: S. ULREY
 Checked By: S. DARIAN

2/15/2017 11:17:14 AM C:\Users\lindy.walford\Desktop\Projects\Revit\Revit 2015\D-CVTP-2015_lindy.walford.rvt



1 CYCLONE SYSTEM PLAN
D-501 SCALE: 1/4" = 1'-0"



TETRA TECH
www.tetra.tech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Tel: 702.946.6700 Fax: 702.987.7140

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	SKU
B	02/15/17	75% SUBMITTAL TO BOR	LBW


NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
WEIR DEWATERING TREATMENT
CYCLONE SYSTEM
EQUIPMENT & PIPING
PLAN

Project No.: 200-01299-16015
Designed By: J. GUO
Drawn By: S. ULREY
Checked By: S. DARIAN


D-501

Copyright: Tetra Tech


2/15/2017 11:18:57 AM C:\Users\lindy.walford\Desktop\Projects\Revit\Revit 2015\D-CVTP-2015_lindy.walford.rvt




1 HYDROCYCLONE SECTION
D-502 SCALE: 1/4" = 1'-0"




3 HYDROCYCLONE SECTION
D-502 SCALE: 1/4" = 1'-0"



2 HYDROCYCLONE SECTION
D-502 SCALE: 1/4" = 1'-0"



4 HYDROCYCLONE SECTION
D-502 SCALE: 1/4" = 1'-0"



MARK	DATE	DESCRIPTION	BY	SKU	LBW
A	11/28/16	ISSUED FOR 60% SUBMITTAL			
B	02/15/17	75% SUBMITTAL TO BOR			


NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
**WEIR DEWATERING TREATMENT
CYCLONE SYSTEM
EQUIPMENT & PIPING
SECTIONS**

Project No.: 200-01299-16015
Designed By: J. GUO
Drawn By: S. ULREY
Checked By: S. DARIAN


D-502

Copyright: Tetra Tech

2/15/2017 11:19:42 AM C:\Users\lindy.walford\Desktop\Projects\Revit\Revit 2015\D-CVTP-2015_lindy.walford.rvt



1 MULTI-MEDIA FILTER SYSTEM PLAN
D-601 SCALE: 1/4" = 1'-0"



MARK	DATE	DESCRIPTION	BY	SKU	LBW
A	11/28/16	ISSUED FOR 60% SUBMITTAL			
B	02/15/17	75% SUBMITTAL TO BOR			


NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
**WEIR DEWATERING TREATMENT
MULTI-MEDIA FILTER &
SYSTEM EQUIPMENT PIPING PLAN**

Project No.: 200-01299-16015
Designed By: J. GUO
Drawn By: S. ULREY
Checked By: S. DARIAN

D-601

Copyright: Tetra Tech

2/15/2017 11:20:12 AM C:\Users\lindy.walford\Desktop\Projects\Revit\Revit 2015\D-CVTP-2015_lindy.walford.rvt




1 MULTI-MEDIA FILTER SECTION
D-602 SCALE: 1/4" = 1'-0"

2 MULTI-MEDIA FILTER SECTION
D-602 SCALE: 1/4" = 1'-0"

4 MULTI-MEDIA FILTER SECTION
D-602 SCALE: 1/4" = 1'-0"

3 MULTI-MEDIA FILTER SECTION
D-602 SCALE: 1/4" = 1'-0"

5 BLOWER SECTION
D-602 SCALE: 1/4" = 1'-0"




MARK	DATE	DESCRIPTION	BY	SKU	LBW
A	11/28/16	ISSUED FOR 60% SUBMITTAL			
B	02/15/17	75% SUBMITTAL TO BOR			


NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
**WEIR DEWATERING TREATMENT
MULTI-MEDIA FILTER &
SYSTEM EQUIPMENT &
PIPING SECTIONS**

Project No.: 200-01299-16015
Designed By: J. GUO
Drawn By: S. ULREY
Checked By: S. DARIAN

2/15/2017 11:20:30 AM C:\Users\lindy.walford\Desktop\Projects\Revit\Revit 2015\D-CVTP-2015_lindy.walford.rvt



1 ION EXCHANGER SYSTEM PLAN
D-701 SCALE: 1/4" = 1'-0"



MARK	DATE	DESCRIPTION	BY	SKU	LBW
A	11/28/16	ISSUED FOR 60% SUBMITTAL			
B	02/15/17	75% SUBMITTAL TO BOR			


NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
**WEIR DEWATERING TREATMENT
ION EXCHANGE SYSTEM
EQUIPMENT & PIPING
PLAN**

Project No.: 200-01299-16015
Designed By: J. GUO
Drawn By: S. ULREY
Checked By: S. DARIAN


D-701

Copyright: Tetra Tech


1 2 3 4 5 6 7




1 ION EXCHANGE SYSTEM SECTION
D-702 SCALE: 1/4" = 1'-0"




2 ION EXCHANGE SYSTEM SECTION
D-702 SCALE: 1/4" = 1'-0"



3 ION EXCHANGE SYSTEM SECTION
D-702 SCALE: 1/4" = 1'-0"



4 ION EXCHANGE SYSTEM SECTION
D-702 SCALE: 1/4" = 1'-0"



2/15/2017 11:20:46 AM C:\Users\lindyl.walford\Desktop\Projects\Revit\Revit 2015\D-CVTP-2015_indy.walford.rvt

TETRA TECH
www.tetratech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Tel: 702.946.6700 Fax: 702.987.7140

MARK	DATE	DESCRIPTION	BY	SKU	LBW
A	11/28/16	ISSUED FOR 60% SUBMITTAL			
B	02/15/17	75% SUBMITTAL TO BOR			

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA


**WEIR DEWATERING TREATMENT
ION EXCHANGE SYSTEM
EQUIPMENT AND PIPING
SECTIONS**

Project No.: 200-01299-16015
Designed By: J. GUO
Drawn By: S. ULREY
Checked By: S. DARIAN


D-702

Copyright: Tetra Tech

C:\Users\lindy.walford\Desktop\Active Projects\Revit\Revit 2015\D-CVTP-2015_lindy.walford.rvt



1 TREATED WATER SYSTEM PLAN
D-801 SCALE: 1/4" = 1'-0"



MARK	DATE	DESCRIPTION	BY
A	11/25/16	ISSUED FOR 60% SUBMITTAL	SKU
B	02/15/17	75% SUBMITTAL TO BOR	LBW

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA

WEIR DEWATERING TREATMENT
WASTE, BACKWASH &
TREATED WATER SYSTEM
EQUIPMENT & PIPING

Project No.: 200-01299-16015
Designed By: J. GUO
Drawn By: S. ULREY
Checked By: S. DARIAN


D-801

TETRA TECH


www.tetrattech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Tel: 702.946.6700 Fax: 702.987.7140

Copyright: Tetra Tech

2/15/2017 11:21:06 AM C:\Users\lindy.walford\Desktop\Active Projects\Revit\Revit 2015\D-CVTP-2015_lindy.walford.rvt



1 TREATED WATER PUMPING SYSTEMS PLAN
D-802 SCALE: 1/4" = 1'-0"



MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	SKU
B	02/15/17	75% SUBMITTAL TO BOR	LBW

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA

**WEIR DEWATERING TREATMENT
TREATED WATER
PUMPING SYSTEMS PLAN**


Project No.: 200-01299-16015
Designed By: J. GUO
Drawn By: S. ULREY
Checked By: S. DARIAN

D-802


TETRA TECH
www.tetratech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Tel: 702-946-6700 Fax: 702-997-7140

Copyright: Tetra Tech

2/15/2017 11:21:25 AM C:\Users\lindy.wolford\Desktop\Active Projects\Revit\Revit 2015\D-CVTP-2015_lindy.wolford.rvt



1 WASTE-BACKWASH-TREATED WATER SYSTEM PLAN
D-803 SCALE: 1/4" = 1'-0"



www.tetratech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Tel: 702.946.6700 Fax: 702.987.7140

BY LBW

DESCRIPTION 75% SUBMITTAL TO BOR

DATE 02/15/17

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA


WEIR DEWATERING TREATMENT
WASTE, BACKWASH &
TREATED WATER SYSTEM
EQUIP. & PIPING PLAN

Project No.: 200-01299-16015
Designed By: J. GUO
Drawn By: L. WOLFORD
Checked By: S. DARIAN


D-803

Copyright: Tetra Tech


2/15/2017 11:21:32 AM C:\Users\lindy.walford\Desktop\Projects\Revit\Revit 2015\D-CVTP-2015_lindy.walford.rvt




1 TREATED WATER TANK SECTION
D-804 SCALE: 1/4" = 1'-0"




2 TREATED WATER TANK SECTION
D-804 SCALE: 1/4" = 1'-0"



3 CYCLONE/BACKWASH TANK SECTION
D-804 SCALE: 1/4" = 1'-0"



4 CYCLONE/BACKWASH TANK SECTION
D-804 SCALE: 1/4" = 1'-0"



www.tetratech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Tel: 702.946.6700 Fax: 702.987.7140

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	SKU
B	02/15/17	75% SUBMITTAL TO BOR	LBW





NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
WEIR DEWATERING TREATMENT
WASTE, BACKWASH &
TREATED WATER SYSTEM
SECTIONS

Project No.: 200-01299-16015
Designed By: J. GUO
Drawn By: S. ULREY
Checked By: S. DARIAN

D-804

Copyright: Tetra Tech

2/15/2017 11:21:41 AM C:\Users\lindyl.walford\Desktop\Projects\Revit\Revit 2015\D-CVTP-2015_indy.walford.rvt



MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	SKU
B	02/15/17	75% SUBMITTAL TO BOR	LBW

NEVADA ENVIRONMENTAL RESPONSE TRUST
 HENDERSON, NEVADA

**WEIR DEWATERING TREATMENT
 WASTE, BACKWASH &
 TREATED WATER SYSTEM
 SECTIONS**

Project No.: 200-01299-16015
 Designed By: J. GUO
 Drawn By: S. ULREY
 Checked By: S. DARIAN

2/15/2017 9:56:00 AM - C:\PROJECT\SATLANTA\TAIER\01299\200-01299-16015\CAD\SHEET\FILESE-001 - ELECTRICAL LEGEND.DWG - SEIGNORET, JASON

BACKGROUND PLAN AND ONE LINE SYMBOLS			
SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION
	CONTROL SWITCH (SEL. OR P.B.) SEE CIRCUITS FOR SPECIFIC TYPE		LOW VOLTAGE DISCONNECT SWITCH
	SEE CIRCUITS FOR SPECIFIC TYPE FLOAT SWITCH - FLOW SWITCH		LOW VOLTAGE FUSE (BELOW 600V)
	MOTORIZED DAMPER		ALL STARTERS SHALL BE FULL VOLTAGE NON-REVERSING UNLESS OTHERWISE INDICATED (FVR) FULL VOLTAGE REVERSING (RV) REDUCED VOLTAGE (2S,2W) TWO SPEED, TWO WINDING
	LIMIT - PRESSURE - VACUUM SWITCH		600V, 3 POLE MOLDED CASE CIRCUIT BREAKER, FRAME & RATING AS SHOWN
	ELECTRICAL OR MECHANICAL ALTERNATOR (SEE WIRING)		SINGLE PHASE, FRACTIONAL HP MOTOR TO LOCATION INDICATED (SEE GEN. NOTE 4)
	OVERLOAD SWITCH OR DEVICE		THREE PHASE LOAD WITH IDENTIFICATION
	TERMINAL BOX		HIGH VOLTAGE FUSE (ABOVE 600 V)
	SOLENOID VALVE		TAG NO. (BALLOON) FOR DEVICE INDICATED
	PHOTOCELL LINE VOLTAGE		FOR POWER (SEE GEN. NOTE 4) 3/4" C/2" C#18 SHLD. CONDUIT AND WIRE RUN FROM DEVICE INDICATED TO LOCATION INDICATED
	ITEM NO. INTERCOM EQUIPMENT		CAPACITOR, 3 PHASE, SIZE AS INDICATED
	INTERCOMMUNICATION SYSTEM AMPLIFIER - WALL STATION - LINE BALANCE		DISCONNECT SWITCH (F) = FUSED (C) = CIRCUIT BREAKER
	DOOR INTRUSION SWITCH		MAGNETIC STARTER (BACKGROUND DRAWINGS ONLY)
	INTERCOM. SPEAKER (SURFACE MTD.)		COMBINATION MAGNETIC STARTER FUSED UNLESS NOTED (CIRCUIT BREAKER)
	INTERCOM. SPEAKER (CEILING LAY-IN)		COMBINATION LIGHTING CONTACTOR WITH HAND-OFF-AUTO SWITCH
	TELEPHONE OUTLET OR JUNCTION BOX		MANUAL STARTER (R) = REVERSING
	WELDING RECEPTACLE - NEMA L9-50R 600V, 2P, 3W, SIMPLEX		CONTROL PANEL
	INTERCOM HANDSET - SURFACE MOUNTED WITH REMOTE SPEAKER AMPLIFIER		TEMPERATURE CONTROL PANEL
	INTERCOM VOLUME CONTROL		UNIT HEATER, 1/8 HORSEPOWER
	INTERCOM SPEAKER - SURFACE MOUNTED		600 VOLT FEEDER BUS DUCT (AMPERAGE AS INDICATED)
	INTERCOM HANDSET - FLUSH MOUNTED WITH REMOTE SPEAKER AMPLIFIER		LIGHTNING ARRESTOR
	AS NOTED (LIGHTING PANEL, CONTROL PANEL, DISTRIBUTION PANEL ETC.) WALL MOUNTED		LOW VOLTAGE HOME RUNS 120/208 V 120/240 V (SEE GEN. NOTE 4)
	JUNCTION BOX		WATERTIGHT
	HEATER		WATERTIGHT AND CORROSION PROOF
	TRANSFORMER		EXPLOSION PROOF - CLASS I, DIVISION I, GROUP D
	CONDUIT WITH CONDUIT SEAL FITTING		EXPLOSION PROOF - CLASS II, DIVISION 1
	CONDUIT EXPOSED		KEYLOCK
	CONDUIT CONCEALED OR DIRECT BURIED		SMOKE DETECTOR
	DIRECT BURIED CONDUIT		EXIT LIGHT
	DIRECT BURIED CABLE		FLUORESCENT LUMINAIRE
	OVERHEAD LINE		INCANDESCENT LUMINAIRE
	UNDERGROUND CONCRETE ENCASED DUCT BANK		POLE MOUNTED LIGHT FIXTURE
	CONCRETE ENCASED DUCT BANK, WITH CABLE LOCATIONS AND SPARE DUCTS AS INDICATED ON DRAWINGS		EMERGENCY BATTERY PACK
	CABLE REEL		AIR TERMINAL
	THERMOSTAT		POLE MOUNTED SITE LIGHT FIXTURE
	BOND TO WIRE MESH		
	GROUND ROD		

CONTROL CIRCUIT & PILOT DEVICE LEGEND			
SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION
	PRESS. ACTUATED SWITCH		SELECTOR SWITCH OPERATOR WITH FUNCTION SHOWN
	FLOAT ACTUATED SWITCH		MOMENTARY PUSHBUTTON OPERATOR-NORMALLY OPEN
	FLOW ACTUATED SWITCH		MOMENTARY PUSHBUTTON OPERATOR-NORMALLY CLOSED
	TEMP. ACTUATED SWITCH		PUSHBUTTON OPERATOR WITH MUSHROOM HEAD
	LIMIT SWITCH- NORMALLY OPEN		FIELD LOCATED STOP BUTTON
	LIMIT SWITCH- NORMALLY CLOSED		MAINTAINED PUSH-PULL OPERATOR
	LIMIT SWITCH-NORMALLY CLOSED-HELD OPEN		MAINTAINED STOP-START PUSHBUTTON OPERATOR
	LIMIT SWITCH-NORMALLY OPEN-HELD CLOSED		
	LATCHING CABLE SWITCH		
	TIME-DELAY FUSE		SOLENOID OR CLUTCH
	CONTROL RELAY COIL		PUSH-TO-TEST INDICATING LIGHT
	CONTROL RELAY CONTACT-NORMALLY OPEN		MAINTAINED STOP- MOMENTARY START PUSHBUTTON (JOG)
	CONTROL RELAY CONTACT-NORMALLY CLOSED		ZERO SPEED OR ANTI- PLUGGING SWITCH
	TWO COIL LATCHING RELAY		LOCAL TERMINALS WITH EXTERNAL WIRING
	TIMING RELAY COIL		ELAPSED TIME INDICATOR
	TIMED CLOSED CONTACT ON ENERGIZATION		TIMING RELAY INSTANTANEOUS CONTACTS
	TIMED OPEN CONTACT ON ENERGIZATION		
	TIMED CLOSED CONTACT ON DE-ENERGIZATION		
	120 VAC TRANSFORMER		

WIRING DEVICE SCHEDULE		
SYMBOL	DESCRIPTION	NEMA TYPE
	125V, 2P, SIMPLEX, CLOCK HANGER	1-15 R
	125V, 2P, SIMPLEX, 3W	5-20 R
	125V, 2P, DUPLEX, 3W	5-20 R
	125/250V, 3P, SIMPLEX, 3W, RANGE TYPE	10-50 R
	20A, 120/277 V SWITCH	SPST
	20A, 120/277 V SWITCH	2PDT
	20A, 120/277 V SWITCH	3 WAY
	20A, 120/277 V SWITCH	4 WAY
	20A, 120/277 V DIMMER SWITCH	
	250V, 2P, SIMPLEX, 3W, 50A	6-50R
	125V, 2P, MULTI-RECEPTACLE	5-15R
	250V, 2P, SIMPLEX, 3W, 20A	6-20R
	600V, 2P, 3W, SIMPLEX WELDING	L9-50R
	208V, 3P, SIMPLEX, 4W, LOCKING	L14-20R
	277V, 2P, DUPLEX, 3W	7-15R

GENERAL NOTES	
NUMBER	NOTE
1.	ELECTRICAL MATERIALS AND EQUIPMENT ITEMS SHOWN IN LIGHT LINE WEIGHTS ON THE DRAWINGS ARE EXISTING ITEMS TO REMAIN. ELECTRICAL MATERIALS AND EQUIPMENT ITEMS SHOWN IN HEAVY LINE WEIGHTS ARE NEW THIS CONTRACT.
2.	ITEMS SHOWN CROSSHATCHED ON THE DRAWINGS ARE EXISTING ITEMS TO BE REMOVED.
3.	FOR ITEMS INDICATED AS "FIELD LOCATE" CHECK DRAWINGS OF OTHER TRADES (IN PARTICULAR PIPING AND STRUCTURAL) FOR INTERFERENCE AND FOR LOCATIONS OF MOUNTING FLANGES, CONNECTION POINTS, ETC.
4.	INSTALL A SINGLE CONDUCTOR INSULATED (RHW, THHN, OR XHHW) COPPER GROUND WIRE IN EACH CONDUIT, SIZE AS SHOWN ON DRAWINGS OR AS A MINIMUM PER THE NATIONAL ELECTRICAL CODE. THIS GROUND WIRE SHALL BE CONNECTED AT EACH END TO THE EQUIPMENT GROUND. CONDUIT SHALL BE 3/4" MIN.
5.	THE FOLLOWING COMPONENT IDENTIFICATION SHALL BE USED AS APPROPRIATE: (F) FIELD MOUNTED, NOT AT STARTER OR OTHER CONTROL PANELS. (S) STARTER PANEL MOUNTED. (MCP) AT MAIN CONTROL PANEL. (1) AT CONTROL PANEL NO. 1 (2) AT CONTROL PANEL NO. 2 (TCP) AT TEMPERATURE CONTROL PANEL.

www.tetra-tech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.967.7140

TETRA TECH

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	JAS

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA



WEIR DEWATERING TREATMENT
ELECTRICAL
LEGEND

Project No.:	200-01299-16015
Designed By:	J. SEIGNORET
Drawn By:	J. SEIGNORET
Checked By:	S. DARIAN

E-001

Copyright: Tetra Tech

2/15/2017 9:56:34 AM - C:\PROJECTS\ATLANTA\TAI\ER\01299\200-01299-16015\CAD\SHEETFILES\E-210 SUNRISE MOUNTAIN PUMP STATION GROUNDING PLAN.DWG - SEIGNORET, JASON



SUNRISE MOUNTAIN PUMP STATION AND CENTRAL WATER TREATMENT PLANT ELECTRICAL SITE PLAN
SCALE: 1/16" = 1'-0"

TETRA TECH
www.tetra.tech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.967.7140

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HR
C	02/15/17	75% SUBMITTAL TO BOR	JAS

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
SUNRISE MOUNTAIN PS AND CENTRAL WTP SITE PLAN



Project No.: 200-01299-16015
Designed By: J. SEIGNORET
Drawn By: J. SEIGNORET
Checked By: S. DARIAN

E-200

Copyright: Tetra Tech

2/15/2017 9:56:42 AM - C:\PROJECTS\ATLANTA\TAIER\012399\200-012399-16015\CAD\SHEETFILES\210 SUNRISE MOUNTAIN PUMP STATION GROUNDING PLAN.DWG - SEIGNORET, JASON

F
E
D
C
B
A



**SUNRISE MOUNTAIN INFLUENT TANKS
ENLARGED ELECTRICAL SITE PLAN**
SCALE: 1/4" = 1'-0"

TETRA TECH
www.tetra.tech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.997.7140

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	JAS


NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
**SUNRISE MOUNTAIN
PUMP STATION TANKS
ELECTRICAL PLAN**

Project No.: 200-01299-16015
Designed By: J. SEIGNORET
Drawn By: J. SEIGNORET
Checked By: S. DARIAN



E-201
Copyright: Tetra Tech

2/15/2017 9:56:47 AM - C:\PROJECTS\ATLANTA\TAIER\012399\200-012399-16015\CAD\SHEETFILES\E-210 SUNRISE MOUNTAIN PUMP STATION GROUNDING PLAN.DWG - SEIGNORET, JASON

F
E
D
C
B
A



**SUNRISE MOUNTAIN PUMPS
ENLARGED ELECTRICAL SITE PLAN**
SCALE: 1/4" = 1'-0"



TETRA TECH

www.tetra.tech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.997.7140

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	JAS


NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
**WEIR DEWATERING TREATMENT
PUMP STATION PUMPS
ELECTRICAL PLAN**

Project No.: 200-01299-16015
Designed By: J. SEIGNORET
Drawn By: J. SEIGNORET
Checked By: S. DARIAN

E-202


Copyright: Tetra Tech

2/15/2017 9:56:52 AM - C:\PROJECTS\ATLANTA\IER012399\200-012399-16015\CAD\SHEETFILES\E-210 SUNRISE MOUNTAIN PUMP STATION GROUNDING PLAN.DWG - SEIGNORET, JASON



**SUNRISE MOUNTAIN PUMP STATION
GROUNDING SITE PLAN**

SCALE: 1/8" = 1'-0"



GENERAL NOTES:

1. CONTRACTOR SHALL ENSURE THAT GROUND RODS AND TEST WELLS ARE NOT INSTALLED ABOVE LINER.
2. GROUND COUNTERPOISE SHALL BE ROUTED OVER LINER BERM WITHIN 2" PVC CONDUIT.



TETRA TECH

www.tetrattech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.997.7140


MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	JAS

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
**SUNRISE MOUNTAIN
PUMP STATION
GROUNDING PLAN**

Project No.:	200-012399-16015
Designed By:	J. SEIGNORET
Drawn By:	J. SEIGNORET
Checked By:	S. DARIAN


E-210

2/15/2017 9:56:58 AM - C:\PROJECT\SATLANTA\TAI\012399\200-012399-16015\CAD\SHEET\FILE\210 SUNRISE MOUNTAIN PUMP STATION GROUNDING PLAN.DWG - SEIGNORET, JASON



SITE LIGHTING ELECTRICAL PLAN

SCALE: 1/16" = 1'-0"



TETRA TECH

www.tetratech.com
 1489 West Warm Springs Road, Suite 110
 Henderson, NV 89014
 Phone: 702.946.6700 Fax: 702.967.7140

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	JAS



NEVADA ENVIRONMENTAL RESPONSE TRUST
 HENDERSON, NEVADA
 WEIR DEWATERING TREATMENT
 CENTRAL WATER
 TREATMENT PLANT
 SITE LIGHTING PLAN

Project No.: 200-01299-16015
 Designed By: J. SEIGNORET
 Drawn By: J. SEIGNORET
 Checked By: S. DARIAN

E-220

Copyright: Tetra Tech

2/15/2017 9:57:40 AM - C:\PROJECTS\ATLANTA\TAI\ER\012399\200-012399-16015\CAD\SHEETFILES\E-301 HISTORIC LATERAL PUMP STATION ELECTRICAL SITE PLAN.DWG - SEIGNORET, JASON



ELECTRICAL SITE PLAN

SCALE: 1/8" = 1'-0"

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	JAS

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA

**WEIR DEWATERING TREATMENT
HISTORIC LATERAL
PUMP STATION
ELECTRICAL SITE PLAN**

Project No.: 200-012399-16015
Designed By: J. SEIGNORET
Drawn By: J. SEIGNORET
Checked By: S. DARIAN


E-301

TETRA TECH

www.tetra-tech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.967.7140

Copyright: Tetra Tech


2/15/2017 9:57:58 AM - C:\PROJECTS\ATLANTA\TAI\ER\01299-16015\CAD\SHEETFILES\E-310 HISTORIC LATERAL PUMP STATION GROUNDING PLAN.DWG - SEIGNORET, JASON



ELECTRICAL GROUNDING SITE PLAN
SCALE: 1/8" = 1'-0"

GENERAL NOTES:

1. CONTRACTOR SHALL ENSURE THAT GROUND RODS AND TEST WELLS ARE NOT INSTALLED ABOVE LINER.
2. GROUND COUNTERPOISE SHALL BE ROUTED OVER LINER BERM WITHIN 2" PVC CONDUIT.



MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	JAS

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
**WEIR DEWATERING TREATMENT
HISTORIC LATERAL
PUMP STATION
GROUNDING PLAN**



Project No.: 200-01299-16015
Designed By: J. SEIGNORET
Drawn By: J. SEIGNORET
Checked By: S. DARIAN

E-310

TETRA TECH
www.tetra-tech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.967.7140

Copyright Tetra Tech

2/15/2017 9:58:12 AM - C:\PROJECTS\ATLANTA\TAI\TAI\012399-16015\CAD\SHEETFILES\E-210 SUNRISE MOUNTAIN PUMP STATION GROUNDING PLAN.DWG - SEIGNORET, JASON



**CENTRAL WATER TREATMENT
GROUNDING SITE PLAN**
SCALE: 1/8" = 1'-0"

- GENERAL NOTES:**
- CONTRACTOR SHALL ENSURE THAT GROUND RODS AND TEST WELLS ARE NOT INSTALLED ABOVE LINER.
 - GROUND COUNTERPOISE SHALL BE ROUTED OVER LINER BERM WITHIN 2" PVC CONDUIT.

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	JAS

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA

WEIR DEWATERING TREATMENT
CENTRAL WATER
TREATMENT PLANT
GROUNDING PLAN

Project No.: 200-01299-16015
Designed By: J. SEIGNORET
Drawn By: J. SEIGNORET
Checked By: S. DARIAN


E-410

TETRA TECH

www.tetratech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.967.7140

Copyright: Tetra Tech

2/15/2017 9:58:18 AM - C:\PROJECTS\ATLANTA\TAIER\012399\200-012399-16015\CAD\SHEETFILES\210 SUNRISE MOUNTAIN PUMP STATION GROUNDING PLAN.DWG - SEIGNORET, JASON



**CENTRAL WATER TREATMENT
GROUNDING SITE PLAN**
SCALE: 1/8" = 1'-0"

- GENERAL NOTES:**
- CONTRACTOR SHALL ENSURE THAT GROUND RODS AND TEST WELLS ARE NOT INSTALLED ABOVE LINER.
 - GROUND COUNTERPOISE SHALL BE ROUTED OVER LINER BERM WITHIN 2" PVC CONDUIT.

TETRA TECH
www.tetratech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.997.7140

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	JAS




NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
**WEIR DEWATERING TREATMENT
CENTRAL WATER
TREATMENT PLANT
GROUNDING PLAN**

Project No.: 200-012399-16015
Designed By: J. SEIGNORET
Drawn By: J. SEIGNORET
Checked By: S. DARIAN

E-411
Copyright: Tetra Tech

2/15/2017 9:58:23 AM - C:\PROJECTS\ATLANTA\TAIER\012399\200-012399-16015\CAD\SHEETFILES\210 SUNRISE MOUNTAIN PUMP STATION GROUNDING PLAN.DWG - SEIGNORET, JASON

F
E
D
C
B
A




HYDRO-CYCLONES ENLARGED ELECTRICAL SITE PLAN
SCALE: 1/4" = 1'-0"

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	JAS

NEVADA ENVIRONMENTAL RESPONSE TRUST
 HENDERSON, NEVADA
 WEIR DEWATERING TREATMENT
 HYDRO-CYCLONES
 ELECTRICAL PLAN

Project No.: 200-01299-16015
 Designed By: J. SEIGNORET
 Drawn By: J. SEIGNORET
 Checked By: S. DARIAN

2/15/2017 9:58:28 AM - C:\PROJECTS\ATLANTA\TAI\ER\012399\200-012399-16015\CAD\SHEETFILES\E-210 SUNRISE MOUNTAIN PUMP STATION GROUNDING PLAN.DWG - SEIGNORET, JASON



MULTI-MEDIA FILTERS ENLARGED ELECTRICAL SITE PLAN
SCALE: 1/4" = 1'-0"

- GENERAL NOTES:**
- CONTROL PANEL PROVIDED BY MULTI-MEDIA FILTER MANUFACTURER. ELECTRICAL CONTRACTOR SHALL BE RESPONSIBLE FOR ELECTRICAL CONNECTIONS SHOWN ON PLAN.

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	JAS

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA

WEIR DEWATERING TREATMENT
MULTI-MEDIA
FILTERS
ELECTRICAL PLAN

Project No.: 200-012399-16015
Designed By: J. SEIGNORET
Drawn By: J. SEIGNORET
Checked By: S. DARIAN


E-601

TETRA TECH
www.tetra.tech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.967.7140

Copyright Tetra Tech

2/15/2017 9:58:32 AM - C:\PROJECTS\ATLANTA\TAIER\012399\200-012399-16015\CAD\SHEETFILES\E-210 SUNRISE MOUNTAIN PUMP STATION GROUNDING PLAN.DWG - SEIGNORET, JASON

F
E
D
C
B
A



ION EXCHANGE ENLARGED ELECTRICAL SITE PLAN

SCALE: 1/4" = 1'-0"

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	JAS


NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
**WEIR DEWATERING TREATMENT
ION EXCHANGE
ELECTRICAL PLAN**

Project No.: 200-01299-16015
Designed By: J. SEIGNORET
Drawn By: J. SEIGNORET
Checked By: S. DARIAN

E-701




www.tetra-tech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.997.7140




Copyright: Tetra Tech

2/15/2017 9:58:37 AM - C:\PROJECTS\ATLANTA\TAIER\01299\200-01299-16015\CAD\SHEETFILES\210 SUNRISE MOUNTAIN PUMP STATION GROUNDING PLAN.DWG - SEIGNORET, JASON



WASTE TANKS ENLARGED ELECTRICAL SITE PLAN

SCALE: 1/4" = 1'-0"



TETRA TECH

www.tetratech.com
 1489 West Warm Springs Road, Suite 110
 Henderson, NV 89014
 Phone: 702.946.6700 Fax: 702.997.7140

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	JAS

NEVADA ENVIRONMENTAL RESPONSE TRUST
 HENDERSON, NEVADA
**WEIR DEWATERING TREATMENT
 TANKS
 ELECTRICAL PLAN**


Project No.: 200-01299-16015
 Designed By: J. SEIGNORET
 Drawn By: J. SEIGNORET
 Checked By: S. DARIAN

E-801

Copyright: Tetra Tech


2/15/2017 9:58:43 AM - C:\PROJECTS\ATLANTA\TAI\ER\012399\200-012399-16015\CAD\SHEETFILES\E-210 SUNRISE MOUNTAIN PUMP STATION GROUNDING PLAN.DWG - SEIGNORET, JASON

F
E
D
C
B
A



WASTE PUMPS ENLARGED ELECTRICAL SITE PLAN

SCALE: 1/4" = 1'-0"



www.tetratech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.997.7140

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	JAS

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
**WEIR DEWATERING TREATMENT
BACKWASH AND
WASTE PUMPS
ELECTRICAL PLAN**



Project No.: 200-01299-16015
Designed By: J. SEIGNORET
Drawn By: J. SEIGNORET
Checked By: S. DARIAN

E-802

Copyright Tetra Tech

2/15/2017 9:58:47 AM - C:\PROJECTS\ATLANTA\TAI\ER\012399\200-012399-16015\CAD\SHEETFILES\E-210 SUNRISE MOUNTAIN PUMP STATION GROUNDING PLAN.DWG - SEIGNORET, JASON

F
E
D
C
B
A



TRANSFER PUMPS ENLARGED ELECTRICAL SITE PLAN

SCALE: 1/4" = 1'-0"



www.tetratech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.997.7140

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	JAS


NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
**CENTRAL WATER TREATMENT PLANT
PUMPS ELECTRICAL PLAN**

Project No.: 200-01299-16015
Designed By: J. SEIGNORET
Drawn By: J. SEIGNORET
Checked By: S. DARIAN

E-803


Copyright: Tetra Tech

2/15/2017 9:58:52 AM - C:\PROJECTS\ATLANTA\TAI\ER\012399\200-012399-16015\CAD\SHEETFILES\E-210 SUNRISE MOUNTAIN PUMP STATION GROUNDING PLAN.DWG - SEIGNORET, JASON



TANKS ENLARGED ELECTRICAL SITE PLAN

SCALE: 1/4" = 1'-0"



www.tetra.tech.com
 1489 West Warm Springs Road, Suite 110
 Henderson, NV 89014
 Phone: 702.946.6700 Fax: 702.967.7140

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	JAS


NEVADA ENVIRONMENTAL RESPONSE TRUST
 HENDERSON, NEVADA
**WEIR DEWATERING TREATMENT
 TANKS
 ELECTRICAL PLAN**

Project No.: 200-01299-16015
 Designed By: J. SEIGNORET
 Drawn By: J. SEIGNORET
 Checked By: S. DARIAN

E-804

Copyright: Tetra Tech

2/15/2017 9:59:02 AM - C:\PROJECTS\ATLANTA\TAI\ER\012399\200-012399-16015\CAD\SHEETFILES\E-1401 HISTORIC LATERAL SINGLE LINE DIAGRAM.DWG - SEIGNORET, JASON



- NOTES:
- 1 5-4"C (3-400 KCMIL, 1#4/0 KCMIL)
 - 2 1 1/4"C(3#6, 1#10)
 - 3 2 RUNS 3"C(3#350 KCMIL, 1#1)
 - 4 2 1/2"C (3#4/0, 1#4)
 - 5 1 1/2"C (3#1, 1#6)
 - 6 1"C (2#12)

DP-1 SWITCHGEAR LOAD CALCULATION			
LOADNAME	DEMAND LOAD	CONNECTED LOAD	
PU-2A/2B/2C PUMPS	1050HP; 967KVA	1050HP; 967KVA	
PANEL DP-2	40KVA	40KVA	
TOTAL	1007KVA 1211A	1007KVA 1211A	

**HISTORIC LATERAL PUMP STATION
SINGLE-LINE DIAGRAM**

NO SCALE



www.tetratech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.967.7140

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	JAS


NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
**WEIR DEWATERING TREATMENT
HISTORIC LATERAL
SINGLE LINE DIAGRAM**

Project No.: 200-01299-16015
Designed By: J. SEIGNORET
Drawn By: J. SEIGNORET
Checked By: S. DARIAN

E-1401

Copyright Tetra Tech

2/15/2017 9:59:12 AM - C:\PROJECTS\ATLANTA\TAIER\01299-16015\CAD\SHEETFILES\E-1402 CENTRAL WATER TREATMENT PLANT SINGLE LINE DIAGRAM.DWG - SEIGNORET, JASON



- NOTES:**
- 1 6-4°C (3-400 KCMIL, 1#250 KCMIL)
 - 2 1 1/4°C(3#6, 1#10)
 - 3 1°C(3#10, 1#12)
 - 4 1°C(3#12, 1#12)
 - 5 1 1/4°C (3#4, 1#8)
 - 6 1°C (3#8, 1#10)
 - 7 2 1/2°C (3#4/0, 1#4)
 - 8 1 1/2°C (3#1, 1#6)
 - 9 2 RUNS 2 1/2°C(3#4/0, 1#2)
 - 10 1°C (2#12)

DP-2 SWITCHGEAR LOAD CALCULATION		
LOADNAME	DEMAND LOAD	CONNECTED LOAD
PU-1A/1B/1C PUMPS	900HP; 829KVA	900HP; 829KVA
PU-5A/5B/5C PUMPS	150HP; 138KVA	150HP; 138KVA
PU-6A/6B/6C/6D PUMPS	80HP; 73.7KVA	80HP; 73.7KVA
PU-7A/7B PUMPS	30HP; 27.6KVA	30HP; 27.6KVA
MX-1A/1B/1C/1D MIXERS	40HP; 36.8KVA	40HP; 36.8KVA
MX-2A/2B/2C/2D MIXERS	40HP; 36.8KVA	40HP; 36.8KVA
MX-3A/3B/3C/3D MIXERS	40HP; 36.8KVA	40HP; 36.8KVA
PU-3A/3B/3C PUMPS	15HP; 13.8KVA	15HP; 13.8KVA
PU-4A/4B PUMPS	6HP; 5.53KVA	6HP; 5.53KVA
PANEL DP-2	69.3KVA	69.3KVA
TOTAL	1304KVA 1568A	1304KVA 1568A

SUNRISE MOUNTAIN PUMP STATION AND CENTRAL TREATMENT PLANT SINGLE-LINE DIAGRAM
NO SCALE

www.tetrattech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.967.7140

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	JAS

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA

WEIR DEWATERING TREATMENT
CENTRAL WATER
TREATMENT PLANT
SINGLE LINE DIAGRAM

Project No.:

200-01299-16015

Designed By:

J. SEIGNORET

Drawn By:

J. SEIGNORET

Checked By:

S. DARIAN

E-1402

2/15/2017 9:59:42 AM - C:\PROJECTS\ATLANTA\TAIER\01299\200-01299-16015\CAD\SHEETFILES\E-1403 PANEL BOARD SCHEDULES.DWG - SEIGNORET, JASON

F
E
D
C
B
A

PANELBOARD: DP-1												
SERVICE: 480/277V, 3 PH, 3 W + GND												
BUS SIZE: 225A			LOAD:			NOTES: NEMA 3R			LOCATION: HISTORIC LATERAL PUMP STATION			
MAIN DEVICE: 225A			CONN. 7.2 kVA									
65,000 AIC			DEM. 7.2 kVA									
MOUNTING: SURFACE			DEM. 8.7 Amps									
CKT #	TRIP/POLE	NOTES	CONNECTED LOAD (VA)			CIRCUIT DESCRIPTION	NOTES	TRIP/POLE	CKT #			
			PHASE A	PHASE B	PHASE C							
1	20A/3		FCV-3010	2,400					100A/3	2		
3	-				2,400				-	4		
5	-					2,400			-	6		
7	20A/3								-	8		
9	-								-	10		
11	-								-	12		
13	20A/3								-	14		
15	-								-	16		
17	-								-	18		
19	60A/3								-	20		
21	-								-	22		
23	-								-	24		
25	-								-	26		
27	-								-	28		
29	-								-	30		
31	-								-	32		
33	-								-	34		
35	-								-	36		
37	-								-	38		
39	-								-	40		
41	-								-	42		
TOTAL CONNECTED LOADS:			2,400	0	2,400	0	2,400	0				

PANELBOARD: DP-2												
SERVICE: 480/277V, 3 PH, 3 W + GND												
BUS SIZE: 225A			LOAD:			NOTES: NEMA 3R			LOCATION: CENTRAL WATER PLANT			
MAIN DEVICE: 225A			CONN. 69.3 kVA									
65,000 AIC			DEM. 69.3 kVA									
MOUNTING: SURFACE			DEM. 83.4 Amps									
CKT #	TRIP/POLE	NOTES	CONNECTED LOAD (VA)			CIRCUIT DESCRIPTION	NOTES	TRIP/POLE	CKT #			
			PHASE A	PHASE B	PHASE C							
1	90A/3		MULTI-MEDIA FILTER BLOWER SKID	11,000	800				20A/3	2		
3	-				11,000	800			-	4		
5	-					11,000	800		-	6		
7	20A/3		FCV-7010	800	800				20A/3	8		
9	-					800	800		-	10		
11	-						800	800	-	12		
13	20A/3		FCV-7020	800	2,500				30A/3	14		
15	-						800	2,500	-	16		
17	-							800	2,500	18		
19	60A/3		XFMR T-3 (PANEL LA-3)	5,600	800				20A/3	20		
21	-						5,600	800	-	22		
23	-							5,600	800	24		
25	-								-	26		
27	-								-	28		
29	-								-	30		
31	-								-	32		
33	-								-	34		
35	-								-	36		
37	-								-	38		
39	-								-	40		
41	-								-	42		
TOTAL CONNECTED LOADS:			18,200	4,900	18,200	4,900	18,200	4,900				


PANELBOARD: LA-1												
SERVICE: 208/120V, 3 PH, 4 W + GND												
BUS SIZE: 100A			LOAD:			NOTES: NEMA 3R			LOCATION: HISTORIC LATERAL PUMP STATION			
MAIN DEVICE: 100A			CONN. 5.1 kVA									
SFC RATING: 10,000AIC			DEM. 5.1 kVA									
MOUNTING: SURFACE			DEM. 14.2 Amps									
CKT #	TRIP/POLE	NOTES	CONNECTED LOAD (VA)			CIRCUIT DESCRIPTION	NOTES	TRIP/POLE	CKT #			
			PHASE A	PHASE B	PHASE C							
1	20A/1		FE/FIT-3010	180	180				20A/1	2		
3	20A/1		AE/AIT-3010		180	1,200			20A/1	4		
5	20A/1		LE/LIT-3020			180			20A/1	6		
7	20A/1		SITE LIGHTING	800					20A/1	8		
9	20A/1		SITE LIGHTING		800				20A/1	10		
11	20A/1		SITE LIGHTING			800			20A/1	12		
13	20A/1		SITE LIGHTING	800					20A/1	14		
15	-								-	16		
17	-								-	18		
19	-								-	20		
21	-								-	22		
23	-								-	24		
25	-								-	26		
27	-								-	28		
29	-								-	30		
31	20A/1								20A/1	32		
33	20A/1								20A/1	34		
35	20A/1								20A/1	36		
37	-								-	38		
39	-								-	40		
41	-								-	42		
TOTAL CONNECTED LOADS:			1,780	180	980	1,200	980	0				

PANELBOARD: LA-2A												
SERVICE: 208/120V, 3 PH, 4 W + GND												
BUS SIZE: 200A			LOAD:			NOTES: NEMA 3R			LOCATION: CENTRAL WATER PLANT			
MAIN DEVICE: 200A			CONN. 6.7 kVA									
SFC RATING: 10,000AIC			DEM. 6.7 kVA									
MOUNTING: SURFACE			DEM. 18.5 Amps									
CKT #	TRIP/POLE	NOTES	CONNECTED LOAD (VA)			CIRCUIT DESCRIPTION	NOTES	TRIP/POLE	CKT #			
			PHASE A	PHASE B	PHASE C							
1	20A/1		PE/PIT-4010	180	180				20A/1	2		
3	20A/1		AE/AIT-4010		180	180			20A/1	4		
5	20A/1		FE/FIT-4010			180	180		20A/1	6		
7	20A/1		PE/PIT-5010	180	180				20A/1	8		
9	20A/1		PE/PIT-6010		180	180			20A/1	10		
11	20A/1		FE/FIT-7010			180	180		20A/1	12		
13	20A/1		PE/PIT-7010	180	180				20A/1	14		
15	20A/1		PE/PIT-7011		180	180			20A/1	16		
17	20A/1		PE/PIT-7020			180	180		20A/1	18		
19	20A/1		PE/PIT-7021	180	180				20A/1	20		
21	20A/1		LE/LIT-8010		180	180			20A/1	22		
23	20A/1		LE/LIT-8020			180	180		20A/1	24		
25	20A/1		LE/LIT-8030	180	180				20A/1	26		
27	20A/1		FE/FIT-8040		180	180			20A/1	28		
29	20A/1		FE/FIT-8050			180	180		20A/1	30		
31	20A/1		AE/AIT-7010		180	180			20A/1	32		
33	20A/1		AE/AIT-6010		180	180			20A/1	34		
35	20A/1		FE/FIT-2010			180	180		20A/1	36		
37	20A/1		AE/AIT-2010	180					30A/3	38		
39	20A/1		LE/LIT-2020		180				-	40		
41	-								-	42		
TOTAL CONNECTED LOADS:			1,260	1,080	1,260	1,080	1,080	900				

PANELBOARD: LA-2B												
SERVICE: 208/120V, 3 PH, 4 W + GND												
BUS SIZE: 100A			LOAD:			NOTES: NEMA 3R			LOCATION: SUNRISE MOUNTAIN			
MAIN DEVICE: 100A			CONN. 16.8 kVA									
SFC RATING: 10,000AIC			DEM. 13.4 kVA									
MOUNTING: SURFACE			DEM. 37.3 Amps									
CKT #	TRIP/POLE	NOTES	CONNECTED LOAD (VA)			CIRCUIT DESCRIPTION	NOTES	TRIP/POLE	CKT #			
			PHASE A	PHASE B	PHASE C							
1	20A/1		MASTER CONTROL PANEL (MCP)	1,200	1,200				20A/1	2		
3	20A/1		LE/LIT-8021		180	2,640			30A/1	4		
5	20A/1		LE/LIT-8031			180	2,640		30A/1	6		
7	20A/1		LE/LIT-8011	180	2,640				30A/1	8		
9	20A/1		LE/LIT-8012		180	800			20A/1	10		
11	20A/1		LE/LIT-8013			180	800		20A/1	12		
13	20A/1		SITE LIGHTING	1,200	800				20A/1	14		
15	20A/1		SITE LIGHTING		1,200	800			20A/1	16		
17	-								-	18		
19	-								-	20		
21	-								-	22		
23	-								-	24		
25	-								-	26		
27	-								-	28		
29	-								-	30		
31	-								-	32		
33	-								-	34		
35	-								-	36		
37	-								-	38		
39</												


2/15/2017 9:59:57 AM - C:\PROJECTS\ATLANTA\TAI\01299-1601\CAD\SHEETFILES-1601\ELECTRICAL DETAILS.DWG - SEIGNORET, JASON

GROUND STORAGE TANK LIGHT FIXTURE DETAIL




DETAIL 8
SCALE: NTS

AIR TERMINAL HANDRAILING MOUNT




DETAIL 9
SCALE: NTS

TYPICAL YARD LIGHTING FIXTURE




DETAIL 10
SCALE: NTS

GROUND ROD INSPECTION TEST WELL INSTALLATION




DETAIL 11
SCALE: NTS

MOTOR OPERATED VALVE




DETAIL 17
SCALE: NTS

LIGHT POLE STANDARD FOUNDATION




DETAIL 13
SCALE: NTS

AIR TERMINAL AND BASE



DETAIL 14
SCALE: NTS

CONTROL PANEL MOUNTING



DETAIL 16
SCALE: NTS


MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HR
C	02/15/17	75% SUBMITTAL TO BOR	JAS

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
WEIR DEWATERING TREATMENT
**ELECTRICAL
DETAILS**

Project No.: 200-01299-16015
Designed By: J. SEIGNORET
Drawn By: J. SEIGNORET
Checked By: S. DARIAN

2/15/2017 10:00:07 AM - O:\PROJECTS\ATLANTA\TAIER01299\200-01299-16015\CAD\SHEETFILES\1502 ELECTRICAL DETAILS.DWG - SEIGNORET, JASON


INSTRUMENT TAG



- NOTE:
1. STAINLESS STEEL TAG
 2. STAINLESS STEEL CHAIN
 3. BLACK LETTERING
 4. INSTALL TAG ON ELEMENTS AND INSTRUMENTS.

DETAIL 35
SCALE: NTS


FEEDER BRANCH CIRCUIT RACEWAY LABELS



- NOTE:
1. NO LABELING REQUIRED FOR RACEWAYS WITH READILY IDENTIFIABLE TERMINATIONS WITHIN THE SAME ROOM
 2. IN ACCESSIBLE CEILING SPACES AND EXPOSED IN UNFINISHED AREAS, LABEL CONDUIT WITH PANEL AND CIRCUIT NUMBERS OF CONDUCTORS ROUTED THROUGH THE CONDUIT. LABEL CONDUIT AT WALL PENETRATIONS AND CONNECTIONS TO ALL PANELS, JUNCTION BOXES, AND EQUIPMENT SERVED.


DETAIL 36
SCALE: NTS

ADHESIVE CABLE HOLDER



DETAIL 3
SCALE: NTS


MAGNETIC FLOW METER



- NOTES:
1. LOCATION FOR TRANSMITTERS NOT INTEGRALLY MOUNTED ON THE FLOW METER.
 2. GROUND MAGMETER AS INSTRUCTED BY THE VENDOR.
 3. INSTALL SEPARATELY MOUNTED INDICATOR. NOT REQUIRED ON INDICATING WALL MOUNTED TRANSMITTERS.
 4. POWER WIRING. 1" C POWER AS SUPPLIED BY MANUFACTURER.
 5. SIGNAL WIRING. 1" C SIGNAL AS SUPPLIED BY MANUFACTURER.


DETAIL 27
SCALE: NTS

EMERGENCY PUSH STOP BUTTON



DETAIL 21
SCALE: NTS

VERTICAL AND HORIZONTAL CONDUIT RACKS AND HANGERS



DETAIL 6
SCALE: NTS

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	JAS


NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
WEIR DEWATERING TREATMENT
**ELECTRICAL
DETAILS**

Project No.: 200-01299-16015
Designed By: J. SEIGNORET
Drawn By: J. SEIGNORET
Checked By: S. DARIAN

Copyright: Tetra Tech


2/15/2017 10:00:17 AM - O:\PROJECTS\ATLANTA\TAIER01299\200-01299-16015\CAD\SHEETFILES\E-1503 ELECTRICAL DETAILS.DWG - SEIGNORET, JASON

FENCE POST/GATE BONDING DETAIL




DETAIL 24
SCALE: NTS

FLOW SWITCH EYE/SOWER WASH STATION DETAIL




DETAIL 33
SCALE: NTS

INSTRUMENT SUNSHADE DETAIL



DETAIL 34
SCALE: NTS

MOTOR CONDUIT DETAIL



DETAIL 29
SCALE: NTS

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	JAS

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
WEIR DEWATERING TREATMENT
ELECTRICAL
DETAILS

Project No.: 200-01299-16015
Designed By: J. SEIGNORET
Drawn By: J. SEIGNORET
Checked By: S. DARIAN

2/13/2017 2:36:50 PM - D:\PROJECTS\NERTL\09\CAD\FROMPROJECT\DIRECTOR\I-001 - INSTRUMENTATION LEGEND.DWG - SAITO, JON

GRAPHIC SYMBOL FOR INSTRUMENTATION ITEMS			
	LOGIC IN PLC DISPLAYED ON OIP & SCADA (INCLUDING INPUTS & OUTPUTS)		TEMPERATURE SWITCH-NC
	LOGIC IN PLC		CONTROL RELAY CONTACT-NORMALLY OPEN
	FIELD OR LOCALLY MOUNTED DEVICE		CONTROL RELAY CONTACT-NORMALLY CLOSED
	MASTER CONTROL PANEL FUNCTION (DASHED LINE - NOT ACCESSIBLE, SOLID LINE - OPERATOR ACCESSIBLE)		LIGHTNING ARRESTOR
	LOCAL CONTROL PANEL FUNCTION (DASHED LINE - NOT ACCESSIBLE, SOLID LINE - OPERATOR ACCESSIBLE)		ELAPSED TIME INDICATOR
	PANEL MOUNTED INDICATOR		PUSH-TO-TEST INDICATING LIGHT
	INTERLOCKING		BATTERY
	EXCLUSIVE OR		SECONDARY TRANSFORMER
	ALTERNATOR		VARIABLE RESISTOR
	OR		RESISTOR
	AND		MOLDED CASE CIRCUIT BREAKER
	MOTOR STARTER		SPEED SWITCH
	VARIABLE FREQUENCY DRIVE		MOMENTARY PUSHBUTTON OPERATOR- NORMALLY CLOSED
	DIGITAL INPUT TO PROGRAMMABLE CONTROLLER		MOMENTARY PUSHBUTTON OPERATOR- NORMALLY OPEN
	DIGITAL OUTPUT TO PROGRAMMABLE CONTROLLER		SELECTOR SWITCH-NORMALLY OPEN
	ANALOG INPUT TO PROGRAMMABLE CONTROLLER		PUSHBUTTON OPERATOR WITH MUSHROOM HEAD
	ANALOG OUTPUT TO PROGRAMMABLE CONTROLLER		SOLENOID OR CLUTCH
	FLOAT SWITCH		THERMAL OVERLOAD
	PARSHALL FLUME		A-C SURGE PROTECTOR
	MIXER		HORN
	SEAL		FIELD LOCATED
	OFF PAGE CONNECTOR		TERMINAL POINT
	PROCESS MACHINERY MOTOR		TERMINAL POINT ARROW
	VENTURI OR INSERT FLOW TUBE		LOW VOLTAGE FUSE
	IN-LINE FLOW ELEMENT (PROPELLER TYPE)		CIRCUIT BREAKER WITH STAB CONNECTION
	IN-LINE FLOW ELEMENT (MAGNETIC TYPE)		TWO COIL LATCHING RELAY
	IN-LINE FLOW ELEMENT (ULTRA SONIC)		RECEPTACLE
	FLOW ORIFICE		SELECTOR SWITCH OPERATOR WITH FUNCTION SHOWN
	TURBIDIMETER		MAINTAINED PUSH-PULL OPERATOR
	ROTAMETER		MAINTAINED STOP-START PUSHBUTTON OPERATOR
	CENTRIFUGAL PUMP		CONTROL POWER TRANSFORMER
	PROGRESSIVE CAVITY PUMP		DIODE RECTIFIER OR D-C SURGE PROTECTOR
	ULTRASONIC LEVEL SENSOR		LIMIT SWITCH - NORMALLY OPEN
	GENERAL USE DISCONNECTING SWITCH		LIMIT SWITCH - NORMALLY OPEN - HELD CLOSED
	TIMED CLOSED CONTACT ON ENERGIZATION		LIMIT SWITCH - NORMALLY CLOSED - HELD OPEN
	TIMED OPEN CONTACT ON ENERGIZATION		LIMIT SWITCH - NORMALLY CLOSED
	TIMED OPEN CONTACT ON DE-ENERGIZATION		CURRENT / PNEUMATIC CONVERTER
	TIMED CLOSED CONTACT ON DE-ENERGIZATION		
	FLOAT ACTUATED SWITCH-NO		
	FLOAT ACTUATED SWITCH-NC		
	PRESSURE ACTUATED SWITCH-NC		
	PRESSURE ACTUATED SWITCH-NO		
	FLOW ACTUATED SWITCH-NO		
	FLOW ACTUATED SWITCH-NC		
	TEMPERATURE SWITCH-NO		

GRAPHIC SYMBOLS FOR VALVES	
	STROKE OR POSITION ACTUATOR CYLINDER (OPEN-SHUT)
	STROKE OR POSITION ACTUATOR CYLINDER (THROTTLING)
	PNEUMATIC OPERATED (OPEN-SHUT)
	PNEUMATIC OPERATED (THROTTLING)
	MOTOR OPERATED (THROTTLING)
	MOTOR OPERATED (OPEN-SHUT)
	KNIFE GATE VALVE
	SLUICE GATE
	AIR SET ASSEMBLY
	BALL VALVE
	GLOBE VALVE
	GATE VALVE OR KNIFE GATE
	CHECK VALVE
	PLUG VALVE
	BUTTERFLY VALVE, DAMPER OR LOUVER
	PRESSURE REDUCING VALVE
	TWO-WAY SOLENOID VALVE OPERATOR
	ELECTRONICALLY CONTROLLED CHECK VALVE
	TWO-WAY SOLENOID VALVE OPERATOR-DETENTED
	THREE-WAY SOLENOID VALVE OPERATOR
	FOUR-WAY SOLENOID VALVE OPERATOR
	PRESSURE RELIEF VALVE
	PIPE REDUCER (CONCENTRIC)
	PIPE REDUCER (ECCENTRIC)
	STATIC MIXER
	FLEXIBLE CONNECTOR

INSTRUMENTATION LINE SYMBOLS	
	ELECTRICAL SIGNAL
	AIR LINE
	HYDRAULIC SIGNAL
	ELECTROMAGNETIC OR SONIC SIGNAL
	SOFTWARE SIGNAL
	CONNECTION TO PROCESS, OR MECHANICAL LINK
	ETHERNET CABLE (CAT 5E)
	FIBER OPTIC CABLE

PIPING ABBREVIATIONS			
INSULATION - CC		TRACING - DD	
IH	HOT INSULATION	ET	ELECTRIC TRACING
IC	COLD INSULATION	ST	STEAM TRACING
PP	PERSONNEL PROTECTION	WT	WATER TRACING
FP	FREEZE PROTECTION	XJ	JACKETED, DENOTE TYPE
X	NO INSULATION		


PIPE MATERIAL LEGEND - AAAA	
CPVC	CHLORINATED POLYVINYL CHLORIDE
CS	CARBON STEEL
CU	COPPER
CUT	COPPER TUBING
HDPE	HIGH-DENSITY POLYETHYLENE
HOSE	RUBBER HOSE
HTH	HIGH TEMPERATURE HOSE
GS	GALVANIZED STEEL
PRID	PVC COATED RIGID CONDUIT
PT	PLASTIC TUBING (NYLON / TYGON TUBING)
PVC	POLYVINYL CHLORIDE
RID	RIGID CONDUIT
SS04	STAINLESS STEEL, 304
SS16	STAINLESS STEEL, 316

PIPE FLUID LEGEND - BBBB	
RW	RAW WATER
CE	CYCLONE EFFLUENT
FW	FILTERED WATER
TW	TREATED WATER
BW	BACKWASH WATER
RS	RISING WATER
BWW	BACKWASH WASTE
CW	CYCLONE WASTE
AS	AIR SOURING

I.S.A. STANDARD LETTER FUNCTIONS		
SYMBOL	FIRST LETTER	SUCCEEDING LETTERS
A	ANALYSIS, ANALOG	ALARM
B	BURNER, FLAME	BATCH, BUTTON
C	CONDUCTIVITY, COMMAND	CONTROL (FEEDBACK TYPE)
D	DENSITY, SPECIFIC GRAVITY	
E	VOLTAGE	PRIMARY ELEMENT
F	FLOW RATE	RATIO
G	GAGING	GLASS
H	HAND, MANUAL	HIGH
I	CURRENT	INDICATE
J	POWER	SCAN
K	TIME, TIME SCHEDULE	CONTROL (NO FEEDBACK)
L	LEVEL, LIGHT	LOW
M	MOISTURE, HUMIDITY	MIDDLE, MODULATE
N		
O	OVERLOAD	ORIFICE
P	PRESSURE, VACUUM, PUSH	POINT
Q	QUANTITY	TOTALIZE, INTEGRATE
R	RADIOACTIVITY	RECORD, PRINT, RECEIVE
S	SPEED, FREQUENCY, SOLENOID	SWITCH
T	TEMPERATURE, TURBIDITY	TRANSMIT, TRANSFORM
U	MULTIVARIABLE	MULTIFUNCTION
V	VIBRATION, VISCOSITY	VALVE, DAMPER, LOUVER
W	WEIGHT, FORCE	
X		
Y	EVENT, STATE, PRESENCE	RELAY, COMPUTE
Z	POSITION	DRIVE, ACTUATE

INSTRUMENT DESIGNATIONS		SAMPLE
	AHC - AUTO / HOLD / CLOSE AM - AUTO / MANUAL DEV - DEVIATION HOA - HAND / OFF / AUTO HOR - HAND / OFF / REMOTE LOR - LOCAL / OFF / REMOTE LOS - LOCKOUT STOP LR - LOCAL / REMOTE MOA - MANUAL / OFF / AUTO OO - ON / OFF OCA - OPEN / CLOSE / AUTO	OSC - OPEN / STOP / CLOSE POT - POTENTIOMETER RL - RAISE / LOWER RSL - RAISE / STOP / LOWER RST - RESET SD - SHUTDOWN SEL - SELECT SP - SETPOINT SS - START / STOP STR - START STP - STOP
		LOCAL / OFF / REMOTE LOR HS 210A HAND SWITCH INSTRUMENT TAG

ANALYTICAL		SAMPLE
	AE - ALKALINITY CL2 - CHLORINE CONCENTRATION COM - COMBUSTIBLE GAS CON - CONDUCTIVITY DO - DISSOLVED OXYGEN H2S - HYDROGEN SULFIDE LEL - LOWER EXPLOSIVE LIMIT O2 - OXYGEN CONCENTRATION O3 - OZONE	PH AI 204A
	AIT - ANALYTICAL INSTRUMENT TAG	
	AI - ANALYTICAL INSTRUMENT TAG	
	ORP - OXYGEN / REDUCTION POTENTIAL	
	PH - HYDROGEN ION CONCENTRATION	
	SO2 - SULFUR DIOXIDE	
	TH - TOTAL HARDNESS	
	TURB - TURBIDITY	
	UV - ULTRAVIOLET	



TETRA TECH

www.tetra.tech.com
 1488 West Warm Springs Road, Suite 110
 Henderson, NV 89014
 Phone: 702.946.6700 Fax: 702.957.7140

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	JS
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	JMS
C	02/15/17	75% SUBMITTAL TO BOR	JMS

NEVADA ENVIRONMENTAL RESPONSE TRUST
 HENDERSON, NEVADA

AP-5 POND PHASE II
 PROJECT IMPLEMENTATION

**INSTRUMENTATION
 LEGEND**

Project No.:	200-01299-16002
Designed By:	J. COWARD
Drawn By:	J. SEIGNORET
Checked By:	D. BURGER

I-001


Copyright: Tetra Tech

NERT Weir L09 Process Interlock Matrix

Interlock ID	Input Device	Description	Output	Condition	Value	EngUnits	Action	Tag	Description
1	AI2010	SMPS Influent TSS	Alarm	>=	135	PPM	1	CLOSE	SMPS Influent Tank Feed FCV
2	FI2010	SMPS Influent Tank Flow	Alarm	>=	6900	gpm	2	STOP	SMPS Discharge Pump 1 PU-1A
3	LI2020/LI2021	Influent Tank Level	Alarm	LOW LOW	1	N/A	3	STOP	SMPS Discharge Pump 2 PU-1B
4	LI2020/LI2021	Influent Tank Level	Alarm	HIGH HIGH	1	N/A	4	STOP	SMPS Discharge Pump 3 PU-1C
5	AI3010	HLPS Influent TSS	Alarm	>=	135	PPM	5	CLOSE	HLPS Influent Tank Feed FCV
6	FI3010	HLPS Influent Tank Flow	Alarm	>=	6900	gpm	6	STOP	HLPS Discharge Pump 1 PU-2A
7	LI3020/LI3021	Influent Tank Level	Alarm	LOW LOW	1	N/A	7	STOP	HLPS Discharge Pump 2 PU-2B
8	LI3020/LI3021	Influent Tank Level	Alarm	HIGH HIGH	1	N/A	8	STOP	HLPS Discharge Pump 3 PU-2C
9	AI4010	CWTP Combined Influent TSS	Alarm	>=	135	PPM	9	CLOSE	CWTP Combined Influent FCV
10	LI8010/LI8011	Treated Water Tank Level	Alarm	LOW LOW	1	N/A	10	STOP	Treated Water Pump PU-6A
11	LI8020/LI8021	Cyclone Waste Tank Level	Alarm	LOW LOW	1	N/A	11	STOP	Treated Water Pump PU-6B
12	LI8030/LI8031	Backwash Waste Tank Level	Alarm	LOW LOW	1	N/A	12	STOP	Treated Water Pump PU-6C
13	LI8060/LI8061	Filter Rinse Water Tank Level	Alarm	LOW LOW	1	N/A	13	STOP	Treated Water Pump PU-6D
14	AI8060	Treated Water Discharge TSS	Alarm	>=	135	PPM	14	STOP	Cyclone Waste Pump PU-4A
15							15	STOP	Cyclone Waste Pump PU-4B
16							16	STOP	Backwash Waste Pump PU-3A
17							17	STOP	Backwash Waste Pump PU-3B
18							18	STOP	Backwash Waste Pump PU-3C
19							19	STOP	Filter Rinse Water Transfer Pump PU-7A
								STOP	Filter Rinse Water Transfer Pump PU-7B
								STOP	Filter Backwash Pump PU-5A
								STOP	Filter Backwash Pump PU-5B
								STOP	Filter Backwash Pump PU-5C

"X*" indicates interlocks which vary depending on station with the greater measured process variable (station with highest flow or TSS).

NOTE: INTERLOCK MATRIX DOES NOT PROVIDE ALL PROCESS PARAMETERS. FOR DETAILED CONTROL LIMITS REFER TO THE PROCESS CONTROL NARRATIVE.



MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	JS
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	JMS
C	02/15/17	75% SUBMITTAL TO BOR	JMS


NEVADA ENVIRONMENTAL RESPONSE TRUST
 HENDERSON, NEVADA
 AP-5 POND PHASE II
 PROJECT IMPLEMENTATION
 PROCESS
 INTERLOCK MATRIX

Project No.: 200-01299-16002
 Designed By: J. COWARD
 Drawn By: J. SEIGNORET
 Checked By: D. BURGER


I-002

Copyright: Tetra Tech

2/15/2017 1:40:50 PM - NTTS\717FS1.TT.LOCAL\ERP\PROJ\ECTS\NER\01299-16015\CAD\SHEETFILES\I-200 - P&ID SHEETS.DWG - WOLFORD, LINDY



EQUIPMENT ID	AE-2010	AIT-2010	FIT-2010	LV-2010	FM-2010	FM-2010	-	-	-	-
DESCRIPTION	FEED TSS	FEED TSS	FEED FLOW	FEED FLOW CONTROL	FLOW-METER	FEED FLOW	-	-	-	-
TYPE	CUS51D	-	-	BUTTERFLY	-	-	-	-	-	-
MANUFACTURER	INSITE IG	INSITE IG	SIEMENS	DEZURIK	ROSEMOUMT	SIEMENS	-	-	-	-
SIZE	-	-	16"	16"	16"	-	-	-	-	-
FLOW RANGE	-	-	-	0-8000 GPM	-	-	-	-	-	-
LEVEL RANGE	-	-	-	-	-	-	-	-	-	-
POWER REQUIREMENTS	120 VAC	-	120 VAC	480 VAC	-	-	-	-	-	-
ANALYZER RANGE	-	0-4000 PPM	-	-	-	-	-	-	-	-
WETTED MATERIAL	-	-	-	-	-	-	-	-	-	-
ELEVATION	-	-	-	-	-	-	-	-	-	-
LOCAL CONTROLS / INDICATION	REMOTE DISPLAY	-	REMOTE DISPLAY	-	-	-	-	-	-	-
MOUNTING	-	-	-	-	-	-	-	-	-	-
CONTROL TYPE	4-20 MA	-	-	4-20 MA	-	-	-	-	-	-
NOTES	PROVIDE SUN SHIELD	-	-	-	-	-	-	-	-	-



TETRA TECH
www.tetrattech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.997.7140

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	LBW

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA


**SUNRISE MOUNTAIN
PUMP STATION FEED
P&ID**

Project No.:	200-01299-16015
Designed By:	J. GUO
Drawn By:	S. ULREY
Checked By:	S. DARIAN

I-201


Copyright: Tetra Tech

2/15/2017 1:40:35 PM - NTTS171F51.TT.LOCAL\ERP\PROJ\ECTS\NERR01299200-01299-16015\CAD\SHETSHEETS\I-202 - P&ID SHEETS.DWG - WOLFORD, LINDY



NOTES:
 1. LEVEL TRANSMITTERS CONFIGURED AS PRIMARY AND BACKUP. THE SYSTEM SHALL SWITCH TO BACKUP LEVEL TRANSMITTER EITHER MANUALLY (OPERATOR) OR WITH TRANSMITTER FAULT.
 2. CONNECTION FOR SHELF SPARE PUMP.

EQUIPMENT ID	LIT-200	TK-1A / 1B / 1C / 1D	LIT-201	PU-1A / 1B / 1C	-	-	-	-	-
DESCRIPTION	TANK LEVEL (PRIMARY)	INFLUENT TANKS	TANK LEVEL (BACKUP)	INFLUENT PUMP	-	-	-	-	-
TYPE	ULTRASONIC	-	ULTRASONIC	CENTRIFUGAL	-	-	-	-	-
MANUFACTURER	SIEMENS	-	SIEMENS	FLOWSERVE	-	-	-	-	-
SIZE	-	20,000 GAL	-	-	-	-	-	-	-
FLOW RANGE	0 - 10 FT	-	0 - 10 FT	2,300 GPM	-	-	-	-	-
LEVEL RANGE	-	-	-	-	-	-	-	-	-
POWER REQUIRMENTS	LOOP POWERED	-	LOOP POWERED	300 HP	-	-	-	-	-
ANALYZER RANGE	-	-	-	-	-	-	-	-	-
WETTED MATERIAL	PVDF	-	PVDF	-	-	-	-	-	-
ELEVATION	-	-	-	-	-	-	-	-	-
LOCAL CONTROLS / INDICATION	YES	-	YES	-	-	-	-	-	-
MOUNTING	FLANGE, 4" STILLING WELL	-	FLANGE, 4" STILLING WELL	-	-	-	-	-	-
CONTROL TYPE	4-20 MA	-	4-20 MA	-	-	-	-	-	-
NOTES	PROSONIC	-	PROSONIC	-	-	-	-	-	-



TETRA TECH

www.tetratech.com
 1489 West Warm Springs Road, Suite 110
 Henderson, NV 89014
 Phone: 702.946.6700 Fax: 702.967.7140

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	LBW

NEVADA ENVIRONMENTAL RESPONSE TRUST
 HENDERSON, NEVADA

WEIR DEWATERING TREATMENT
 SUNRISE MOUNTAIN
 PUMP STATION INFLUENT
 TANKS AND PUMPS P&ID


Project No.: 200-01299-16015
Designed By: J. GUO

Drawn By: S. ULREY
Checked By: S. DARIAN

I-202

Copyright: Tetra Tech

2/15/2017 1:14:08 PM - NTTS\717\F51.TT.LOCAL\IER\PRO-ECTS\NER\01299-16015\CAD\SH\FILE\I-300 - P&ID SHEETS.DWG - WOLFORD, LINDY



EQUIPMENT ID	AE-3010	AIT-3010	FIT-3010	LV-3010	FM-3010	-	-	-	-	-
DESCRIPTION	FEED TSS	FEED TSS	FEED FLOW	FEED FLOW CONTROL	-	-	-	-	-	-
TYPE	-	-	-	BUTTERFLY	-	-	-	-	-	-
MANUFACTURER	INSITE IG	INSITE IG	SIEMENS	DEZURIK	SIEMENS	-	-	-	-	-
SIZE	-	-	16"	16"	-	-	-	-	-	-
FLOW RANGE	-	-	-	0-8000 GPM	-	-	-	-	-	-
LEVEL RANGE	-	-	-	-	-	-	-	-	-	-
POWER REQUIREMENTS	120 VAC	-	120 VAC	480 VAC	-	-	-	-	-	-
ANALYZER RANGE	-	0-4000 PPM	-	-	-	-	-	-	-	-
WETTED MATERIAL	-	-	-	-	-	-	-	-	-	-
ELEVATION	-	-	-	-	-	-	-	-	-	-
LOCAL CONTROLS / INDICATION	REMOTE DISPLAY	-	REMOTE DISPLAY	-	-	-	-	-	-	-
MOUNTING	-	-	-	-	-	-	-	-	-	-
CONTROL TYPE	4-20 MA	-	-	4-20 MA	-	-	-	-	-	-
NOTES	PROVIDE SUN SHIELD	-	-	-	-	-	-	-	-	-

TETRA TECH

 www.tetratech.com
 1489 West Warm Springs Road, Suite 110
 Henderson, NV 89014
 Phone: 702.946.6700 Fax: 702.997.7140


MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	LBW

NEVADA ENVIRONMENTAL RESPONSE TRUST
 HENDERSON, NEVADA
**WEIR DEWATERING TREATMENT
 HISTORIC LATERAL
 PUMP STATION FEED
 P&ID**

Project No.: 200-01299-16015
 Designed By: J. GUO
 Drawn By: S. ULREY
 Checked By: S. DARIAN

I-301
 Copyright: Tetra Tech

2/15/2017 1:41:19 PM - NTTS\717\F51.TT\LOCAL\ERP\PROJ\ECTS\NER01299200-01299-16015\CAD\SH\FILES\I-300 - P&ID SHEETS.DWG - WOLFORD, LINDY



- NOTES:**
- LEVEL TRANSMITTERS CONFIGURED AS PRIMARY AND BACKUP. THE SYSTEM SHALL SWITCH TO BACKUP LEVEL TRANSMITTER EITHER MANUALLY (OPERATOR) OR WITH TRANSMITTER FAULT.
 - CONNECTION FOR SHELF SPARE PUMP.

EQUIPMENT ID	LIT-3020	TK-2A / 2B / 2C / 2D	LIT-3021	PU-2A / 2B / 2C	-	-	-	-	-	-
DESCRIPTION	TANK LEVEL (PRIMARY)	INFLUENT TANKS	TANK LEVEL (BACKUP)	INFLUENT PUMP	-	-	-	-	-	-
TYPE	ULTRASONIC	-	ULTRASONIC	CENTRIFUGAL	-	-	-	-	-	-
MANUFACTURER	SIEMENS	-	SIEMENS	FLOWERVE	-	-	-	-	-	-
SIZE	-	20,000 GAL	-	-	-	-	-	-	-	-
FLOW RANGE	0 - 10 FT	-	0 - 10 FT	2,300 GPM	-	-	-	-	-	-
LEVEL RANGE	-	-	-	-	-	-	-	-	-	-
POWER REQUIRMENTS	LOOP POWERED	-	LOOP POWERED	300 HP	-	-	-	-	-	-
ANALYZER RANGE	-	-	-	-	-	-	-	-	-	-
WETTED MATERIAL	PVDF	-	PVDF	-	-	-	-	-	-	-
ELEVATION	-	-	-	-	-	-	-	-	-	-
LOCAL CONTROLS / INDICATION	YES	-	YES	-	-	-	-	-	-	-
MOUNTING	FLANGE, 4" STILLING WELL	-	FLANGE, 4" STILLING WELL	-	-	-	-	-	-	-
CONTROL TYPE	4-20 MA	-	4-20 MA	-	-	-	-	-	-	-
NOTES	PROSONIC	-	PROSONIC	-	-	-	-	-	-	-

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA

**WEIR DEWATERING TREATMENT
HISTORIC LATERAL
PUMP STATION INFLUENT
TANKS AND PUMPS P&ID**

Copyright: Tetra Tech


Project No.: 200-01299-16015
Designed By: J. GUO
Drawn By: S. ULREY
Checked By: S. DARIAN

I-302


MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	LBW

TETRA TECH
www.tetra-tech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.967.7140

2/15/2017 1:41:50 PM - NTTS\717\F51.TT\LOCAL\ERP\PROJ\ECTS\NER\01299-16015\CAD\SHETSHEETFILES\I-401 - P&ID SHEETS.DWG - WOLFORD, LINDY



EQUIPMENT ID	AE-4010	AIT-4010	FIT-4010	V-4010	FM-4010	PE-4010	PIT-4010	-	-	-
DESCRIPTION	FEED TSS	FEED TSS	FEED FLOW	FEED CONTROL	FLOW MEASUREMENT	FEED PRESSURE	FEED PRESSURE	-	-	-
TYPE	CUS51D	LIQUILINE 442	-	BUTTERFLY	-	-	-	-	-	-
MANUFACTURER	INSITE IG	INSITE IG	SIEMENS	DEZURIK	SIEMENS	SIEMENS	SIEMENS	-	-	-
SIZE	-	-	16"	16"	-	-	-	-	-	-
FLOW RANGE	-	-	-	0-8000 GPM	-	-	-	-	-	-
LEVEL RANGE	-	-	-	-	-	-	-	-	-	-
POWER REQUIRMENTS	120 VAC	-	120 VAC	480 VAC	-	-	-	-	-	-
ANALYZER RANGE	-	0-4000 PPM	-	-	-	-	-	-	-	-
WETTED MATERIAL	-	-	-	-	-	-	-	-	-	-
ELEVATION	-	-	-	-	-	-	-	-	-	-
LOCAL CONTROLS / INDICATION	REMOTE DISPLAY	-	REMOTE DISPLAY	-	-	-	-	-	-	-
MOUNTING	-	-	-	-	-	-	-	-	-	-
CONTROL TYPE	4-20 MA	-	-	4-20 MA	-	-	-	-	-	-
NOTES	PROVIDE SUN SHIELD	-	-	-	-	-	-	-	-	-



www.tetratech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.997.7140

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	LBW

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
WEIR DEWATERING TREATMENT
CENTRAL WATER TREATMENT PLANT
FEED P&ID

Project No.: 200-01299-16015
Designed By: J. GUO
Drawn By: S. ULREY
Checked By: S. DARIAN

I-401

Copyright: Tetra Tech


2/15/2017 1:42:35 PM - N:\TTS\717\F51.TT\LOCAL\IER\PROJ\ECTS\IER\01299-16015\CAD\SHETS\FILES\I-500 - P&ID SHEETS.DWG - WOLFORD, LINDY

MAIN CONTROL PANEL
ALARM AUTO DIALER

MAIN CONTROL PANEL


MAIN CONTROL PANEL

FIELD




CYCLONE VALVE MATRIX			Chambers												
SEQUENCE	FLOW RANGE (GPM)	# CYCLONES OPERATING	Value	V-502	V-511	V-505	V-514	V-508	V-517	V-522	V-531	V-525	V-534	V-528	V-537
1	2,000 - 2,320	80		X	X										
2	2,320 - 2,755	95		X	X										
3	2,755 - 2,900	100				X	X	X	X						
4	2,900 - 3,045	105				X	X	X	X						
5	3,045 - 3,480	120								X	X	X	X	X	X
6	3,480 - 3,915	135		X	X	X	X			X	X	X	X	X	X
7	3,915 - 4,205	145				X	X	X	X						
8	4,205 - 4,785	165		X	X	X	X					X	X	X	X
9	4,785 - 5,220	180		X	X	X	X			X	X	X	X	X	X
10	5,220 - 5,800	200		X	X		X	X	X	X	X	X	X	X	X
11	5,800 - 6,525	225		X	X	X	X	X	X	X	X	X	X	X	X
12	6,525 - 6,900	240		X	X	X	X	X	X	X	X	X	X	X	X

NOTE: "X" INDICATES VALVE THAT SHOULD BE OPEN



PROVIDED BY EQUIPMENT SUPPLIER



EQUIPMENT ID	HC-1	PE-5010	PIT-5010	PE-5011	PE-5011	PIT-5012	PE-5012	-	-	-
DESCRIPTION	CYCLONE	-	-	-	-	-	-	-	-	-
TYPE	-	-	-	-	-	-	-	-	-	-
MANUFACTURER	FLSMIDTH	SIEMENS	SIEMENS	SIEMENS	SIEMENS	SIEMENS	SIEMENS	-	-	-
SIZE	-	-	-	-	-	-	-	-	-	-
FLOW RANGE	-	-	-	-	-	-	-	-	-	-
LEVEL RANGE	-	-	-	-	-	-	-	-	-	-
POWER REQUIRMENTS	-	-	-	-	-	-	-	-	-	-
ANALYZER RANGE	-	-	-	-	-	-	-	-	-	-
WETTED MATERIAL	-	-	-	-	-	-	-	-	-	-
ELEVATION	-	-	-	-	-	-	-	-	-	-
LOCAL CONTROLS / INDICATION	-	-	-	-	-	-	-	-	-	-
MOUNTING	-	-	-	-	-	-	-	-	-	-
CONTROL TYPE	-	-	-	-	-	-	-	-	-	-
NOTES	-	-	-	-	-	-	-	-	-	-

TETRA TECH
www.tetra-tech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.967.7140

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	LBW

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
WEIR DEWATERING TREATMENT
CYCLONE HC-1
P&ID

Project No.: 200-01299-16015
Designed By: J. GUO
Drawn By: S. ULREY
Checked By: S. DARIAN

I-501

Copyright Tetra Tech

2/15/2017 1:42:19 PM - NTTS171F51.TT.LOCAL\IERPROJ\ECTS\IER01299200-01299-16015\CAD\SHEETFILES\I-500 - P&ID SHEETS.DWG - WOLFORD, LINDY

MAIN CONTROL PANEL
ALARM AUTO DIALER

MAIN CONTROL PANEL


MAIN CONTROL PANEL

FIELD



CYCLONE VALVE MATRIX			Chambers									
SEQUENCE	FLOW RANGE (GPM)	# CYCLONES OPERATING	Value	1A	1B	1C	2A	2B	2C			
			V-502	V-511	V-505	V-514	V-508	V-517	V-522	V-531	V-525	V-534
1	2,000 - 2,320	80	X	X			X	X				
2	2,320 - 2,755	95	X	X			X	X				
3	2,755 - 2,900	100			X	X	X	X				
4	2,900 - 3,045	105								X	X	X
5	3,045 - 3,480	120							X	X	X	X
6	3,480 - 3,915	135	X	X	X	X			X	X		X
7	3,915 - 4,205	145					X	X			X	X
8	4,205 - 4,785	165	X	X	X	X			X	X	X	X
9	4,785 - 5,220	180	X	X	X	X			X	X	X	X
10	5,220 - 5,800	200	X	X	X	X	X	X	X	X	X	X
11	5,800 - 6,525	225	X	X	X	X	X	X	X	X	X	X
12	6,525 - 6,900	240	X	X	X	X	X	X	X	X	X	X

NOTE: "X" INDICATES VALVE THAT SHOULD BE OPEN



EQUIPMENT ID	HC-2											
DESCRIPTION	CYCLONE											
TYPE	-											
MANUFACTURER	FLSMIDTH											
SIZE	-											
FLOW RANGE	-											
LEVEL RANGE	-											
POWER REQUIREMENTS	-											
ANALYZER RANGE	-											
WETTED MATERIAL	-											
ELEVATION	-											
LOCAL CONTROLS / INDICATION	-											
MOUNTING	-											
CONTROL TYPE	-											
NOTES	-											

TETRA TECH
www.tetra-tech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.967.7140

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	LBW


NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
WEIR DEWATERING TREATMENT
CYCLONE HC-2
P&ID

Project No.:	200-01299-16015
Designed By:	J. GUO
Drawn By:	S. ULREY
Checked By:	S. DARIAN


I-502

Copyright: Tetra Tech

2/15/2017 1:43:52 PM - NTTS\717FS1.TT.LOCAL\IERPROJ.ECTS\IER01299200-01299-16015\CAD\SHETS\FILES\I-601-P&ID SHEETS.DWG - WOLFORD, LINDY



EQUIPMENT ID	MMF-1A/B	FM-6010	FIT-6010	FM-6011	FIT-6011	PI-6010	PI-6011	PI-6012	FV-6010	-
DESCRIPTION	-	-	-	-	-	-	-	-	-	-
TYPE	-	-	-	-	-	-	-	-	-	-
MANUFACTURER	WESTECH	SIEMENS	SIEMENS	SIEMENS	SIEMENS	SIEMENS	SIEMENS	SIEMENS	SIEMENS	-
SIZE	-	-	-	-	-	-	-	-	-	-
FLOW RANGE	-	-	-	-	-	-	-	-	-	-
LEVEL RANGE	-	-	-	-	-	-	-	-	-	-
POWER REQUIREMENTS	-	-	-	-	-	-	-	-	-	-
ANALYZER RANGE	-	-	-	-	-	-	-	-	-	-
WETTED MATERIAL	-	-	-	-	-	-	-	-	-	-
ELEVATION	-	-	-	-	-	-	-	-	-	-
LOCAL CONTROLS / INDICATION	-	-	-	-	-	-	-	-	-	-
MOUNTING	-	-	-	-	-	-	-	-	-	-
CONTROL TYPE	-	-	-	-	-	-	-	-	-	-
NOTES	-	-	-	-	-	-	-	-	-	-



www.tetrattech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.967.7140

MARK
DATE
DESCRIPTION
BY

A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	LBW

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
WEIR DEWATERING TREATMENT
MULTI-MEDIA FILTERS
MMF-1A/1B
P&ID



Project No.: 200-01299-16015
Designed By: J. GUO

Drawn By: S. ULREY
Checked By: S. DARIAN

I-601

Copyright: Tetra Tech

2/15/2017 1:43:33 PM - NTTS171FS1.TT.LOCAL\IERPROJ.EC\S\IER01299200-01299-16015\CAD\SHEETFILES\I-600 - P&ID SHEETS.DWG - WOLFORD, LINDY



EQUIPMENT ID	MMF-2A/B	FM-6020	FIT-6020	FM-6021	FIT-6021	FV-6020	PI-6020	PI-6021	PI-6022	-
DESCRIPTION	-	-	-	-	-	-	-	-	-	-
TYPE	-	-	-	-	-	-	-	-	-	-
MANUFACTURER	WESTECH	SIEMENS	SIEMENS	SIEMENS	SIEMENS	-	SIEMENS	SIEMENS	SIEMENS	-
SIZE	-	-	-	-	-	-	-	-	-	-
FLOW RANGE	-	-	-	-	-	-	-	-	-	-
LEVEL RANGE	-	-	-	-	-	-	-	-	-	-
POWER REQUIREMENTS	-	-	-	-	-	-	-	-	-	-
ANALYZER RANGE	-	-	-	-	-	-	-	-	-	-
WETTED MATERIAL	-	-	-	-	-	-	-	-	-	-
ELEVATION	-	-	-	-	-	-	-	-	-	-
LOCAL CONTROLS / INDICATION	-	-	-	-	-	-	-	-	-	-
MOUNTING	-	-	-	-	-	-	-	-	-	-
CONTROL TYPE	-	-	-	-	-	-	-	-	-	-
NOTES	-	-	-	-	-	-	-	-	-	-

www.tetrattech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.967.7140

BY

HCR	HCR	HCR	LBW
-----	-----	-----	-----

MARK

A	B	C
---	---	---

DATE

11/28/16	01/27/17	02/15/17
----------	----------	----------

DESCRIPTION

ISSUED FOR 60% SUBMITTAL	ISSUED FOR DRAFT 90% SUBMITTAL	75% SUBMITTAL TO BOR
--------------------------	--------------------------------	----------------------

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA

WEIR DEWATERING TREATMENT
MULTI-MEDIA FILTERS
MMF-1C/1D
P&ID

Project No.:

200-01299-16015

Designed By:

J. GUO

Drawn By:



S. ULREY

Checked By:

S. DARIAN

I-602

2/15/2017 1:43:00 PM - NTTS\717\FS1.TT.LOCAL\IER\PROJ\ECTS\NER\01299-16015\CAD\SH\FILES\I-600 - P&ID SHEETS.DWG - WOLFORD, LINDY



EQUIPMENT ID	MMF-3A/B	FM-6030	FIT-6030	FM-6031	FIT-6031	FV-6030	PI-6030	PI-6031	PI-6032	-
DESCRIPTION	-	-	-	-	-	-	-	-	-	-
TYPE	-	-	-	-	-	-	-	-	-	-
MANUFACTURER	WESTECH	SIEMENS	SIEMENS	SIEMENS	SIEMENS	-	SIEMENS	SIEMENS	SIEMENS	-
SIZE	-	-	-	-	-	-	-	-	-	-
FLOW RANGE	-	-	-	-	-	-	-	-	-	-
LEVEL RANGE	-	-	-	-	-	-	-	-	-	-
POWER REQUIREMENTS	-	-	-	-	-	-	-	-	-	-
ANALYZER RANGE	-	-	-	-	-	-	-	-	-	-
WETTED MATERIAL	-	-	-	-	-	-	-	-	-	-
ELEVATION	-	-	-	-	-	-	-	-	-	-
LOCAL CONTROLS / INDICATION	-	-	-	-	-	-	-	-	-	-
MOUNTING	-	-	-	-	-	-	-	-	-	-
CONTROL TYPE	-	-	-	-	-	-	-	-	-	-
NOTES	-	-	-	-	-	-	-	-	-	-

TETRA TECH
 www.tetra-tech.com
 1489 West Warm Springs Road, Suite 110
 Henderson, NV 89014
 Phone: 702.946.6700 Fax: 702.997.7140

MARK	DATE	DESCRIPTION	BY	HR
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR	
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR	
C	02/15/17	75% SUBMITTAL TO BOR	LBW	

NEVADA ENVIRONMENTAL RESPONSE TRUST
 HENDERSON, NEVADA

WEIR DEWATERING TREATMENT
 MULTI-MEDIA FILTERS
 MMF-1E/1F
 P&ID

Project No.:	200-01299-16015
Designed By:	J. GUO
Drawn By:	S. ULREY
Checked By:	S. DARIAN

I-603


2/15/2017 1:43:14 PM - NTTS\717FS1.TT.LOCAL\IER\PROJ.ECTS\IER\01299-16015\CAD\SHEETFILES\I-600 - P&ID SHEETS.DWG - WOLFORD, LINDY

MAIN CONTROL PANEL

FIELD



MAIN CONTROL PANEL

FIELD



ELEV. 1'-0" ABOVE
TOP OF FILTER

TO MULTI-MEDIA
FILTERS MMF-1A/B,
2A/B, 3A/B



BLOWERS
(BL-1A AND BL-1B)

EQUIPMENT ID	-	-	-	-	-	-	-	-	-	-
DESCRIPTION	-	-	-	-	-	-	-	-	-	-
TYPE	-	-	-	-	-	-	-	-	-	-
MANUFACTURER	-	-	-	-	-	-	-	-	-	-
SIZE	-	-	-	-	-	-	-	-	-	-
FLOW RANGE	-	-	-	-	-	-	-	-	-	-
LEVEL RANGE	-	-	-	-	-	-	-	-	-	-
POWER REQUIRMENTS	-	-	-	-	-	-	-	-	-	-
ANALYZER RANGE	-	-	-	-	-	-	-	-	-	-
WETTED MATERIAL	-	-	-	-	-	-	-	-	-	-
ELEVATION	-	-	-	-	-	-	-	-	-	-
LOCAL CONTROLS / INDICATION	-	-	-	-	-	-	-	-	-	-
MOUNTING	-	-	-	-	-	-	-	-	-	-
CONTROL TYPE	-	-	-	-	-	-	-	-	-	-
NOTES	-	-	-	-	-	-	-	-	-	-

TETRA TECH
www.tetratech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.997.7140

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	LBW

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA


**WEIR DEWATERING TREATMENT
MULTI-MEDIA FILTERS
AIR SCOUR BLOWER
P&ID**

Project No.: 200-01299-16015
Designed By: J. GUO
Drawn By: S. ULREY
Checked By: S. DARIAN

I-604

Copyright: Tetra Tech

2/15/2017 1:44:45 PM - NTTS\717\FS1.TT.LOCAL\IERPRO.ECTS\IER01299\200-01299-16015\CAD\SHEETFILES\I-700 - P&ID SHEETS.DWG - WOLFORD, LINDY



EQUIPMENT ID	IX-1A/2A	FM-7010	FIT-7010	V-701	PE-7010/7011	PIT-7010/7011	PI-7012/7013	AE-7010	AIT-7010	-
DESCRIPTION	-	-	-	-	-	-	-	-	-	-
TYPE	-	-	-	-	-	-	-	-	-	-
MANUFACTURER	EVOQUA	SIEMENS	SIEMENS	-	SIEMENS	SIEMENS	SIEMENS	INSITE IG	INSITE IG	-
SIZE	-	-	-	-	-	-	-	-	-	-
FLOW RANGE	-	-	-	-	-	-	-	-	-	-
LEVEL RANGE	-	-	-	-	-	-	-	-	-	-
POWER REQUIRMENTS	-	-	-	-	-	-	-	-	-	-
ANALYZER RANGE	-	-	-	-	-	-	-	-	-	-
WETTED MATERIAL	-	-	-	-	-	-	-	-	-	-
ELEVATION	-	-	-	-	-	-	-	-	-	-
LOCAL CONTROLS / INDICATION	-	-	-	-	-	-	-	-	-	-
MOUNTING	-	-	-	-	-	-	-	-	-	-
CONTROL TYPE	-	-	-	-	-	-	-	-	-	-
NOTES	-	-	-	-	-	-	-	-	-	-

TETRA TECH
 www.tetratech.com
 1489 West Warm Springs Road, Suite 110
 Henderson, NV 89014
 Phone: 702.946.6700 Fax: 702.967.7140

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	LBW

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	LBW

NEVADA ENVIRONMENTAL RESPONSE TRUST
 HENDERSON, NEVADA
**WEIR DEWATERING TREATMENT
 ION EXCHANGE
 IX-1A/2A
 P&ID**

Project No.: 200-01299-16015
 Designed By: J. GUO
 Drawn By: S. ULREY
 Checked By: S. DARIAN

I-701
 Copyright: Tetra Tech


2/15/2017 1:44:30 PM - NTTS1717FS1.TT.LOCAL\IER\PROJ\ECTS\IER\01299-16015\CAD\SHEETFILES\I-700 - P&ID SHEETS.DWG - WOLFORD, LINDY

MAIN CONTROL PANEL
ALARM AUTO DIALER

MAIN CONTROL PANEL

MAIN CONTROL PANEL

FIELD



EQUIPMENT ID	IX-1B/2B	FM-7020	FIT-7020	PE-7020/7021	PIT-7020/7021	PI-7022/7023	V-721	-	-	-
DESCRIPTION	-	-	-	-	-	-	-	-	-	-
TYPE	-	-	-	-	-	-	-	-	-	-
MANUFACTURER	EVOQUA	SIEMENS	SIEMENS	SIEMENS	SIEMENS	SIEMENS	-	-	-	-
SIZE	-	-	-	-	-	-	-	-	-	-
FLOW RANGE	-	-	-	-	-	-	-	-	-	-
LEVEL RANGE	-	-	-	-	-	-	-	-	-	-
POWER REQUIRMENTS	-	-	-	-	-	-	-	-	-	-
ANALYZER RANGE	-	-	-	-	-	-	-	-	-	-
WETTED MATERIAL	-	-	-	-	-	-	-	-	-	-
ELEVATION	-	-	-	-	-	-	-	-	-	-
LOCAL CONTROLS / INDICATION	-	-	-	-	-	-	-	-	-	-
MOUNTING	-	-	-	-	-	-	-	-	-	-
CONTROL TYPE	-	-	-	-	-	-	-	-	-	-
NOTES	-	-	-	-	-	-	-	-	-	-

TETRA TECH
www.tetratech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.967.7140


MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	LBW

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
**WEIR DEWATERING TREATMENT
ION EXCHANGE
IX-1B/2B
P&ID**

Project No.: 200-01299-16015
Designed By: J. GUO
Drawn By: S. ULREY
Checked By: S. DARIAN

I-702
Copyright: Tetra Tech

2/15/2017 1:44:15 PM - NTTS\717FS1.TT.LOCAL\ERP\PROJ\ECTS\NER01299\200-01299-16015\CAD\SHEETFILES\I-700 - P&ID SHEETS.DWG - WOLFORD, LINDY



NOTE:
1. VACUUM BREAKER COMES WITH INTEGRATE AIR RELEASE VALVE.

EQUIPMENT ID	IX-1C/2C	FM-7030	FIT-7030	V-741	PE-7030/7031	PIT-7030/7031	PI-7032/7033	AE-7010	AIT-7010	-
DESCRIPTION	-	-	-	-	-	-	-	-	-	-
TYPE	-	-	-	-	-	-	-	-	-	-
MANUFACTURER	EVOQUA	SIEMENS	SIEMENS	-	SIEMENS	SIEMENS	SIEMENS	INSITE IG	INSITE IG	-
SIZE	-	-	-	-	-	-	-	-	-	-
FLOW RANGE	-	-	-	-	-	-	-	-	-	-
LEVEL RANGE	-	-	-	-	-	-	-	-	-	-
POWER REQUIRMENTS	-	-	-	-	-	-	-	-	-	-
ANALYZER RANGE	-	-	-	-	-	-	-	-	-	-
WETTED MATERIAL	-	-	-	-	-	-	-	-	-	-
ELEVATION	-	-	-	-	-	-	-	-	-	-
LOCAL CONTROLS / INDICATION	-	-	-	-	-	-	-	-	-	-
MOUNTING	-	-	-	-	-	-	-	-	-	-
CONTROL TYPE	-	-	-	-	-	-	-	-	-	-
NOTES	-	-	-	-	-	-	-	-	-	-

TETRA TECH
www.tetra-tech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.967.7140

MARK	DATE	DESCRIPTION	BY	HR
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR	
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR	
C	02/15/17	75% SUBMITTAL TO BOR	LBW	


NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA

**WEIR DEWATERING TREATMENT
ION EXCHANGE
IX-1C/2C
P&ID**

Project No.: 200-01299-16015
Designed By: J. GUO
Drawn By: S. ULREY
Checked By: S. DARIAN

I-703
Copyright Tetra Tech

2/15/2017 1:38:48 PM - NTTS171F51.TT.LOCAL\IERPRO.ECTS\IER01299200-01299-16015\CAD\SHEETFILES\I-801-P&ID SHEETS.DWG - WOLFORD, LINDY



- NOTES:
- LEVEL TRANSMITTERS CONFIGURED AS PRIMARY AND BACKUP. THE SYSTEM SHALL SWITCH TO BACKUP LEVEL TRANSMITTER EITHER MANUALLY (OPERATOR) OR WITH TRANSMITTER FAULT.
 - VFD I/O CONNECTIONS PROVIDED VIA ETHERNET.

EQUIPMENT ID	TK-4A/B/C	TK-6	PU-6A/B/C/D	LE-8010/8011	LIT-8010/8011	LE-8012/8013	LIT-8012/8013	-	-	-
DESCRIPTION	-	-	-	-	-	-	-	-	-	-
TYPE	-	-	-	-	-	-	-	-	-	-
MANUFACTURER	-	-	FLWRSERVE	SIEMENS	SIEMENS	SIEMENS	SIEMENS	-	-	-
SIZE	-	-	-	-	-	-	-	-	-	-
FLOW RANGE	-	-	-	-	-	-	-	-	-	-
LEVEL RANGE	-	-	-	-	-	-	-	-	-	-
POWER REQUIRMENTS	-	-	-	-	-	-	-	-	-	-
ANALYZER RANGE	-	-	-	-	-	-	-	-	-	-
WETTED MATERIAL	-	-	-	-	-	-	-	-	-	-
ELEVATION	-	-	-	-	-	-	-	-	-	-
LOCAL CONTROLS / INDICATION	-	-	-	-	-	-	-	-	-	-
MOUNTING	-	-	-	-	-	-	-	-	-	-
CONTROL TYPE	-	-	-	-	-	-	-	-	-	-
NOTES	-	-	-	-	-	-	-	-	-	-

TETRA TECH

www.tetratech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.967.7140

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA

WEIR DEWATERING TREATMENT TANKS AND PUMPS P&ID


Project No.: 200-01299-16015
Designed By: J. GUO
Drawn By: S. ULREY
Checked By: S. DARIAN

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	LBW

I-801

Copyright: Tetra Tech

2/15/2017 1:38:29 PM - NTTS\717FS1.TT.LOCAL\ERP\PROJ\ECTS\NIE\01299-01299-16015\CAD\SHEETFILES\I-800 - P&ID SHEETS.DWG - WOLFORD, LINDY



NOTES:
 1. LEVEL TRANSMITTERS CONFIGURED AS PRIMARY AND BACKUP. THE SYSTEM SHALL SWITCH TO BACKUP LEVEL TRANSMITTER EITHER MANUALLY (OPERATOR) OR WITH TRANSMITTER FAULT.

EQUIPMENT ID	TK-5	MX-2A/B/C/D	FM-8020	FIT-8020	LE-8020	LIT-8020	LE-8021	LIT-8021	-	-
DESCRIPTION	-	-	-	-	-	-	-	-	-	-
TYPE	-	-	-	-	-	-	-	-	-	-
MANUFACTURER	-	-	SIEMENS	SIEMENS	SIEMENS	SIEMENS	SIEMENS	SIEMENS	-	-
SIZE	-	-	-	-	-	-	-	-	-	-
FLOW RANGE	-	-	-	-	-	-	-	-	-	-
LEVEL RANGE	-	-	-	-	-	-	-	-	-	-
POWER REQUIREMENTS	-	-	-	-	-	-	-	-	-	-
ANALYZER RANGE	-	-	-	-	-	-	-	-	-	-
WETTED MATERIAL	-	-	-	-	-	-	-	-	-	-
ELEVATION	-	-	-	-	-	-	-	-	-	-
LOCAL CONTROLS / INDICATION	-	-	-	-	-	-	-	-	-	-
MOUNTING	-	-	-	-	-	-	-	-	-	-
CONTROL TYPE	-	-	-	-	-	-	-	-	-	-
NOTES	-	-	-	-	-	-	-	-	-	-

TETRA TECH

www.tetrattech.com
 1489 West Warm Springs Road, Suite 110
 Henderson, NV 89014
 Phone: 702.946.6700 Fax: 702.967.7140

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	LBW


NEVADA ENVIRONMENTAL RESPONSE TRUST
 HENDERSON, NEVADA

WEIR DEWATERING TREATMENT
CYCLONE WASTE TANK P&ID

Project No.: 200-01299-16015
 Designed By: J. GUO
 Drawn By: S. ULREY
 Checked By: S. DARIAN

I-802

2/15/2017 1:38:07 PM - NTTS171FS1.TT.LOCAL\ERP\PROJ\ECTS\NER01299\200-01299-16015\CAD\SHEETFILES\I-800 - P&ID SHEETS.DWG - WOLFORD, LINDY



NOTES:
 1. LEVEL TRANSMITTERS CONFIGURED AS PRIMARY AND BACKUP. THE SYSTEM SHALL SWITCH TO BACKUP LEVEL TRANSMITTER EITHER MANUALLY (OPERATOR) OR WITH TRANSMITTER FAULT.

EQUIPMENT ID	TK-3A/B	MX-1A/B/C/D	MX-1E/F/G/H	LE-8030	LIT-8030	LE-8031	LIT-8031	-	-	-
DESCRIPTION	-	-	-	-	-	-	-	-	-	-
TYPE	-	-	-	-	-	-	-	-	-	-
MANUFACTURER	-	-	-	SIEMENS	SIEMENS	SIEMENS	SIEMENS	-	-	-
SIZE	-	-	-	-	-	-	-	-	-	-
FLOW RANGE	-	-	-	-	-	-	-	-	-	-
LEVEL RANGE	-	-	-	-	-	-	-	-	-	-
POWER REQUIREMENTS	-	-	-	-	-	-	-	-	-	-
ANALYZER RANGE	-	-	-	-	-	-	-	-	-	-
WETTED MATERIAL	-	-	-	-	-	-	-	-	-	-
ELEVATION	-	-	-	-	-	-	-	-	-	-
LOCAL CONTROLS / INDICATION	-	-	-	-	-	-	-	-	-	-
MOUNTING	-	-	-	-	-	-	-	-	-	-
CONTROL TYPE	-	-	-	-	-	-	-	-	-	-
NOTES	-	-	-	-	-	-	-	-	-	-

TETRA TECH

www.tetratech.com

1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.967.7140

MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	LBW

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA

WEIR DEWATERING TREATMENT

BACKWASH WASTE TANK P&ID

Project No.: 200-01299-16015
 Designed By: J. GUO
 Drawn By: S. ULREY
 Checked By: S. DARIAN

I-803

Copyright: Tetra Tech


2/15/2017 1:37:49 PM - N:\TSS\17\F51.TT.LOCAL\IWR\PROJ\ECTS\IWR\01299-16015\CAD\SHEETFILES\I-800 - P&ID SHEETS.DWG - WOLFORD, LINDY

MAIN CONTROL PANEL
ALARM AUTO DIALER

MAIN CONTROL PANEL

MAIN CONTROL PANEL

FIELD



NOTES:
 1. LEVEL TRANSMITTERS CONFIGURED AS PRIMARY AND BACKUP THE SYSTEM SHALL SWITCH TO BACKUP LEVEL TRANSMITTER EITHER MANUALLY (OPERATOR) OR WITH TRANSMITTER FAULT
 2. VFD I/O CONNECTIONS PROVIDED VIA ETHERNET.

EQUIPMENT ID	PU-4A/B	PU-3A/B/C	FM-8040	FIT-8040	FM-8045	FIT-8045	PI	-	-	-
DESCRIPTION	-	-	-	-	-	-	-	-	-	-
TYPE	-	-	-	-	-	-	-	-	-	-
MANUFACTURER	-	-	SIEMENS	SIEMENS	SIEMENS	SIEMENS	SIEMENS	-	-	-
SIZE	-	-	-	-	-	-	-	-	-	-
FLOW RANGE	-	-	-	-	-	-	-	-	-	-
LEVEL RANGE	-	-	-	-	-	-	-	-	-	-
POWER REQUIREMENTS	-	-	-	-	-	-	-	-	-	-
ANALYZER RANGE	-	-	-	-	-	-	-	-	-	-
WETTED MATERIAL	-	-	-	-	-	-	-	-	-	-
ELEVATION	-	-	-	-	-	-	-	-	-	-
LOCAL CONTROLS / INDICATION	-	-	-	-	-	-	-	-	-	-
MOUNTING	-	-	-	-	-	-	-	-	-	-
CONTROL TYPE	-	-	-	-	-	-	-	-	-	-
NOTES	-	-	-	-	-	-	-	-	-	-

TETRA TECH
 www.tetra-tech.com
 1489 West Warm Springs Road, Suite 110
 Henderson, NV 89014
 Phone: 702.946.6700 Fax: 702.967.7140


MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	LBW

NEVADA ENVIRONMENTAL RESPONSE TRUST
 HENDERSON, NEVADA
**WEIR DEWATERING TREATMENT
 CYCLONE AND
 BACKWASH WASTE
 PUMPS P&ID**

Project No.: 200-01299-16015
 Designed By: J. GUO
 Drawn By: S. ULRIAN
 Checked By: S. DARIAN

I-804
 Copyright Tetra Tech

2/15/2017 1:37:32 PM - NTTS\717FS1.TT.LOCAL\ERP\PROJ\ECTS\NER01299\200-01299-16015\CAD\SHEETFILES\I-800 - P&ID SHEETS.DWG - WOLFORD, LINDY



NOTES:
 1. LEVEL TRANSMITTERS CONFIGURED AS PRIMARY AND BACKUP. THE SYSTEM SHALL SWITCH TO BACKUP LEVEL TRANSMITTER EITHER MANUALLY (OPERATOR) OR WITH TRANSMITTER FAULT.
 2. VFD I/O CONNECTIONS PROVIDED VIA ETHERNET.

EQUIPMENT ID	PU-5A/B/C	FM-8050	FIT-8050	PI-8050-8055	-	-	-	-	-	-
DESCRIPTION	-	-	-	-	-	-	-	-	-	-
TYPE	-	-	-	-	-	-	-	-	-	-
MANUFACTURER	-	SIEMENS	SIEMENS	SIEMENS	-	-	-	-	-	-
SIZE	-	-	-	-	-	-	-	-	-	-
FLOW RANGE	-	-	-	-	-	-	-	-	-	-
LEVEL RANGE	-	-	-	-	-	-	-	-	-	-
POWER REQUIREMENTS	-	-	-	-	-	-	-	-	-	-
ANALYZER RANGE	-	-	-	-	-	-	-	-	-	-
WETTED MATERIAL	-	-	-	-	-	-	-	-	-	-
ELEVATION	-	-	-	-	-	-	-	-	-	-
LOCAL CONTROLS / INDICATION	-	-	-	-	-	-	-	-	-	-
MOUNTING	-	-	-	-	-	-	-	-	-	-
CONTROL TYPE	-	-	-	-	-	-	-	-	-	-
NOTES	-	-	-	-	-	-	-	-	-	-

TETRA TECH
 www.tetratech.com
 1489 West Warm Springs Road, Suite 110
 Henderson, NV 89014
 Phone: 702.946.6700 Fax: 702.967.7140


MARK	DATE	DESCRIPTION	BY
A	11/28/16	ISSUED FOR 60% SUBMITTAL	HCR
B	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	HCR
C	02/15/17	75% SUBMITTAL TO BOR	LBW

NEVADA ENVIRONMENTAL RESPONSE TRUST
 HENDERSON, NEVADA
 WEIR DEWATERING TREATMENT
 FILTER RINSE/
 BACKWASH PUMPS
 P&ID

Project No.: 200-01299-16015
 Designed By: J. GUO
 Drawn By: S. ULREY
 Checked By: S. DARIAN

I-805
 Copyright: Tetra Tech

2/15/2017 1:37:08 PM - NTTS\717FS1.TT.LOCAL\IERPRO.ECTS\IER01299-01299-16015\CAD\SHEETFILES\I-800 - P&ID SHEETS.DWG - WOLFORD, LINDY



NOTES:
 1. LEVEL TRANSMITTERS CONFIGURED AS PRIMARY AND BACKUP. THE SYSTEM SHALL SWITCH TO BACKUP LEVEL TRANSMITTER EITHER MANUALLY (OPERATOR) OR WITH TRANSMITTER FAULT.
 2. VFD I/O CONNECTIONS PROVIDED VIA ETHERNET.

EQUIPMENT ID	PU-7A/B	FM-8060	FIT-8060	FM-8065	FIT-8065	PI-8060-8063	-	-	-	-
DESCRIPTION	-	-	-	-	-	-	-	-	-	-
TYPE	-	-	-	-	-	-	-	-	-	-
MANUFACTURER	-	SIEMENS	SIEMENS	SIEMENS	SIEMENS	SIEMENS	-	-	-	-
SIZE	-	-	-	-	-	-	-	-	-	-
FLOW RANGE	-	-	-	-	-	-	-	-	-	-
LEVEL RANGE	-	-	-	-	-	-	-	-	-	-
POWER REQUIREMENTS	-	-	-	-	-	-	-	-	-	-
ANALYZER RANGE	-	-	-	-	-	-	-	-	-	-
WETTED MATERIAL	-	-	-	-	-	-	-	-	-	-
ELEVATION	-	-	-	-	-	-	-	-	-	-
LOCAL CONTROLS / INDICATION	-	-	-	-	-	-	-	-	-	-
MOUNTING	-	-	-	-	-	-	-	-	-	-
CONTROL TYPE	-	-	-	-	-	-	-	-	-	-
NOTES	-	-	-	-	-	-	-	-	-	-

TETRA TECH
www.tetratech.com
1489 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.967.7140

BY: HCR
 DESCRIPTION: ISSUED FOR 60% SUBMITTAL
 DATE: 11/28/16
 MARK: A
 DESCRIPTION: ISSUED FOR DRAFT 90% SUBMITTAL
 DATE: 01/27/17
 MARK: B
 DESCRIPTION: ISSUED FOR 75% SUBMITTAL TO BOR
 DATE: 02/15/17
 MARK: C



NEVADA ENVIRONMENTAL RESPONSE TRUST
 HENDERSON, NEVADA

**WEIR DEWATERING TREATMENT
 FILTER RINSE
 WATER TRANSFER PUMPS
 P&ID**

Project No.: 200-01299-16015
 Designed By: J. GUO
 Drawn By: S. ULREY
 Checked By: S. DARIAN

I-806

2/13/2017 2:43:05 PM - D:\PROJECTS\NERTL\09\CAD\FROMPROJECT\DIRECTOR\VI-902 MCP-100 WIRE DIAGRAM.DWG - SAITO, JON



www.tetrattech.com
1488 West Warm Springs Road, Suite 110
Henderson, NV 89014
Phone: 702.946.6700 Fax: 702.987.7140



MARK	DATE	DESCRIPTION	BY
A	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	JMS
B	02/15/17	75% SUBMITTAL TO BOR	JMS

NEVADA ENVIRONMENTAL RESPONSE TRUST
HENDERSON, NEVADA
WEIR DEWATERING TREATMENT
MCP-100 PANEL
WIRE DIAGRAM

Project No.: 200-01299-16015
Designed By: J. COWARD
Drawn By: T. CALZARETTA
Checked By: D. BURGER

I-902

Copyright: Tetra Tech



NOTES:

- OPERATOR INTERFACES MOUNTED ON INNER PANEL. OBJECTS SHOWN FOR CLARITY



www.tetra.tech.com
 1488 West Warm Springs Road, Suite 110
 Henderson, NV 89014
 Phone: 702.946.6700 Fax: 702.997.7140

MARK	DATE	DESCRIPTION	BY
A	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	JMS
B	02/15/17	75% SUBMITTAL TO BOR	JMS

NEVADA ENVIRONMENTAL RESPONSE TRUST
 HENDERSON, NEVADA
 WEIR DEWATERING TREATMENT
 RCP-300
 PANEL LAYOUT

Project No.: 200-01299-16015
 Designed By: J. COWARD
 Drawn By: J. SAITO
 Checked By: D. BURGER

I-920

QTY	ID	DESCRIPTION	MFG.	PART#
1	1	Enclosure, 60H x 48W x 18D, 304SS	Hoffman	A604818SSFSDN4
1	2	Back Panel	Hoffman	A60P48F1G
1	3	Air Conditioner, NEMA 4X, SS, 3000 BTU/Hr	Hoffman	CR290216G036
1	4	Panel Light, LED	Hoffman	LEDA1S35
1	5	Door Switch	Hoffman	900-MS01S0100
1	6	Operator Interface Terminal (Panel HMI)	Allen Bradley	2711P-T15C4A8
1	7	Ethernet Switch 4 copper, 2 Fiber w/ ST connectors)	N-TRON	306FX2-ST
1	8	Panel Heater (200W)	Hoffman	DAH2001A
4	9	Circuit Breaker, 15A	Square D	HDL36015
1	10	Circuit Breaker, 20A	Square D	720-QOU120
2	11	Circuit Breaker, 10A	Square D	GB2CB16
5	12	Circuit Breaker, 5A	Square D	GB2CB10
3	13	Circuit Breaker, 2A	Square D	GB2CB07
8	14	Circuit Breaker Base, 24VDC	Phoenix Contact	2801305
3	15	Circuit Breaker, 24VDC, 5A	Phoenix Contact	2800840
1	16	Din Rail (7.5 x 35 x 2000 mm)	Phoenix Contact	801733
1	17	CompactLogix PLC	Allen Bradley	1769-L18ER-BB1B
1	18	PLC Field Power Distributor	Allen Bradley	1734-FPD
5	19	Terminal Block Module	Allen Bradley	17634TB
1	20	Digital Input Module, 24VDC 8 DI	Allen Bradley	1734-IB8
1	21	Digital Output Module, 4 DO (Relay)	Allen Bradley	1734-OW4
3	22	Analog Input Module, 4 AI	Allen Bradley	1734-IE4C
1	23	Analog Output Module, 4 AO	Allen Bradley	1734-OE4C
1	24	PLC End Cap Terminator	Allen Bradley	1769-ECR
1	25	Cellular Modem	Phoenix Contact	2400428
1	26	GSM Omnidirectional Antenna	Phoenix Contact	2702273
1	27	Incoming Main Surge Suppressor	Phoenix Contact	2905228
1	28	Incoming Main Surge Suppressor	Phoenix Contact	2905228
3	29	IO Expansion Module (6 DI, 4 DO 24V)	Phoenix Contact	27201072
16	30	Analog Surge	Phoenix Contact	2838186
24	31	Digital Surge Base	Phoenix Contact	2788401
24	32	Digital Surge	Phoenix Contact	2818083
2	33	24 VDC Power Supply	Sola	SDN-5-24-100P
1	34	Receptacle-Single DIN mount for UPS	Phoenix Contact	2963860
1	35	Receptacle-Dual DIN Mount GFCI 15A	Phoenix Contact	5600462
2	36	Control Relay, 120VAC, 2-Pole, Push-to-Test	Phoenix Contact	2903332
18	37	Control Relay, 24VDC, 2-Pole, Push-to-Test	Phoenix Contact	2903342
1	38	UPS, 850VA	SOLA	SDU 850
1	39	Ground Bar	Square D	PK5GTA
1	40	Multipvariable Analyzer & Controller	Endress + Hauser	CM442
1	41	Side Mount Exhaust Fan	Schneider Electric	NSYCVF165M115PF
1	42	Pilot Light, White	800H-QRTH2W	ALLEN BRADLEY
1	43	Alarm Beacon, Red	855F-SBSC20B24C1Y4	ALLEN BRADLEY
1	44	Selector Switch, 3 Positoin	800H-HR2A	ALLEN BRADLEY
1	45	RELAY SOCKET	MAGNOCRAFT	70-788EL11-1
1	46	POWER RELAY, PDPT, 30A, 120VAC COIL, UL RECOGNIZED	MAGNECRAFT	300XBXC1-120A
1	47	Timer Relay	Phoenix Contact	2905813
1	48	Circuit Breaker 6A	Square D	GB2CB12
3	49	Circuit Breaker, 24VDC, 2A	Phenix Contact	2800837
2	50	Circuit Breaker, 24VDC, 3A	Phoenix Contact	2800838
1	51	Radio Modem	Phoenix Contact	2900016
1	52	Antenna Cable Adapter	Phoenix Contact	2885207
1	53	Antenna Surge Suppressor	Phoenix Contact	2803166
1	54	Antenna Cable	Phoenix Contact	5606125



www.tetra.tech.com
 1485 West Warm Springs Road, Suite 110
 Henderson, NV 89014
 Phone: 702.946.6700 Fax: 702.997.7140

MARK	DATE	DESCRIPTION	BY
A	01/27/17	ISSUED FOR DRAFT 90% SUBMITTAL	JMS
B	02/15/17	75% SUBMITTAL TO BOR	JMS

NEVADA ENVIRONMENTAL RESPONSE TRUST
 HENDERSON, NEVADA
 WEIR DEWATERING TREATMENT
 RCP-300
 BILL OF MATERIALS

Project No.: 200-01299-16015
 Designed By: J. COWARD
 Drawn By: J. SAITO
 Checked By: D. BURGER

I-921

